CONTRACT NO: HK/2015/01

WANCHAI DEVELOPMENT PHASE II AND CENTRAL WANCHAI BYPASS SAMPLING, FIELD MEASUREMENT AND TESTING WORKS (STAGE 3)

ENVIRONMENTAL PERMIT NO. EP-356/2009, FURTHER EVIRONMENTAL PERMIT NOS. FEP-02/356/2009, FEP-03/356/2009, FEP-04/356/2009 , FEP-06/356/2009, FEP-07/356/2009 AND FEP-08/356/2009

MONTHLY ENVIRONMENTAL MONITORING & AUDIT REPORT

- OCTOBER 2017 -

CLIENTS:

Civil Engineering and Development Department

and

Highways Department

PREPARED BY:

Lam Geotechnics Limited

11/F Centre Point
181-185 Gloucester Road,
Wanchai, H.K.

Telephone: (852) 2882-3939
Facsimile: (852) 2882-3331
E-mail: info@lamenviro.com
Website: http://www.lamenviro.com

CERTIFIED BY:



Raymond Dai
Environmental Team Leader

DATE:

9 November 2017

RAMBOLL ENVIRON

Ref.: AACWBIECEM00_0_9914L.17

9 November 2017

AECOM Asia Company Limited
Engineer's Representative's Office
25 Hung Hing Road,
Causeway Bay,
Hong Kong

By Post and Fax (3912 3010)

Attention: Mr. Peter Poon

Dear Mr. Poon,

Re: Contract No. HK/2015/01
Wan Chai Development Phase II - Central-Wan Chai Bypass
Sampling, Field Measurement and Testing Works (Stage 3)

Monthly Environmental Monitoring and Audit Report (October 2017) for EP-356/2009, FEP-02/356/2009, FEP-03/356/2009, FEP-04/356/2009, FEP-06/356/2009, FEP-07/356/2009 and FEP-08/356/2009

Reference is made to the Environmental Team's submission of the captioned Monthly Environmental Monitoring and Audit (EM&A) Report for October 2017 received by e-mail on 9 November 2017 for our review and comment.

Please be informed that we have no adverse comment on the captioned submission. We write to verify the captioned submission in accordance with Condition 3.4 in the captioned Environmental Permits.

Thank you very much for your kind attention and please do not hesitate to contact the undersigned should you have any queries.

Yours sincerely,

David Yeung
Independent Environmental Checker

Q:\Projects\AACWBIECEM00\Corr\AACWBIECEM00_0_9914L.17.docx

Ramboll Environ Hong Kong Limited 英環香港有限公司
21/F, BEA Harbour View Centre, 56 Gloucester Road, Wan Chai, Hong Kong Tel: 852.3465 2888 Fax: 852.3465 2899
www.Ramboll-Environ.com

Encl.

c.c.

HyD	Attn: Mr. Tony Cheung	by fax: 2714 5289
CEDD	Attn: Mr. L K Tsang	by fax: 2577 5040
AECOM	Attn: Mr. Frankie Fan	by fax: 2691 2649
AECOM	Attn: Mr. Conrad Ng	by fax: 2691 2649
Lam	Attn: Mr. Raymond Dai	by fax: 2882 3331

TABLE OF CONTENTS

1 INTRODUCTION 9

1.1 Scope of the Report 9
1.2 Structure of the Report 9

2 PROJECT BACKGROUND 11

2.1 Background 11
2.2 Scope of the Project and Site Description 11
2.3 Division of the Project Responsibility 12
2.4 Project Organization and Contact Personnel 13

3 STATUS OF REGULATORY COMPLIANCE 17

3.1 Status of Environmental Licensing and Permitting under the Project 17

4 MONITORING REQUIREMENTS 27

4.1 Noise Monitoring 27
4.2 Air Monitoring 28
4.3 Water Quality Monitoring 31

5. MONITORING RESULTS 36

5.1 Noise Monitoring Results 36
5.2 Air Monitoring Results 39
5.3 Water quality monitoring Results 41
5.4 Waste Monitoring Results 47

6. COMPLIANCE AUDIT 52

6.1 Noise Monitoring 52
6.2 Air Monitoring 52
6.3 Water Quality Monitoring 53
6.4 Review of the Reasons for and the Implications of Non-compliance 55
6.5 Summary of action taken in the event of and follow-up on non-compliance 55

7. CUMULATIVE CONSTRUCTION IMPACT DUE TO THE CONCURRENT PROJECTS 57

8. ENVIRONMENTAL SITE AUDIT 58

9. COMPLAINTS, NOTIFICATION OF SUMMONS AND PROSECUTION 60

10. CONCLUSION 61

LIST OF TABLES

Table I Summary of Water Quality Monitoring Exceedances in Reporting Month
Table II Summary of Enhanced Dissolved Oxygen Monitoring Exceedances in Reporting Month
Table 2.1 Schedule 2 Designated Projects under this Project
Table 2.2 Details of Individual Contracts under the Project
Table 2.3 Contact Details of Key Personnel
Table 3.1 Summary of the current status on licences and/or permits on environmental protection pertinent to the Project
Table 3.2 Cumulative Summary of Valid Licences and Permits under Contract no. HK/2009/01
Table 3.3 Summary of submission status under FEP-02/356/2009 Condition
Table 3.4 Cumulative Summary of Valid Licences and Permits under Contract no. HK/2009/02
Table 3.5 Summary of submission status under FEP-03/356/2009 Condition
Table 3.6 Cumulative Summary of Valid Licences and Permits under Contract no. HY/2009/15
Table 3.7 Summary of submission status under FEP-04/356/2009 Condition
Table 3.8 Cumulative Summary of Valid Licences and Permits under Contract no. HY/2009/19
Table 3.9 ***Cumulative Summary of Valid Licences and Permits under Contract no. HK/2012/08***
Table 3.10 ***Summary of submission status under EP-356/2009 & FEP-06/356/2009 Condition***
Table 3.11 ***Cumulative Summary of Valid Licences and Permits under Contract no. HY/2010/08***
Table 3.12 ***Summary of submission status under EP-356/2009 and FEP-07/356/2009 Condition***
Table 4.1 Noise Monitoring Station
Table 4.2 Air Monitoring Station
Table 4.3 Marine Water Quality Stations for Water Quality Monitoring
Table 4.4 Marine Water Quality Monitoring Frequency and Parameters
Table 4.5 Marine Water Quality Stations for Enhanced Water Quality Monitoring
Table 5.1 Noise Monitoring Station for Contract nos. HK/2009/01, HK/2009/02
Table 5.2 Noise Monitoring Station for Contract no. HY/2009/15
Table 5.3 Noise Monitoring Station for Contract no. HY/2009/19
Table 5.4 ***Noise Monitoring Station for Contract no. HY/2010/08***
Table 5.5 ***Air Monitoring Station for Contract no. HK/2009/01***
Table 5.6 Air Monitoring Station for Contract no. HK/2009/02
Table 5.7 Air Monitoring Station for Contract no. HY/2009/15
Table 5.8 Air Monitoring Stations for Contract no. HY/2009/19
Table 5.9 ***Air Monitoring Stations for Contract no. HK/2012/08***
Table 5.10 ***Air Monitoring Stations for Contract no. HY/2010/08***
Table 5.11 ***Water quality monitoringStations for contracts with respect to remaining DP3 work areas after the completion of DP5 & DP6 in 2012 and intake diversion in 2013***
Table 5.12 Water quality monitoringStations for Contract no. HK/2009/01
Table 5.13 Water quality monitoringStations for Contract no. HK/2009/02
Table 5.14 ***Water quality monitoringStations for Contract no. HK/2012/08***
Table 5.15 ***Water quality monitoring Station for Contract no. HY/2010/08***
Table 5.16 ***Enhance Dissolved Oxygen Monitoring Stations for Contract no. HY/2010/08***
Table 5.17 ***Details of Waste Disposal for Contract no. HK/2009/01***
Table 5.18 ***Details of Waste Disposal for Contract no. HK/2009/02***
Table 5.19 Details of Waste Disposal for Contract no. HY/2009/15
Table 5.20 Details of Waste Disposal for Contract no. HY/2009/19
Table 5.21 Details of Waste Disposal for Contract no. HK/2012/08
Table 5.22 Details of Waste Disposal for Contract no. HY/2010/08
Table 8.2 Summary of Environmental Inspections for Contract no. HK/2009/02
Table 8.5 Summary of Environmental Inspections for Contract no. HK/2012/08
Table 8.6 Summary of Environmental Inspections for Contract no. HY/2010/08
Table 9.1 Cumulative Statistics on Complaints
Table 9.2 Cumulative Statistics on Successful Prosecutions
Table 10.1 Construction Activities and Recommended Mitigation Measures in Coming Reporting Month

LIST OF FIGURES

Figure 2.1 Project Layout
Figure 2.2 Project Organization Chart
Figure 4.1 Locations of Environmental Monitoring Stations

LIST OF APPENDICES

Appendix 3.1 Environmental Mitigation Implementation Schedule
Appendix 4.1 Action and Limit Level
Appendix 4.2 Copies of Calibration Certificates
Appendix 5.1 Monitoring Schedule for Reporting Month and Coming month
Appendix 5.2 Noise Monitoring Results and Graphical Presentations
Appendix 5.3 Air Quality Monitoring Results and Graphical Presentations
Appendix 5.4 Water Quality Monitoring Results and Graphical Presentations
Appendix 6.1 Event Action Plans
Appendix 6.2 Summary for Notification of Exceedance
Appendix 9.1 Complaint Log
Appendix 10.1 Construction Programme of Individual Contracts

EXECUTIVE SUMMARY

i. This is the Environmental Monitoring and Audit (EM&A) Monthly Report – October 2017 for the Project of Wan Chai Development Phase II and Central-Wanchai Bypass under Environmental Permit no. EP-356/2009 and Further Environmental permit nos. FEP-02/356/2009, FEP-03/356/2009, FEP-04/356/2009, FEP-06/356/2009, FEP-07/356/2009 and FEP-08/356/2009. This report presents the environmental monitoring findings and information recorded during the period of 27th September 2017 to 26th October 2017. The cut-off date of reporting is at 26th of each reporting month.

Construction Activities for the Reported Period

ii. During this reporting period, the major work activities for Contract no. HK/2009/01 included:
- Nil

iii. During this reporting period, the major work activities for Contract no. HK/2009/02 included:
- Nil

iv. During this reporting period, the major work activities for Contract no. HY/2009/15 included:
- Nil

v. During this reporting period, the major work activities for Contract no. HY/2009/19 included:
- Nil

vi. During this reporting period, the major work activities for Contract no. HK/2012/08 included:
- Construction of Box 1 unit and backfilling

vii. During this reporting period, the major work activities for Contract no. HY/2010/08.
- Diversion pipe maintenance
- Diaphragm Wall Removal Works
- Removal of reclamation at TS3E and TS3W

Noise Monitoring

viii. With respect to the shift in major construction site portions at Wan Chai North, the noise monitoring station M1a – Harbour Sports Centre was finely adjusted from East of Harbour Road Sports Centre to West of Harbour Road Sports Centre on 21 June 2016.

ix. With respect to the demolition of Ex-Harbour Road Sports Centre, the respective noise monitoring station M1a – Harbour Road Sports Centre were finely adjusted on 16 and 25 May 2017 and thereafter to the Footbridge for Harbour Road Sports for noise monitoring.

x. No action and limit level exceedances was recorded in this reporting month.

xi. Noise monitoring during daytime and restricted hour were conducted at the stations M1a, M2b, M3a, M4b, M5b and M6 on a weekly basis in the reporting month.

Air Quality Monitoring

xii. Due to electricity interruption, the TSP monitoring in the reporting month are rescheduled as follow:
24hr TSP monitoring at CMA5b was rescheduled from 19 Oct 2017 to 20 Oct 2017.

xiii. One 1hr TSP action level exceedance was recorded at CMA5b – Pedestrian Plaza on 26 October 2017 in the reporting month and the exceedance was concluded as non-Project related.

xiv. One 1hr TSP limit level exceedance was recorded at CMA1b – Harbour Grand Hotel Boundary Wall on 26 October 2017 in the reporting month and the exceedance was concluded as non-Project related.

xv. With respect to the proposed demolition of the Oil Street Site Office, the respective air quality monitoring station CMA1b – Oil Street Site Office was finely adjusted from the Oil Street Site Office to Harbour Grand Hotel Boundary Wall from 05 June 2017 onwards.

xvi. With respect to the proposed demolition of eastern podium of Oil Street Site Office, the respective air quality monitoring station CMA1b – Oil Street Site Office was finely adjusted from East podium of the Oil Street Site Office to the West podium of the Oil Street Site Office on 21 December 2016.

xvii. 1-hour and 24-hour Total Suspended Particulates (TSP) monitoring were conducted at CMA1b – Oil Street Site Office; CMA2a – Causeway Bay Community Center; CMA3a – CWB PRE Site Office Area; CMA4a – Society for the Prevention of Cruelty to Animals; CMA5b – Pedestrian Plaza; CMA6a – WDII PRE Site Office in the reporting month.

Water Quality Monitoring

xviii. Action and Limit level of water quality monitoring was transited from wet season to dry season from 1 October 2017.

xix. Water quality monitoring station C7 and Enhance DO monitoring station C6 shall be associated with Contract HY/2010/08, upon confirmation of marine construction works completion under Contract HY/2009/15 at CBTS area and Ex-PCWA area since 19 June 2017.

xx. Referring to CWB RSS confirmation on the completion of marine construction activities within the Ex-PCWA area and the completion of the post construction water quality monitoring, the respective Enhance DO Monitoring within Ex-PCWA for monitoring station Ex-PCWA SE and Ex-PCWA SW was temporarily suspended since 07 March 2017 ebb tide onwards.

xxi. With respect to the reinstatement of the silt screen system for Cooling Water Intakes P7, P8, P9 and WSD Water Intake RW21, the respective water quality monitoring was reverted to the previous monitoring location for Water Quality Monitoring Station RW21-P789 from water quality stations RW21-P789 East (RW21-P789E) and RW21-P789 West (RW21-P789W) from 25 January 2017 onwards.

xxii. With respect to the removal of silt screen at WQM station RW21-P789 on 26 November 2016, the respective water quality monitoring at RW21-P789 was adjusted to RW21-P789E and RW21-P789W since 28 November 2016 ebb-tide.

xxiii. With respect to the temporarily suspension of marine construction works at WCR3 Area by Contract HK/2009/02, the installed silt screen for intake group (P7, P8, P9 and WSD21) was removed on 26 November 2016.

xxiv. As advised by the Contractor of HK/2009/01, all silt screen remains removal works at P1, P3, P4, P5 and C1 water quality monitoring stations were completed on 8 May 2016.

xxv. With respect to the marine works undertaken at WCR3 by Contract HK/2009/02, the respective water quality monitoring station C1 associated with Contract HK/2009/01 was updated as in association with Contract HK/2009/01 and Contract HK/2009/02.

xxvi. With respect to the marine works undertaken at CBTS by Contract HY/2010/08, the respective water quality monitoring station C7 associated with Contract HY/2009/15 was updated as in association with Contract HY/2009/15 and Contract HY/2010/08.

xxvii. With respect to the marine works undertaken at HKCEC2 by Contract HK/2012/08, the respective water quality monitoring station WSD19, P1, P3, P4, and P5 were associated with Contract HK/2012/08.

Table I Summary of Water Quality Monitoring Exceedances in Reporting Month

Contract no.	Water quality monitoring Station	Mid-flood						Mid-ebb					
		DO		Turbidity		SS		DO		Turbidity		SS	
		AL	LL	AL	LL	AL	LL	AL	LL	AL	LL	AL	LL
HK/2009/01 & HK/2009/02	C1	0	0	2	7	0	0	0	0	1	0	0	0
HK/2012/08	WSD19	1	0	1	6	0	3	0	0	3	4	2	1
	P1	0	0	1	2	0	0	0	0	0	0	0	0
	P3	0	0	2	3	0	0	0	0	0	0	0	0
	P4	0	0	2	6	2	0	0	0	1	1	0	0
	P5	0	0	3	5	0	0	0	0	1	1	0	0
HK/2009/02	RW21-P789	0	0	1	4	0	1	1	0	2	2	0	0
HY/2009/15 & HY/2010/08	C7	0	0	1	2	0	1	0	0	1	1	0	0
Total		1	0	13	35	2	5	1	0	9	9	2	1

Remarks: -
- The cessation of seawater intake operation for C6 was confirmed on 17 May 2011 and the water quality monitoring at C6 was then terminated since 17 May 2011.
- 4-week post construction water quality monitoring at WSD9, WSD10, WSD15 and WSD17 were completed on 6 Feb 2012 and the water quality monitoring at WSD 10 and WSD15 were temporary suspended since 8 Feb 2012, and WSD9 and WSD17 was implemented with respect to HK/2009/02 from 8 Feb 2012 onwards.
- C8 and C9 were implemented with respect to HY/2009/19 from 28 Jan 2012.
- C8 & C9 were temporary suspended since 4 March 2013.
- WSD7 and WSD20 water quality monitoring were temporarily suspended from 27 Apr 2012.
- C2, C3 C4e and C4w water quality monitoring station was temporarily suspended since 22 Apr 2013
- P1, P3, P4 and P5 were commenced since 24 Apr 2013
- C5e and C5w water quality monitoring station was temporarily suspended since 29 Jul 2013.
- WSD21 water quality monitoring station was temporarily suspended since 12 Mar 2014
- WSD9 and WSD17 water quality monitoring station was temporarily suspended since 8 Sep 2014 flood tide.
- The water quality monitoring station C1 shall be associated with Contract No. HK/2009/02 upon commencement of marine works under DP3 at WCR3 area.

- The water quality monitoring station RW21-P789 was adjusted to RW21-P789E and RW21-P789W since 28 November 2016 ebb-tide.
- The water quality monitoring was reverted to previous monitoring station RW21-P789 from PW21-P789E and RW21-P789W from 25 January 2017 onwards.

xxviii. There were 2 action level of DO exceedances, 22 action level and 44 limit level of turbidity exceedances and 4 action level and 6 limit level of suspended solid exceedances were recorded in this reporting month.

xxix. Investigation found that 2 action and 3 limit level of turbidity exceedance and 1 limit level of suspended solid exceedance recorded at monitoring station C7 on 7, 9 and 25 October 2017 were related to Project Works under HY/2010/08.

xxx. Investigation found that the 2 action level of DO exceedances, 20 action level and 41 limit level of turbidity exceedances and 3 action level and 6 limit level of suspended solid exceedances recorded in this reporting month were not related to Project works.

xxxi. The details of the recorded exceedance can be referred to ***Section 6.4***.

xxxii. Enhanced DO monitoring at 3 monitoring stations in Causeway Bay Typhoon Shelter and Ex-Public Cargo Works Area was conducted three days per week during the reporting period. The action and limit level exceedances of water quality monitoring are summarized in ***Table II***.

Table II Summary of Enhanced Dissolved Oxygen Monitoring Exceedances in Reporting Month

Contract no.	Water quality monitoring Station	Mid-flood		Mid-ebb	
		DO		DO	
		AL	LL	AL	LL
HY/2009/15 & HY/2010/08	C6	0	0	0	0
Total		0	0	0	0

Remarks:

1. Enhanced DO monitoring at Windsor House Cooling (Station Ref: C7) was temporarily suspended since 22 October 2014 with respect to the formation of temporary reclamation zone TS3 and to be resumed upon removal of the respective temporary reclamation zone.
2. Enhanced DO monitoring at Monitoring station Ex-WPCWA SE was temporarily suspended from 31 August 2015 with respect to seawall reinstatement works and formation of active works area. The Enhance DO monitoring at Ex-WPCWA SE was resumed on 11 May 2016 due to completed section of seawall reinstatement works at Ex-PCWA.

xxxiii. No action or limit level exceedance for enhanced dissolved oxygen monitoring recorded in this reporting month.

Complaints, Notifications of Summons and Successful Prosecutions

xxxiv. There was no environmental complaint received in this reporting month.

Site Inspections and Audit

xxxv. The Environmental Team (ET) conducted weekly site inspections for Contract nos. HK/2009/01, HK/2009/02, HY/2009/15, HY/2009/19, HK/2012/08 and HY/2010/08 under EP no. EP-356/2009 in the reporting month. Major observations and recommendations made during the audit sessions were rectified by the Contractors. No non-conformance was identified during the site inspections.

Future Key Issues

xxxvi. In coming reporting month, the principal work activities of individual contracts are anticipated as follows:

Contract no. HK/2009/01 – Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

- Nil

Contract no. HK/2009/02 – Wan Chai Development Phase II – Central – Wan Chai Bypass at Wan Chai East

- Nil

Contract no. HY/2009/15 – Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)

- Nil

Contract no. HY/2009/19- Wan Chai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

- Nil

Contract no. HK/2012/08 – Wan Chai Development Phase II – Central- Wan Chai Bypass at Wan Chai West

- Construction of Box 1 unit and backfilling

Contract no. HY/2010/08 –Central - Wan Chai Bypass (CWB) –Tunnel (Slip Road 8)

- Diversion pipe maintenance
- Diaphragm Wall Removal works
- Removal of reclamation at TS3E and TS3W

1 Introduction

1.1 Scope of the Report

1.1.1. Lam Geotechnics Limited (LGL) has been appointed to work as the Environmental Team (ET) under Environmental Permit no. EP-356/2009 and Further Environmental permit nos. FEP-02/356/2009, FEP-03/356/2009, FEP-04/356/2009, FEP-06/356/2009, FEP-07/356/2009 and FEP-08/356/2009 to implement the Environmental Monitoring and Audit (EM&A) programme as stipulated in the EM&A Manual of the approved Environmental Impact Assessment (EIA) Report for Wan Chai Development phase II and Central-Wan Chai Bypass (Register No.: AEIAR-125/2008) and in the EM&A Manual of the approved EIA Report for Central-Wan Chai Bypass and Island Eastern Corridor Link (Register No. AEIAR-041/2001).

1.1.2. This report presents the environmental monitoring and auditing work carried out in accordance to the Section 10.3 of EM&A Manual and "*Environmental Monitoring and Audit Requirements"* under Particular Specification Section 27.

1.1.3. This report documents the finding of EM&A works for Environmental Permit no. EP-356/2009, Further Environmental Permit no. FEP-02/356/2009, FEP-03/356/2009, FEP-04/356/2009, FEP-06/356/2009, FEP-07/356/2009 and FEP-08/356/2009 during the period of 27th September 2017 to 26th October 2017. The cut-off date of reporting is at 26th of each reporting month.

1.2 Structure of the Report

Section 1 ***Introduction*** – details the scope and structure of the report.

Section 2 ***Project Background*** – summarizes background and scope of the project, site description, project organization and contact details of key personnel during the reporting period.

Section 3 ***Status of Regulatory Compliance*** – summarizes the status of valid Environmental Permits / Licenses during the reporting period.

Section 4 ***Monitoring Requirements*** – summarizes all monitoring parameters, monitoring methodology and equipment, monitoring locations, monitoring frequency, criteria and respective event and action plan and monitoring programmes.

Section 5 ***Monitoring Results*** – summarizes the monitoring results obtained in the reporting period.

Section 6 ***Compliance Audit*** – summarizes the auditing of monitoring results, all exceedances environmental parameters.

Section 7 ***Cumulative Construction Impact due to the Concurrent Projects*** – summarizes the relevant cumulative construction impact due to the concurrent

activities of the concurrent Projects.

Section 8 **Environmental Site Audit** – summarizes the findings of weekly site inspections undertaken within the reporting period, with a review of any relevant follow-up actions within the reporting period.

Section 9 ***Complaints, Notification of summons and Prosecution*** – summarizes the cumulative statistics on complaints, notification of summons and prosecution

Section 10 ***Conclusion***

2 Project Background

2.1 Background

2.1.1. "Wan Chai Development phase II and Central-Wan Chai Bypass" and "Central-Wan Chai Bypass and Island Eastern Corridor Link" (hereafter called "the Project") are Designed Project (DP) under the Environmental Impact Assessment Ordinance (Cap. 499) (EIAO). The Environmental Impact Assessment (EIA) Reports for Central-Wan Chai Bypass and Island Eastern Corridor Link (Register No. AEIAR-041/2001) and Wan Chai Development phase II and Central-Wan Chai Bypass (Register No.: AEIAR-125/2008) have been approved on 31 August 2001 and 11 December 2008 respectively.

2.1.2. The key purpose of Wan Chai Development Phase II (WDII) is to provide land at Wan Chai North and North Point for construction of the Central-Wan Chai Bypass and Island Eastern Corridor Link (CWB). Land formed under the project will be developed as a world-class waterfront promenade joining that at the new Central waterfront for public enjoyment.

2.1.3. There is a compelling and present need for the CWB to provide relief to the very congested east-west Connaught Road Central/Harcourt Road / Gloucester Road Corridor (the Corridor) which is currently operating beyond its capacity. The CWB will provide relief to the existing congestion along the Corridor and cater for the anticipated growth of traffic on Hong Kong Island. Without the CWB and its access roads, there will not be sufficient capacity to serve the heavy traffic demands at both strategic and local levels.

2.2 Scope of the Project and Site Description

2.2.1. The Project is located mainly in Wan Chai North, Causeway Bay and North Point, and is demarcated by Gloucester Road and Victoria Park Road to the south, Fenwick Pier Street to the west and Tong Shui Road Interchange to the east, as shown in ***Figure 2.1***.

2.2.2. The study area encompasses existing developments along the Wan Chai, Causeway Bay and North Point shorelines. Major land uses include the Hong Kong Convention & Exhibition Centre (HKCEC) Extension, the Wan Chai Ferry Pier, the ex-Wan Chai Public Cargo Working Area (ex-PCWA), the Royal Hong Kong Yacht Club (RHKYC), the Police Officers' Club, the Causeway Bay Typhoon Shelter (CBTS) and commercial and residential developments.

2.2.3. The scope of the Project comprises:

- Land formation for key transport infrastructure and facilities, including the Trunk Road (i.e. CWB) and the associated slip roads for connection to the Trunk Road and for through traffic from Central to Wan Chai and Causeway Bay. The land formed for the above transport infrastructure will provide opportunities for the development of an attractive waterfront promenade for the enjoyment of the public
- Reprovisioning / protection of the existing facilities and structures affected by the land formation works mentioned above
- Extension, modification, reprovisioning or protection of existing storm water drainage outfalls, sewerage outfalls and watermains affected by the revised land use and land formation works mentioned above

- Upgrading of hinterland storm water drainage system and sewerage system, which would be rendered insufficient by the land formation works mentioned above
- Provision of the ground level roads, flyovers, footbridges, necessary transport facilities and the associated utility services
- Construction of the new waterfront promenade, landscape works and the associated utility services
- The Trunk Road (i.e. CWB) within the study area and the associated slip roads for connection to the Trunk Road.

2.2.4. The project also contains various Schedule 2 DPs that, under the EIAO, require Environmental Permits (Eps) to be granted by the DEP before they may be either constructed or operated. ***Table 2.1*** summarises the five individual DPs under this Project. ***Figure 2.1*** shows the locations of these Schedule 2 DPs.

Table 2.1 Schedule 2 Designated Projects under this Project

Item	Designated Project	EIAO Reference	Reason for inclusion
DP1	Central-Wanchai Bypass (CWB) including its road tunnel and slip roads	Schedule 2, Part I, A.1 and A.7	Trunk road and road tunnel more than 800 m in length
DP2	Road P2 and other roads which are classified as primary/district distributor roads	Schedule 2, Part I, A.1	Primary / district distributor roads
DP3	Reclamation works including associated dredging works	Schedule 2, Part I, C.1 and C.12	Reclamation more than 5 ha in size and a dredging operation less than 100 m from a seawater intake point
DP5	Wan Chai East Sewage Outfall	Schedule 2, Part I, F.5 and F.6	Submarine sewage pipelines with a total diameter more than 1,200 mm and include a submarine sewage outfall
DP6	Dredging for the Cross-harbour Water Mains from Wan Chai to Tsim Sha Tsui	Schedule 2, Part I, C.12	A dredging operation less than 100 m from a seawater intake point

2.3 Division of the Project Responsibility

2.3.1. Due to the multi-contract nature of the Project, there are a number of contracts sub-dividing the whole works area into different work areas to be commenced. Contractors of individual contracts will be required by the EP holder to apply Further Environmental Permits (FEP) such that the impact monitoring stations are sub-divided accordingly to facilitate the implementation of EM&A programme and to streamline the EM&A reporting for individual FEP holders correspondingly.

2.3.2. The details of individual contracts are summarized in ***Table 2.2***.

Table 2.2 Details of Individual Contracts under the Project

Contract No.	Contract Title	Associated DP(s)	Construction Commencement Date
HK/2009/01	Wan Chai Development Phase II – Central –Wanchai Bypass at Hong Kong Convention and Exhibition Centre	DP3, DP6	23 July 2010
		DP1, DP2	25 August 2011
HK/2009/02	Wan Chai Development Phase II – Central – Wan Chai Bypass at WanChai East	DP3, DP5	5 July 2010
		DP1	26 April 2011
HY/2009/11	Wan Chai Development Phase II and Central – Wan Chai Bypass – North Point Reclamation	DP3	17 March 2010 (Completed)
HY/2009/15	Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)	DP3	10 November 2010
		DP1	13 July 2011
HK/2010/06	Wan Chai Development Phase II-Central-Wan Chai Bypass over MTR Tsuen Wan Line	DP3	22 March 2011 (Completed)
04/HY/2006	Reconstruction of Bus Terminus near Man Yiu Street and Man Kwong Street	DP1	September 2010 (Completed)
HY/2009/17	Central – Wan Chai Bypass (CWB) at FEHD Whitfield Depot – Advanced piling works.	DP1	5 October 2010 (Completed)
HY/2009/18	Central – Wan Chai Bypass (CWB) – Central Interchange	DP1	21 April 2011
HY/2009/19	Central – Wanchai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link	DP1	24 March 2011
HK/2012/08	Wan Chai Development Phase II Central- Wan Chai Bypass at Wan Chai West	DP1,DP2, DP3	10 March 2014
HY/2010/08	Central- Wanchai Bypass Tunnel – Tunnel (Slip Road 8)	DP1, DP2, DP3	21 March 2013
HY/2011/08	Central-Wan Chai Bypass (CWB) – Tunnel Buildings, Systems and Fittings, and Works Associated with Tunnel Commissioning	DP1	8 October 2014

2.4 Project Organization and Contact Personnel

2.4.1. Civil Engineering and Development Department and Highways Department are the overall project controllers for the Wan Chai Development Phase II and Central-Wan Chai Bypass respectively. For the construction phase of the Project, Project Engineer, Contractor(s), Environmental Team and Independent Environmental Checker are appointed to manage and control environmental issues.

2.4.2. The proposed project organization and lines of communication with respect to environmental protection works are shown in ***Figure 2.2***. Key personnel and contact particulars are summarized in ***Table 2.3***:

Table 2.3 Contact Details of Key Personnel

Party	Role	Post	Name	Contact No.	Contact Fax
AECOM	Engineer's Representative for WDII	Principal Resident Engineer	Mr. Frankie Fan	2587 1778	2587 1877
	Engineer's Representative for CWB	Principal Resident Engineer	Mr. Peter Poon	3912 3388	3912 3328
Chun Wo – Leader Joint Venture	Contractor under Contract no. HK/2009/01	Project Manager	Mr. Simon Liu	9304 8355	2587 1878
		Site Agent	Mr. Andy Yu	9648 4896	
		Environmental Officer	Mr. Terry Tsang	6683 9394	
Chun Wo – CRGL Joint Venture	Contractor under Contract no. HK/2009/02	Project Manager	Mr. Paul Yu	3658-3085	2827 9996
		Quality & Environmental Manager	Mr. C.P. Ho	9191 8856	
China State Construction Engineering (HK) Ltd.	Contractor under Contract no. HY/2009/15	Project Director	Chris Leung	3557 6393	2566 2192
		Senior Site Manager	Y Huo	3557 6368	
		Contractor's Representative	Rex Lau	3557 6405	
		Environmental Officer	Andy Mak	3557 6347	
Chun Wo – CRGL – MBEC_ Joint Venture	Contractor under Contract no. HY/2009/19	Project Manager	Rayland Lee	3758 6788	3757 8901
		Site Agent	David Lau	3758 8879	
		Deputy Site Agent	Andy Chan	9879 4325	
		Environmental Manager / Environmental Officer	M.H. Isa	9884 0810	
		Construction Manager (Marine)	Wingo Wong	9300 2625	
		Construction Manager (Land)	Ivan Wong	9200 7552	
China State-Build King Joint Venture	Contractor under Contract no. HK/2012/08	Project Director	C. N. Lai	9106 5806	2877 1522
		Project Manager	Eddie Chung	9189 8118	
		Site Agent	Keith Tse	9037 1839	
		Environmental Officer	James Ma	9130 9549	
China State	Contractor under Contract no. HY/2010/08	Project Director	Chris Leung	3467 4299	2566 8061
		Project Manager	Chan Ying Lun	3418 3001	
		Site Agent	Thomas Lui	3557 6452	

Party	Role	Post	Name	Contact No.	Contact Fax
		Environmental Officer	Gabriel Wong	35576466	
Ramboll Environ Hong Kong Limited	Independent Environmental Checker (IEC)	Independent Environmental Checker (IEC)	Mr. David Yeung	3465 2888	3465 2899
Lam Geotechnics Limited	Environmental Team (ET)	Environmental Team Leader (ETL)	Mr. Raymond Dai	2882 3939	2882 3331

2.4.3. For Contract no. HK/2009/01, the principal work activities in this reporting month included:

- Nil

2.4.4. For Contract no. HK/2009/02, the principal work activities in this reporting month included:

- Nil

2.4.5. For Contract no. HY/2009/15, the principal work activities in this reporting month included:

- Nil

2.4.6. For Contract no. HY/2009/19, the principal work activity in this reporting month included:

- Nil

2.4.7. For Contract no. HK/2012/08, the principal work activity in this reporting month included:

- Construction of Box 1 unit and backfilling

2.4.8. For Contract no. HY/2010/08, no principal work activities this reporting month.

- Diversion pipe maintenance
- Diaphragm Wall Removal Works
- Removal of reclamation at TS3E and TS3W

2.4.9. In coming reporting month, the principal work activities of individual contracts are anticipated as follows:

Contract no. HK/2009/01 – Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

- Nil

Contract no. HK/2009/02 – Wan Chai Development Phase II – Central – Wan Chai Bypass at Wan Chai East

- Nil

Contract no. HY/2009/15 – Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)

- Nil

Contract no. HY/2009/19- Wan Chai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

- Nil

Contract no. HK/2012/08 – Wan Chai Development Phase II – Central- Wan Chai Bypass at Wan Chai West

- Construction of Box 1 unit and backfilling

Contract no. HY/2010/08 –Central - Wan Chai Bypass (CWB) –Tunnel (Slip Road 8)

- Diversion pipe maintenance
- Diaphragm Wall Removal Works
- Removal of reclamation at TS3E and TS3W

3 Status of Regulatory Compliance

3.1 Status of Environmental Licensing and Permitting under the Project

3.1.1. A summary of the current status on licences and/or permits on environmental protection pertinent to the Project is shown in ***Table 3.1***.

Table 3.1 Summary of the current status on licences and/or permits on environmental protection pertinent to the Project

Permits and/or Licences	Reference No.	Issued Date	Status
Environmental Permit	EP-356/2009	30 Jul 2009	Valid
Environmental Permit	EP-364/2009	17 Aug 2009	Superseded
Environmental Permit	EP-364/2009/A	4 Aug 2010	Superseded
Environmental Permit	EP-364/2009/B	20 Sep 2012	Superseded
Environmental Permit	EP-364/2009/C	11 Jul 2014	Superseded
Environmental Permit	EP-364/2009/D	24 Nov 2016	Superseded
Environmental Permit	EP-364/2009/E	22 Dec 2016	Valid
Environmental Permit	EP-376/2009	13 Nov 2010	Valid
Further Environmental Permit	FEP-01/356/2009	18 Feb 2010	Surrendered
Further Environmental Permit	FEP-02/356/2009	24 Mar 2010	Valid
Further Environmental Permit	FEP-03/356/2009	24 Mar 2010	Valid
Further Environmental Permit	FEP-04/356/2009	22 Nov 2010	Valid
Further Environmental Permit	FEP-05/356/2009	24 Mar 2011	Surrendered
Further Environmental Permit	FEP-01/364/2009	24 Mar 2010	Valid
Further Environmental Permit	FEP-02/364/2009	21 Apr 2010	Valid
Further Environmental Permit	FEP-03/364/2009	12 Jul 2010	Surrendered
Further Environmental Permit	FEP-04/364/2009/A	14 Oct 2010	Surrendered
Further Environmental Permit	FEP-05/364/2009/A	15 Nov 2010	Valid
Further Environmental Permit	FEP-06/364/2009/A	22 Nov 2010	Valid
Further Environmental Permit	FEP-07/364/2009/B	20 Sep 2012	Surrendered
Further Environmental Permit	FEP-07/364/2009/D	24 Nov 2015	Valid
Further Environmental Permit	FEP-08/364/2009/A	15 Jun 2012	Surrendered
Further Environmental Permit	FEP-06/356/2009	5 Mar 2013	Valid

Permits and/or Licences	Reference No.	Issued Date	Status
Further Environmental Permit	FEP-07/356/2009	26 July 2013	Valid
Further Environmental Permit	FEP-09/364/2009/B	5 March 2013	Valid
Further Environmental Permit	FEP-10/364/2009/B	26 July 2013	Valid
Further Environmental Permit	FEP-11/364/2009/B	2 May 2014	Superseded
Further Environmental Permit	FEP-08/356/2009	1 Aug 2016	Valid
Further Environmental Permit	FEP-11/364/2009/E	22 Dec 2016	Valid

3.1.2. Due to the multi-contract nature of the Project, the status of permits and/or licences under the individual contract(s) are presented as below:

Contract no. HK/2010/06 – Wan Chai Development Phase II – Central – Wan Chai Bypass over MTR Tsuen Wan Line under FEP-05/356/2009

3.1.3. The construction works were completed and the FEP-05/356/2009 was surrendered by the Contractor on 3 October 2014.

Contract no. HK/2009/01 – Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

3.1.4. Summary of the current status on licences and/or permits on environmental protection pertinent and submission for contract no. HK/2009/01 under FEP-02/356/2009 are shown in ***Table 3.2*** and ***Table 3.3***.

Table 3.2 Cumulative Summary of Valid Licences and Permits under Contract no. HK/2009/01

Permits and/or Licences	Reference No.	Issued Date	Valid Period/ Expiry Date	Status
Further Environmental Permit	FEP-02/356/2009	24 Mar 2010	N/A	Valid
	FEP-02/364/2009	21 Apr 2010	N/A	Valid
Notification of Works Under APCO	313088	06 Jan 2010	N/A	Valid
Discharge Licence	WT00024952-2016	6 Jul 2016	31 Jul 2021	Valid
	WT00024844-2016	29 Jun 2016	31 Mar 2020	Valid
Billing account under Waste Disposal Ordinance	7010069	21 Jan 2010	N/A	Valid

Permits and/or Licences	Reference No.	Issued Date	Valid Period/ Expiry Date	Status
Registration as a Chemical Waste Producer	WPN5213-134-C3585-01	21 Jan 2010	N/A	Valid

Table 3.3 Summary of submission status under FEP-02/356/2009 Condition

EP Condition	Submission	Date of Submission
Condition 2.6	Management Organization of Main Construction Companies	13 Apr 2010
Condition 2.7	Works Schedule and Location Plan	8 Apr 2010
Condition 2.8	Silt Curtain Deployment Plan (Rev. 5)	24 Aug 2012
	Silt Curtain Deployment Plan (Rev. 4)	12 July 2012
	Silt Curtain Deployment Plan (Rev. 3)	27 June 2012
	Silt Curtain Deployment Plan	19 Apr 2010
Condition 2.9	Silt Screen Deployment Plan (Rev. 9)	5 Nov 2015
	Silt Screen Deployment Plan (Rev. 8)	7 Sep 2015
	Silt Screen Deployment Plan (Rev. 7)	21 Nov 2014
	Silt Screen Deployment Plan (Rev. 6)	20 Aug 2014
	Silt Screen Deployment Plan (Rev.5)	24 Jul 2013
	Silt Screen Deployment Plan (Rev.4)	15 Nov 2012
	Silt Screen Deployment Plan	19 Apr 2010
Conditions 2.8 and 2.9	Supplementary Document on Silt Curtain and Silt Screen Deployment Plan	19 Jul 2010
	Report on Field Testing for Silt Curtain	26 Aug 2010
	Report on Field Testing for Silt Curtain (Rev. A)	15 Nov 2010
Condition 2.12(d)	Alternative Proposal on Concurrent Dredging for Sewage Pipeline and Cross Harbour Water Mains	15 Apr 2011
Condition 2.17	Noise Management Plan	23 Apr 2010
Condition 2.18	Landscape Plan (Erection of Decorative Screen Hoarding along Construction Site around Hong Kong Exhibition and Convention Centre)	15 May 2010
	Landscape Plan (Night-time Lighting)	22 Oct 2010

EP Condition	Submission	Date of Submission
	Landscape Plan (Rev. B)	15 Nov 2010
Condition 1.12	Notification of Commencement Date	20 Jun 2011
Condition 2.6 to 2.8	Management Organization, Works Schedule and Location Plan	18 May 2011
Condition 2.9	Silt Screen Deployment Plan	10 Jun 2011
Condition 2.18	Landscape Plan	31 Oct 2013

Contract no. HK/2009/02 – Wan Chai Development Phase II – Central – Wan Chai Bypass at WanChai East

3.1.5. Summary of the current status on licences and/or permits on environmental protection pertinent and submission for contract no. HK/2009/02 under FEP-03/356/2009 are shown in ***Table 3.4*** and ***Table 3.5***.

Table 3.4 Cumulative Summary of Valid Licences and Permits under Contract no. HK/2009/02

Permits and/or Licences	Reference No.	Issued Date	Valid Period/ Expiry Date	Status
Further Environmental Permit	FEP-03/356/2009	24 Mar 2010	N/A	Valid
	FEP-01/364/2009	24 Mar 2010	N/A	Valid
Notification of Works Under APCO	313962	2 Feb 2010	N/A	Valid
Construction Noise Permit (CNP) for non-piling equipment	GW-RS0314-17	7 Apr 2017	11 Apr 2017 to 4 Oct 2017	Expired
	GW-RS0348-17	18 Apr 2017	25 Apr 2017 to 24 Oct 2017	Expired
	GW-RS0726-17	22 Aug 2017	3 Sep 2017 to 25 Feb 2018	Superseded
	GW-RS0751-17	4 Sep 2017	10 Sep 2017 to 4 Feb 2018	Superseded
	GW-RS0756-17	4 Sep 2017	7 Sep 2017 to 28 Feb 2018	Valid
	GW-RS0763-17	4 Sep 2017	6 Sep 2017 to 4 Mar 2018	Superseded
	GW-RS0843-17	28 Sep2017	7 Oct 2017 to 25 Mar 2018	Valid
	GW-RS0869-17	10 Oct 2017	15 Oct 2017 to 11 Mar 2018	Valid
	GW-RS0884-17	12 Oct 2017	24 Oct 2017 to 23 Apr 2018	Valid
	GW-RS0885-17	12 Oct 2017	14 Oct 2017 to 12 Apr 2018	Valid

Permits and/or Licences	Reference No.	Issued Date	Valid Period/ Expiry Date	Status
Discharge Licence	WT00022295-2015	12 Aug 2015	31 July 2020	Valid
	WT00025276-2016	19 Sep 2016	31 July 2021	Valid
Billing Account under Waste Disposal Ordinance (Land)	7010255	10 Feb 2010	N/A	Valid
Billing Account under Waste Disposal Ordinance (Marine)	7011496	6 Oct 2010	N/A	Valid
Registration as Chemical Waste Producer (Wan Chai)	WPN5213-135-C3 593-01	10 Mar 2010	N/A	Valid
Registration as Chemical Waste Producer (TKO 137)	WPN5213-839-C3 593-02	22 Sep 2010	N/A	Valid
Marine Dumping Permit (Dredged Sediment Requiring Type 1 – Open Sea Disposal)	EP/MD/17-191	16 May 2017	18 May 2017 to 17 Nov 2017	Valid

Table 3.5 Summary of submission status under FEP-03/356/2009 Condition

EP Condition	Submission	Date of Submission
Condition 1.12	Commencement Date of Construction of Marine Works	8 April 2010
Condition 2.6	Management Organization of Main Construction Companies	10 April 2010
Condition 2.7	Works Schedule and Location Plans	8 April 2010
Condition 2.8	Silt Curtain Deployment Plan (Revision A)	20 April 2010
	Silt Curtain Deployment Plan (Revision B)	25 May 2010
	Silt Curtain Deployment Plan (Revision C)	14 Jun 2010
	Silt Curtain Deployment Plan (Revision H)	15 Feb 2011
	Silt Curtain Deployment Plan (Revision I)	17 Nov 2011
	Silt Curtain Deployment Plan (Revision J)	15 Feb 2012
	Silt Curtain Deployment Plan (Revision K)	3 May 2012
	Silt Curtain Deployment Plan (Revision L)	25 Oct 2012
	Silt Curtain Deployment Plan (Revision M)	30 Nov 2012
Condition 2.9	Silt Screen Deployment Plan	21 April 2010
	Supplementary Information for Existing WSD Salt Water Intakes at Quarry Bay and Sai Wan Ho	5 Oct 2010
	Silt Screen Deployment Plan (Revision B)	15 Feb 2012

EP Condition	Submission	Date of Submission
	Silt Screen Deployment Plan (Revision C)	3 May 2012
	Silt Screen Deployment Plan (Revision D)	10 Dec 2012
	Silt Screen Deployment Plan (Revision E)	6 May 2013
	Silt Screen Deployment Plan (Revision F)	23 Nov 2016
Condition 2.17	Noise Management Plan	6 May 2010
Condition 2.18	Landscape Plan (Decorative Screen Hoarding)	11 May 2010
	Landscape Plan (Control of Night Time Lighting)	2 June 2010
	Landscape Plan (Combined Version)	20 July 2011
	Landscape Plan (Combined Version)	5 Aug 2011
-----	Acknowledge of Submission	22 Aug 2011

Contract no. HY/2009/15 – Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)

3.1.6. Summary of the current status on licences and/or permits on environmental protection pertinent and submission for contract no. HY/2009/15 under FEP-04/356/2009 are shown in ***Table 3.6*** and ***Table 3.7***.

Table 3.6 Cumulative Summary of Valid Licences and Permits under Contract no. HY/2009/15

Permits and/or Licences	Reference No.	Issued Date	Valid Period/ Expiry Date	Status
Further Environmental Permit	FEP-04/356/2009	22 Nov 2010	N/A	Valid
Notification of Works Under APCO	321822	24 Sep 2010	N/A	Valid
Registration as a Chemical Waste Producer	WPN5213-147-C1169-35	15 Nov 2010	N/A	Valid
Billing Account under Waste Disposal Ordinance	7011553	30 Sep 2010	N/A	Valid

Table 3.7 Summary of submission status under FEP-04/356/2009 Condition

FEP Condition	Submission	Date of Submission
Condition 2.6	Management Organization of Main Construction Companies	30 Sep 2010
	Amendment for Management Organization of Main Construction Companies	16 May 2011
Condition 2.7	Works Schedule and Location Plans	27 Oct 2010
	Amendment for Works Schedule and Location Plans	12 Nov 2010
Condition 2.8	Silt Curtain Deployment Plan	30 Nov 2010
	Amendment for Silt Curtain Deployment Plan	24 Feb 2011
	Amendment for Silt Curtain Deployment Plan	11 May 2011
	Amendment for Silt Curtain Deployment Plan	11 Sep 2012
	Amendment for Silt Curtain Deployment Plan	30 Oct 2012
Condition 2.9	Silt Screen Deployment Plan	19 Oct 2010
	Amendment for Silt Screen Deployment Plan	18 Feb 2011
	Amendment for Silt Screen Deployment Plan	15 Jun 2011
Condition 2.18	Proposal for the Removal of Odorous Sediment and Slime	13 Jan 2011
	Amendment for Proposal for the Removal of Odorous Sediment and Slime	8 Mar 2011
	Amendment for Proposal for the Removal of Odorous Sediment and Slime	2 Aug 2011
Condition 2.21	Landscape Plan	18 Feb 2011
Condition 2.23	Noise Management Plan	20 Oct 2010
	Amendment for Noise Management Plan	27 Jan 2011

Contract no. HY/2009/19 – Central- Wan Chai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

3.1.7. Summary of the current status on licences and/or permits on environmental protection pertinent for contract no. HY/2009/19 is shown in ***Table 3.8***

Table 3.8 Cumulative Summary of Valid Licences and Permits under Contract no. HY/2009/19

Permit / Licence / Notification / Approval	**Reference No.**	**Issued Date**	**Valid Period / Expiry date**	**Status**
Further Environmental Permit	FEP-07/364/2009/D	24 Nov 2015	Granted	Valid
Notification of Works Under APCO	326160	24 Jan 2011	Notified	Valid
C&D Waste Disposal	7012306	10 Feb 2011	Registered	-
Vessel Disposal	7013285	21 July 2011	Registered	-

Permit / Licence / Notification / Approval	Reference No.	Issued Date	Valid Period / Expiry date	Status
Registration as Chemical Waste Producer	5213-151-C3654-01	24 Mar 2011	Registered	-

Contract no. HK/2012/08 – Wan Chai Development Phase II – Central- Wan Chai Bypass at Wan Chai West

3.1.8. Summary of the current status on licences and/or permits on environmental protection pertinent and submission for contract no. HK/2012/08 under FEP-08/356/2009 are shown in ***Table 3.9*** and ***Table 3.10***.

Table 3.9 Cumulative Summary of Valid Licences and Permits under Contract no. HK/2012/08

Permits and/or Licences	Reference No.	Issued Date	Valid Period/ Expiry Date	Status
Further Environmental Permit	FEP-06/356/2009	5 Mar 2013	N/A	Valid
	FEP-08/356/2009	1 Aug 2016	N/A	Valid
Notification of Works Under APCO	355439	4 Feb 2013	N/A	Valid
Registration as a Chemical Waste Producer	5213-134-C3790-01	30 Jun 2016	N/A	Valid
Billing Account under Waste Disposal Ordinance	7016883	18 Feb 2013	N/A	Valid
Water Discharge Licence	WT00020594-2014	22 Dec 2014	31 Jan 2019	Valid
Construction Noise Permit	GW-RS0385-17	27 Apr 2017	5 May 2017 to 4 Nov 2017	Valid
	GW-RS0505-17	9 Jun 2017	13 Jul 2017 to 12 Jan 2018	Valid
	GW-RS0593-17	11 Jul 2017	13 Jul 2017 to 12 Jan 2018	Valid
	GW-RS0504-17	8 Jun 2017	12 Jul 2017 to 11 Jan 2018	Valid
	GW-RS0676-17	3 Aug 2017	26 Aug 2017 to 25 Feb 2018	Valid
Dumping Permit (Type 1 – Open Sea Disposal)	EP/MD/18-039	8 Aug 2017	11 Aug 2017 to 10 Feb 2018	Valid

Table 3.10 Summary of submission status under EP-356/2009 and FEP-06/356/2009 Condition

FEP Condition	Submission	Date of Submission
Condition 2.8	Silt Curtain Deployment Plan (Rev. 3)	Submitted on 25 Nov 2013 was returned to CSLJV by EPD.
Condition 2.9	Silt Screen Deployment Plan (Rev. 2)	Generally in order as commented by EPD on 19 Sep 2013
Condition 2.23	Noise Management Plan (Rev. 2)	Generally in order as commented by EPD on 15 Aug 2013
Condition 2.24	Landscape Plan (Rev. 3)	Generally in order as commented by EPD on 31 Oct 2013

Contract no. HY/2010/08 –Central - Wan Chai Bypass (CWB) –Tunnel (Slip Road 8)

3.1.9. Summary of the current status on licences and/or permits on environmental protection pertinent and submission for contract no. HY/2010/08 under FEP-07/356/2009 are shown in Table ***3.11*** and ***Table 3.12***.

Table 3.11 Cumulative Summary of Valid Licences and Permits under Contract no. HY/2010/08

Permits and/or Licences	Reference No.	Issued Date	Valid Period/ Expiry Date	Status
Further Environmental Permit	FEP-07/356/2009	26 Jul 2013	NA	Valid
	FEP-10/364/2009/B	26 Jul 2013	NA	Valid
Notification of Works Under APCO	357176	2 Apr 2013	NIL	Valid
Registration as a Chemical Waste Producer	WPN5213-147-C11 69-44	27 Mar 2013	NIL	Valid
Billing Account under Waste Disposal Ordinance	7017170	27 Mar 2013	NIL	Valid
Billing Account under Waste Disposal Ordinance (Dumping by Vessel)	7020947	22 Dec 2014	NIL	Valid.
Water Discharge Licence	WT00020468-2014	3 Dec 2014	9 Jul 2013 to 31 Jul 2018	Valid
	WT00028744-2017	4 Aug 2017	4 Aug 2017 to 31 Aug 2019	Valid

Permits and/or Licences	Reference No.	Issued Date	Valid Period/ Expiry Date	Status
Construction Noise Permit	GW-RS0347-17	27 Apr 2017	27 Apr 2017 to 18 Oct 2017	Valid
	GW-RS0877-17	10 Oct 2017	18 Oct 2017 to 17 Apr 2017	Valid

Table 3.12 Summary of submission status under EP-356/2009 and FEP-07/356/2009 Condition

FEP Condition	Submission	Date of Submission
Condition 2.8	Silt Curtain Deployment Plan (rev03)	24 Dec 2014
Condition 2.9	Silt Curtain Deployment Plan (rev03)	29 Sept 2017
Condition 2.9	Silt Screen Deployment Plan (rev02)	18 Feb 2015
Condition 2.23	Noise Management Plan (rev02)	25 Mar 2014
Condition 2.24	Landscape Plant (rev04)	23 Sep 2014

4 Monitoring Requirements

4.1 Noise Monitoring

NOISE MONITORING STATIONS

4.1.1. The noise monitoring stations for the Project are listed and shown in ***Table 4.1*** and ***Figure 4.1***. ***Appendix 4.1*** shows the established Action/Limit Levels for the monitoring works.

Table 4.1 Noise Monitoring Station

Station	Description
M1a	Footbridge for Ex-Harbour Road Sports Centre*
M2b	Noon Gun Area
M3a	Tung Lo Wan Fire Station
M4b	Victoria Centre
M5b	City Garden
M6	HK Baptist Church Henrietta Secondary School

Remarks*: With respect to the demolition of Ex-Harbour Road Sports Centre, the respective noise monitoring station M1a – Harbour Road Sports Centre were finely adjusted on 16 and 25 May 2017 and thereafter to the Footbridge for Harbour Road Sports for noise monitoring

NOISE MONITORING PARAMETERS, FREQUENCY AND DURATION

4.1.2. The construction noise level shall be measured in terms of the A-weighted equivalent continuous sound pressure level (L_{eq}). $L_{eq\ (30\ minutes)}$ shall be used as the monitoring parameter for the time period between 0700 and 1900 hours on normal weekdays. For all other time periods, $L_{eq\ (5\ minutes)}$ shall be employed for comparison with the Noise Control Ordinance (NCO) criteria. Supplementary information for data auditing, statistical results such as L10 and L90 shall also be obtained for reference.

4.1.3. Noise monitoring shall be carried out at all the designated monitoring stations. The monitoring frequency shall depend on the scale of the construction activities. The following is an initial guide on the regular monitoring frequency for each station on a weekly basis when noise generating activities are underway:

- One set of measurements between 0700 and 1900 hours on normal weekdays.

4.1.4. If construction works are extended to include works during the hours of 1900 – 0700 as well as public holidays and Sundays, additional weekly impact monitoring shall be carried out during respective restricted hours periods. Applicable permits under NCO shall be obtained by the Contractor.

MONITORING EQUIPMENT

4.1.5. As referred to in the Technical Memorandum ™ issued under the NCO, sound level meters in compliance with the International Electrotechnical Commission Publications 651: 1979 (Type 1) and 804: 1985 (Type 1) specifications shall be used for carrying out the noise monitoring. Immediately prior to and following each noise measurement the accuracy of the sound level

meter shall be checked using an acoustic calibrator generating a known sound pressure level at a known frequency. Measurements may be accepted as valid only if the calibration level from before and after the noise measurement agree to within 1.0 dB.

4.1.6. Noise measurements shall not be made in fog, rain, wind with a steady speed exceeding 5 m/s or wind with gusts exceeding 10 m/s. The wind speed shall be checked with a portable wind speed meter capable of measuring the wind speed in m/s.

4.2 Air Monitoring

AIR QUALITY MONITORING STATIONS

4.2.1. The air monitoring stations for the Project are listed and shown in ***Table 4.2*** and ***Figure 4.1***. ***Appendix 4.1*** shows the established Action/Limit Levels for the monitoring works.

Table 4.2 Air Monitoring Station

Station ID	Monitoring Location	Description
CMA1b	Harbour Grand Hotel Boundary Wall**	North Point
CMA2a	Causeway Bay Community Centre	Causeway Bay
CMA3a	CWB PRE Site Office *	Causeway Bay
CMA4a	Society for the Prevention of Cruelty to Animals	Wan Chai
CMA5b	Pedestrian Plaza***	Wan Chai
CMA6a	WDII PRE Site Office *	Wan Chai

Remarks*: As per the ENPC meeting in March 2011, the monitoring stations CMA3a – Future CWB site office at Wanchai Waterfront Promenade was renamed as remark.

Remarks**: The location ID of monitoring station CMA1b was updated as “Harbour Grand Hotel Boundary Wall” from 05 June 2017 onwards.

Remarks***: The station ID and monitoring location was updated in December 2014 with respect to monitoring station relocation.

AIR MONITORING PARAMETERS, FREQUENCY AND DURATION

4.2.2. One-hour and 24-hour TSP levels should be measured to indicate the impacts of construction dust on air quality. The 24-hour TSP levels shall be measured by following the standard high volume sampling method as set out in the Title 40 of the Code of Federal Regulations, Chapter 1 (Part 50), Appendix B.

4.2.3. All relevant data including temperature, pressure, weather conditions, elapsed-time meter reading for the start and stop of the sampler, identification and weight of the filter paper, and any other local atmospheric factors affecting or affected by site conditions, etc., shall be recorded down in detail.

4.2.4. For regular impact monitoring, the sampling frequency of at least once in every six-days, shall be strictly observed at all the monitoring stations for 24-hour TSP monitoring. For 1-hour TSP

monitoring, the sampling frequency of at least three times in every six-days should be undertaken when the highest dust impact occurs.

SAMPLING PROCEDURE AND MONITORING EQUIPMENT

4.2.5. High volume samplers (HVSs) in compliance with the following specifications shall be used for carrying out the 1-hour and 24-hour TSP monitoring:

- 0.6 – 1.7 m3 per minute adjustable flow range;
- equipped with a timing / control device with +/- 5 minutes accuracy for 24 hours operation;
- installed with elapsed-time meter with +/- 2 minutes accuracy for 24 hours operation;
- capable of providing a minimum exposed area of 406 cm2;
- flow control accuracy: +/- 2.5% deviation over 24-hour sampling period;
- equipped with a shelter to protect the filter and sampler;
- incorporated with an electronic mass flow rate controller or other equivalent devices;
- equipped with a flow recorder for continuous monitoring;
- provided with a peaked roof inlet;
- incorporated with a manometer;
- able to hold and seal the filter paper to the sampler housing at horizontal position;
- easily changeable filter; and
- capable of operating continuously for a 24-hour period.

4.2.6. Initial calibration of dust monitoring equipment shall be conducted upon installation and thereafter at bi-monthly intervals. The transfer standard shall be traceable to the internationally recognized primary standard and be calibrated annually. The concern parties such as IEC shall properly document the calibration data for future reference. All the data should be converted into standard temperature and pressure condition.

LABORATORY MEASUREMENT / ANALYSIS

4.2.7. A clean laboratory with constant temperature and humidity control, and equipped with necessary measuring and conditioning instruments to handle the dust samples collected, shall be available for sample analysis, and equipment calibration and maintenance. The laboratory should be HOKLAS accredited.

4.2.8. An alternative non-HOKLAS accredited laboratory was set-up for carrying out the laboratory analysis, the laboratory equipment was approved by the ER on 8 February 2011 and the measurement procedures were witnessed by the IEC. Any measurement performed by the laboratory was be demonstrated to the satisfaction of the ER and IEC. IEC shall regularly audit to the measurement performed by the laboratory to ensure the accuracy of measurement results.

4.2.9. Filter paper of size 8” x 10” shall be labelled before sampling. It shall be a clean filter paper with no pinholes, and shall be conditioned in a humidity-controlled chamber for over 24-hours and be pre-weighed before use for the sampling.

4.2.10. After sampling, the filter paper loaded with dust shall be kept in a clean and tightly sealed plastic bag. The filter paper shall then be returned to the laboratory for reconditioning in the humidity controlled chamber followed by accurate weighing by an electronic balance with readout down to 0.1 mg. The balance shall be regularly calibrated against a traceable standard.

4.2.11. All the collected samples shall be kept in a good condition for 6 months before disposal.

IMPACT MONITORING FOR ODOUR PATROL

4.2.12. Odour patrols along the shorelines of Causeway Bay Typhoon Shelter and ex-Wan Chai Public Cargo Working Area when there is temporary reclamation in Causeway Bay Typhoon Shelter and/or in the ex-Wan Chai Public Cargo Working Area, or when there is dredging of the odorous sediment and slime at the south-western corner of the Causeway Bay Typhoon Shelter. Odour patrols will be carried out at bi-weekly intervals during July, August and September by a qualified person of the ET who shall:

- be at least 16 years of age;
- be free from any respiratory illnesses; and
- not be allowed to smoke, eat, drink (except water) or use chewing gum or sweets 30 min
- before and during odour patrol

4.2.13. Odour patrol shall be conducted by independent trained personnel / competent persons patrolling and sniffing around the shore as shown in ***Figure 4.1*** to detect any odour at the concerned hours (afternoon is preferred for higher daily temperature).

4.2.14. The qualified person will use the nose (olfactory sensor) to sniff odours at different locations. The main odour emission sources and the areas to be affected by the odour nuisance will be identified.

4.2.15. The perceived odour intensity is to be divided into 5 levels which are ranked in the descending order as follows:

- 0 – Not detected. No odour perceived or an odour so weak that it cannot be easily characterized or described;
- 1 – Slight Identifiable odour, and slight chance to have odour nuisance;
- 2 – Moderate Identifiable odour, and moderate chance to have odour nuisance;
- 3 – Strong Identifiable, likely to have odour nuisance;
- 4 – Extreme Severe odour, and unacceptable odour level.

4.2.16. The findings including odour intensity, odour nature and possible odour sources, and also the local wind speed and direction at each location will be recorded. In addition, some relevant meteorological and tidal data such as daily average temperature, and daily average humidity, on that surveyed day will be obtained from the Hong Kong Observatory Station for reference. The Action and Limit levels for odour patrol are shown in ***Appendix 4.1***.

4.2.17. The qualified odour patrol member has individual n-butanol thresholds complied with the requirement of European Standard Method of Air Quality – Determination of Odour Concentration by Dynamic Olfactometry (EN13725) in the range of 20 to 80 ppb.

4.3 Water Quality Monitoring

4.3.1. The EIA Report has identified that the key water quality impact would be associated with the dredging works during the construction phase. Marine water quality monitoring for dissolved oxygen (DO), suspended solid (SS) and turbidity is therefore recommended to be carried out at selected WSD flushing water intakes. The impact monitoring should be carried out during the proposed dredging works to ensure the compliance with the water quality standards.

4.3.2. The updated EM&A Manual for EP-356/2009 (Version in March 2011) is approval by EPD on 29 April 2011. As such, the Action Level and Limit Level for the wet season (April – September) will be effected and applied to the water quality monitoring data from 30 April 2011.

Water Quality Monitoring Stations

4.3.3. Water quality monitoring was undertaken at 8 monitoring stations for WSD salt water intakes and cooling water intakes along the seafront of the Victoria Harbour in the reporting month. The proposed water quality monitoring stations of the Project are shown in ***Table 4.3*** and ***Figure 4.1***. ***Appendix 4.1*** shows the established Action/Limit Levels for the monitoring works.

Table 4.3 Marine Water Quality Stations for Water Quality Monitoring

Station Ref.	Location	Easting	Northing
WSD Salt Water Intake			
WSD19	Sheung Wan	833415.0	816771.0
Cooling Water Intake			
C1	HKCEC Extension	835885.6	816223.0
C7	Windsor House	837193.7	816150.0
P1	HKCEC Phase I	835774.7	816179.4
P3	The Academy of performing Arts	835824.6	816212.0
P4	Shui on Centre	835865.6	816220.0
P5	Government Buildings (Wanchai Tower / Revenue Tower / Immigration Tower)	835895.2	816215.2
Cooling Water Intake / WSD Salt Water Intake			
RW21-P789	Great Eagle Centre/ Sun Hung Kai Centre/ WSD Wanchai salt water intake / China Resources Building	836268.0	816020.0

Remarks: -
- The cessation of seawater intake operation for C6 was confirmed on 17 May 2011 and the water quality monitoring at C6 was then terminated since 17 May 2011.
- 4-week post construction water quality monitoring at WSD9, WSD10, WSD15 and WSD17 were completed on 6 Feb 2012 and the water quality monitoring at WSD 10 and WSD15 were temporary suspended since 8 Feb 2012, and WSD9 and WSD17 was implemented with respect to HK/2009/02 from 8 Feb 2012 onwards.
- C8 and C9 were implemented with respect to HY/2009/19 from 28 Jan 2012.
- C8 & C9 were temporary suspended since 4 March 2013.
- WSD7 and WSD20 water quality monitoring were temporarily suspended from 27 Apr 2012.
- C2, C3 C4e and C4w water quality monitoring station was temporarily suspended since 22 Apr 2013
- P1, P3, P4 and P5 were commenced since 24 Apr 2013
- C5e and C5w water quality monitoring station was temporarily suspended since 29 Jul 2013.

- WSD21 water quality monitoring station was temporarily suspended since 12 Mar 2014
- WSD9 and WSD17 water quality monitoring station was temporarily suspended since 8 Sep 2014 flood tide.
- The water quality monitoring station C1 shall be associated with Contract No. HK/2009/02 upon commencement of marine works under DP3 at WCR3 area.
- The water quality monitoring station RW21-P789 was adjusted to RW21-P789E and RW21-P789W since 28 November 2016 ebb-tide.
- The water quality monitoring was reverted to previous monitoring station RW21-P789 from PW21-P789E and RW21-P789W from 25 January 2017 onwards.

WATER QUALITY PARAMETERS

4.3.4. Monitoring of dissolved oxygen (DO), turbidity and suspended solids (SS) shall be carried out at WSD flushing water intakes and cooling water intakes. DO and Turbidity are measured in-situ while SS is determined in laboratory.

4.3.5. In association with the water quality parameters, other relevant data shall also be measured, such as monitoring location/position, time, sampling depth, water temperature, pH, salinity, dissolved oxygen (DO) saturation, weather conditions, sea conditions, tidal stage, and any special phenomena and work underway at the construction site etc.

SAMPLING PROCEDURES AND MONITORING EQUIPMENT

4.3.6. The interval between two sets of monitoring should not be less than 36 hours except where there are exceedances of Action and/or Limit Levels, in which case the monitoring frequency will be increased. ***Table 4.4*** shows the proposed monitoring frequency and water quality parameters. Duplicate in-situ measurements and water sampling should be carried out in each sampling event. For selection of tides for in-situ measurement and water sampling, tidal range of individual flood and ebb tides should be not less than 0.5m.

Table 4.4 Marine Water Quality Monitoring Frequency and Parameters

Activities	**Monitoring Frequency[1]**	**Parameters[2]**
During the 4-week baseline monitoring period	Three days per week, at mid-flood and mid-ebb tides	Turbidity, Suspended Solids (SS), Dissolved Oxygen (DO), pH, Temperature, Salinity
During marine construction works	Three days per week, at mid-flood and mid-ebb tides	Turbidity, Suspended Solids (SS), Dissolved Oxygen (DO), pH, Temperature, Salinity
After completion of marine construction works	Three days per week, at mid-flood and mid-ebb tides	Turbidity, Suspended Solids (SS), Dissolved Oxygen (DO), pH, Temperature, Salinity

Notes:
1. For selection of tides for in-situ measurement and water sampling, tidal range of individual flood and ebb tides should be not less than 0.5m.
2. Turbidity should be measured in situ whereas SS should be determined by laboratory.

DISSOLVED OXYGEN AND TEMPERATURE MEASURING EQUIPMENT

4.3.7. The instrument should be a portable, weatherproof dissolved oxygen measuring instrument complete with cable, sensor, comprehensive operation manuals, and use a DC power source. It should be capable of measuring:

- a dissolved oxygen level in the range of 0-20 mg/l and 0-200% saturation
- a temperature of 0-45 degree Celsius

4.3.8. It should have a membrane electrode with automatic temperature compensation complete with a cable. Sufficient stocks of spare electrodes and cables should be available for replacement where necessary. (e.g. YSI model 59 meter, YSI 5739 probe, YSI 5795A submersible stirrer with reel and cable or an approved similar instrument).

4.3.9. Should salinity compensation not be build-in in the DO equipment, in-situ salinity shall be measured to calibrate the DO equipment prior to each DO measurement.

TURBIDITY MEASUREMENT INSTRUMENT

4.3.10. The instrument should be a portable, weatherproof turbidity-measuring instrument complete with comprehensive operation manual. The equipment should use a DC power source. It should have a photoelectric sensor capable of measuring turbidity between 0-1000 NTU and be complete with a cable (e.g. Hach model 2100P or an approved similar instrument).

SAMPLER

4.3.11. A water sampler comprises a transparent PVC cylinder, with a capacity of not less than 2 litres, and can be effectively sealed with latex cups at both ends. The sampler should have a positive latching system to keep it open and prevent premature closure until released by a messenger when the sampler is at the selected water depth (e.g. Kahlsico Water Sampler or an approved similar instrument).

SAMPLE CONTAINER AND STORAGE

4.3.12. Water samples for suspended solids measurement should be collected in high-density polythene bottles, packed in ice (cooled to 4°C without being frozen), and delivered to ALS Technichem (HK) Pty Ltd. as soon as possible after collection for analysis.

WATER DEPTH DETECTOR

4.3.13. A portable, battery-operated echo sounder shall be used for the determination of water depth at each designated monitoring station. This unit can either be handheld or affixed to the bottom of the workboat, if the same vessel is to be used throughout the monitoring programme.

SALINITY

4.3.14. A portable salinometer capable of measuring salinity in the range of 0-40 ppt shall be provided for measuring salinity of the water at each of monitoring location.

MONITORING POSITION EQUIPMENT

4.3.15. A hand-held or boat-fixed type digital Global Positioning System (GPS) with waypoint bearing indication or other equivalent instrument of similar accuracy shall be provided and used during

monitoring to ensure the monitoring vessel is at the correct location before taking measurements.

CALIBRATION OF IN-SITU INSTRUMENTS

4.3.16. All in-situ monitoring instrument shall be checked, calibrated and certified by a laboratory accredited under HOKLAS or equivalent before use, and subsequently re-calibrated at 3 monthly intervals throughout all stages of the water quality monitoring. Responses of sensors and electrodes should be checked with certified standard solutions before each use. Wet bulb calibration for a DO meter shall be carried out before measurement at each monitoring location.

4.3.17. For the on site calibration of field equipment by the ET, the BS 127:1993, "Guide to Field and on-site test methods for the analysis of waters" should be observed.

4.3.18. Sufficient stocks of spare parts should be maintained for replacements when necessary. Backup monitoring equipment shall also be made available so that monitoring can proceed uninterrupted even when some equipment is under maintenance, calibration, etc.

4.3.19. Current calibration certificates of equipments are presented in ***Appendix 4.2***.

LABORATORY MEASUREMENT / ANALYSIS

4.3.20. Analysis of suspended solids has been carried out in a HOKLAS accredited laboratory, ALS Technichem (HK) Pty Ltd. Water samples of about 1L shall be collected at the monitoring stations for carrying out the laboratory SS determination. The SS determination work shall start within 24 hours after collection of the water samples. The SS determination shall follow APHA 19ed or equivalent methods subject to the approval of IEC and EPD.

ENHANCED WATER QUALITY MONITORING IN THE EX-WAN CHAI PUBLIC CARGO WORKING AREA AND THE CAUSEWAY BAY TYPHOON SHELTER

4.3.21. The enhanced water quality monitoring and audit programme is to avoid aggravation of odour nuisance from seawater arising from temporary reclamation in the ex-Wan Chai Public Cargo Working Area and the Causeway Bay Typhoon Shelter.

4.3.22. Dissolved oxygen monitoring at the intakes C6 and C7 in Causeway Bay Typhoon Shelter when there is temporary reclamation in Causeway Bay Typhoon Shelter and at the south-western and south-eastern corners of the ex-Wan Chai Public Cargo Working Area. The proposed water quality monitoring stations of the Project are shown in ***Table 4.5*** and ***Figure 4.1***.

Table 4.5 Marine Water Quality Stations for Enhanced Water Quality Monitoring

Station	Location
C6	Excelsior Hotel
C7	Windsor House
Ex-WPCWA-SW	South-western of the ex-Wan Chai Public Cargo Working Area
Ex-WPCWA-SE	South-eastern of the ex-Wan Chai Public Cargo Working Area

Remarks:

1. Enhanced DO monitoring at Windsor House Cooling (Station Ref: C7) was temporarily suspended since 22 October 2014 with respect to the formation of temporary reclamation zone TS3 and to be resumed upon removal of the respective temporary reclamation zone.
2. Enhanced DO monitoring at Monitoring station Ex-WPCWA SE was temporarily suspended from 31 August 2015 with respect to seawall reinstatement works and formation of active works area. The Enhance DO monitoring at Ex-WPCWA SE was resumed on 11 May 2016 due to completed section of seawall reinstatement works at Ex-PCWA.

4.3.23. The monitoring of dissolved oxygen are to be carried out 3 days per week, at mid-flood and mid-ebb tides for 3 water depths (1m below water surface, mid-depth and 1m above sea bed, except where the water depth less than 6m, the mid-depth may be omitted. If the water depth be equal to or less than 3m, only the mid-depth will be monitored).

DAILY SS MONITORING AND 24 HOURS TURBIDITY MONITORING SYSTEM

4.3.24. During dredging of the sediment at the south-western corner of the Causeway Bay Typhoon Shelter, daily monitoring of suspended solids and 24 hour monitoring of turbidity at the cooling water intakes (C6 and C7) shall be conducted.

4.3.25. The 24 hours monitoring of turbidty at the cooling water intakes (C6 and C7) shall be established by setting up a continuous water quality monitoring station in front of the intakes during the dredging activities. The monitoring system include the turbidity sensor and data logger which is capable of data capturing at every 5 minutes. The data sahll be downloaded daily and compared with the Action and Limit level determined during the baseline water qualtiy monitoring at the cooling water intake locations.

ADDITIONAL DISSOVLED OXYGEN MONITORING FOR CULVERT L WATER DISCHARGE FLOW

4.3.26. In response to the Condition 2.18 of the Environmental Permit no. EP-356/2009 requiring that a silt curtain / impermeable barrier system be installed to channel water discharge flow from Culvert L to locations outside the embayment area, a proposed replacement of the requirement with additional dissolved oxygen monitoring has been conducted at three monitoring stations, namely A, B and C between the eastern seawall of Central Reclamation Phase III and the HKCEC Extension since November 2011 under EP-356/2009 so that DO level between the eastern seawall of Central Reclamation Phase II and the HKCEC extension could be continuously monitored.

4.3.27. With respect to the commencement of dredging works under HK/2012/08 and the installation of MTR precast protection unit, the enhanced water quality monitoring for Culvert L was temporarily suspended since 24 July 2013

4.3.28. The monitoring of dissolved oxygen are to be carried out once per week, at mid-flood and mid-ebb tides for 3 water depths (1m below water surface, mid-depth and 1m above sea bed, except where the water depth less than 6m, the mid-depth may be omitted. If the water depth be equal to or less than 3m, only the mid-depth will be monitored).

5. Monitoring Results

5.0.1. The environmental monitoring will be implemented based on the division of works areas of each designed project managed under different contracts with separate FEP applied by individual contractors. Overall layout showing work areas of various contracts, latest status of work commencement and monitoring stations is shown in ***Figure 2.1*** and ***Figure 4.1***. The monitoring results are presented in according to the Individual Contract(s).

5.0.2. In the reporting month, the concurrent contracts are as follows:

- Contract no. HK/2009/01 – Wan Chai Development Phase II – Central-Wan Chai Bypass at Hong Kong Convention and Exhibition Centre; and
- Contract no. HK/2009/02 Wan Chai Development Phase II – Central-Wan Chai Bypass at Wan Chai East
- Contract no. HY/2009/15 - Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)
- Contract no. HY/2009/19- Central- Wan Chai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link
- Contract no. HK/2012/08 – Wan Chai Development Phase II – Central- Wan Chai Bypass at Wan Chai West
- Contract no. HY/2010/08 – Central- Wanchai Bypass Tunnel (Slip Road 8 Section)

5.0.3. The environment monitoring schedules for reporting month and coming month are presented in ***Appendix 5.1***.

5.1 Noise Monitoring Results

Contract no. HK/2009/01 - Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC, Contract no. HK/2009/02 - Wan Chai Development Phase II – Central – Wan Chai Bypass at WanChai East

5.1.1. The proposed division of noise monitoring stations are summarized in ***Table 5.1*** below.

Table 5.1 Noise Monitoring Station for Contract nos. HK/2009/01 and HK/2009/02

Station	Description
M1a	Footbridge for Ex-Harbour Road Sports Centre

5.1.2. No action and limit level exceedance recorded in this reporting month.

5.1.3. Noise monitoring results measured in this reporting period are reviewed and summarized. Details of noise monitoring results and graphical presentation can be referred in ***Appendix 5.2.***

Contract no. HY/2009/15 - Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)

5.1.4. The noise monitoring for HY/2009/15 was commenced on 10 November 2010. The proposed division of noise monitoring stations are summarized in ***Table 5.2*** below.

Table 5.2 Noise Monitoring Station for Contract no. HY/2009/15

Station	Description
M2b	Noon Gun Area
M3a	Tung Lo Wan Fire Station

5.1.5. No action or limit level exceedance was recorded in this reporting month.

5.1.6. Noise monitoring results measured in this reporting period are reviewed and summarized. Details of noise monitoring results and graphical presentation can be referred in **Appendix 5.2.**

Contract no. HY/2009/19- Wan Chai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

5.1.7. The proposed division of noise monitoring stations are summarized in ***Table 5.3*** below.

Table 5.3 Noise Monitoring Station for Contract no. HY/2009/19

Station	Description
M4b	Victoria Centre
M5b	City Garden
M6	HK Baptist Church Henrietta Secondary School

5.1.8. No action or limit level exceedance was recorded in this reporting month.

5.1.9. Noise monitoring results measured in this reporting period are reviewed and summarized. Details of noise monitoring results and graphical presentation can be referred in ***Appendix 5.2.***

Contract no. HY/2010/08-Central-Wanchi Bypass Tunnel (Slip Road 8 Section)

5.1.10. The proposed division of noise monitoring stations are summarized in **Table 5.4** below.

Table 5.4 Noise Monitoring Station for Contract no. HY/2010/08

Station	Description
M2b	Noon Gun Area
M3a	Tung Lo Wan Fire Station

5.1.11. No action or limit level exceedance was recorded in this reporting month.

5.1.12. Noise monitoring results measured in this reporting period are reviewed and summarized. Details of noise monitoring results and graphical presentation can be referred in ***Appendix 5.2.***

5.2 Air Monitoring Results

Contract no. HK/2009/01 - Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

5.2.1 Air monitoring was commenced on 1 April 2011 in response to the commencement of the land-filling work for Contract no. HK/2009/01. The proposed divisions of air monitoring stations are summarized in ***Table 5.5*** below.

Table 5.5 Air Monitoring Stations for Contract no. HK/2009/01

Station	Description
CMA5b	Pedestrian Plaza
CMA6a	WDII PRE Site Office

5.2.2 One 1hr TSP action level exceedance was recorded at CMA5b – Pedestrian Plaza on 26 October 2017.

5.2.3 No construction works was undertaken around the monitoring location on 26 October 2017 under Contractor of HK/2009/01 and no particular observation regarding air quality impact was observed during sampling. Nevertheless, non WDII-CWB Project construction activities was observed opposite to the monitoring station on the monitoring date. Meanwhile, it was noted that the EPD AQHI for Causeway Bay District was recorded as level 7 during the monitoring period, indicating a high level of air pollution in the area affecting the ambient air quality condition. In view of the above, the exceedance was considered to be non-project related and generally contributed by ambient air quality condition.

5.2.4 Air quality monitoring results measured in this reporting period are reviewed and summarized. Details of air monitoring results and graphical presentation can be referred in ***Appendix 5.3***.

Contract no. HK/2009/02 - Wan Chai Development Phase II – Central – Wan Chai Bypass at WanChai East

5.2.5 Air monitoring was commenced in mid-January 2011 for the land-filling work for Contract no. HK/2009/02. The proposed division of air monitoring stations are summarized in ***Table 5.6*** below.

Table 5.6 Air Monitoring Station for Contract no. HK/2009/02

Station	Description
CMA4a	Society for the Prevention of Cruelty to Animals

5.2.6 No action or limit level recorded in this reporting month. Air quality monitoring results measured in this reporting period are reviewed and summarized. Details of air monitoring results and graphical presentation can be referred in ***Appendix 5.3***.

Contract no. HY/2009/15 - Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)

5.2.7 Air monitoring was commenced on 15 March 2011 for the land filling work for Contract no. HY/2009/15. The proposed division of air monitoring stations are summarized in ***Table 5.7*** below.

Table 5.7 Air Monitoring Station for Contract no. HY/2009/15

Station	Description
CMA3a	CWB PRE Site Office

5.2.8 No action or limit exceedance was recorded in the reporting month. Air quality monitoring results measured in this reporting period are reviewed and summarized. Details of air monitoring results and graphical presentation can be referred in ***Appendix 5.3***.

Contract no. HY/2009/19- Wan Chai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

5.2.9 The proposed division of air monitoring stations are summarized in ***Table 5.8*** below.

Table 5.8 Air Monitoring Stations for Contract no. HY/2009/19

Station	Description
CMA1b	Harbour Grand Hotel Boundary Wall
CMA2a	Causeway Bay Community Centre

5.2.10 One 1hr TSP limit level exceedance was recorded at CMA1b – Harbour Grand Hotel Boundary Wall on 26 October 2017.

5.2.11 Despite excavation, breaking works and pile head trimming works were undertaken around the monitoring location on the monitoring date at the under Contractor of HY/2009/19 on 26 October 2017, dust mitigation measure including water spraying for breaking works and haul road were generally implemented by the Contractor. Meanwhile, it was observed that vehicle exhaust from non-construction works was observed as the major factor affecting the monitoring station during monitoring period. In view of the above, the exceedance was considered as non-Project related.

5.2.12 Air quality monitoring results measured in this reporting period are reviewed and summarized. Details of air monitoring results and graphical presentation can be referred in ***Appendix 5.3***.

Contract no. HK/2012/08- Wan Chai Development Phase II – Central-Wan Chai Bypass at Wan Chai West

5.2.13 The proposed division of air monitoring stations are summarized in ***Table 5.9*** below.

Table 5.9 Air Monitoring Stations for Contract no. HK/2012/08

Station	Description
CMA5b	Pedestrian Plaza

5.2.14 One 1hr TSP action level exceedance was recorded at CMA5b – Pedestrian Plaza on 26 October 2017.

5.2.15 Road and drains works was undertaken under Contract HK/2012/08 around the monitoring location on 26 October 2017 and no particular observation regarding air quality impact was observed during sampling. Nevertheless, non WDII-CWB Project construction activities was observed opposite to the monitoring station on the monitoring date and dust mitigation including water spraying for haul road was generally implemented. Meanwhile, it was noted that the EPD AQHI for Causeway Bay District was recorded as Level 7 during the monitoring period, indicating a high level of air pollution in the area affecting the ambient condition. In view of the above, the exceedance was considered to be non-project related and potentially contributed by ambient air quality condition.

5.2.16 Air quality monitoring results measured in this reporting period are reviewed and summarized. Details of air monitoring results and graphical presentation can be referred in ***Appendix 5.3***.

Contract no. HY/2010/08- Central-Wanchai Bypass Tunnel (Slip Road 8 Section)

The proposed division of air monitoring stations are summarized in ***Table 5.10*** below.

Table 5.10 Air Monitoring Stations for Contract no. HY/2010/08

Station	Description
CMA3a	CWB PRE Site Office

5.2.17 No action or limit level exceedance was recorded in the reporting month. Air quality monitoring results measured in this reporting period are reviewed and summarized. Details of air monitoring results and graphical presentation can be referred in ***Appendix 5.3***.

5.3 Water quality monitoring Results

5.3.1. Action and Limit level of water quality monitoring was transited from wet season to dry season from 1 October 2017.

5.3.2. Water quality monitoring station C7 and Enhance DO monitoring station C6 shall be associated with Contract HY/2010/08, upon confirmation of marine construction works completion under Contract HY/2009/15 at CBTS area and Ex-PCWA area since 19 June 2017.

5.3.3. Referring to CWB RSS confirmation on the completion of marine construction activities within the Ex-PCWA area and the completion of the post construction water quality monitoring, the

respective Enhance DO Monitoring within Ex-PCWA for monitoring station Ex-PCWA SE and Ex-PCWA SW was temporarily suspended since 07 March 2017 ebb tide onwards.

5.3.4. With respect to the reinstatement of the silt screen system for Cooling Water Intakes P7, P8, P9 and WSD Water Intake RW21, the respective water quality monitoring was reverted to the previous monitoring location for Water Quality Monitoring Station RW21-P789 from water quality stations RW21-P789 East (RW21-P789E) and RW21-P789 West (RW21-P789W) from 25 January 2017 onwards.

5.3.5. With respect to the temporarily suspension of marine construction works at WCR3 Area by Contract HK/2009/02, the installed silt screen for intake group (P7, P8, P9 and WSD21) was removed on 26 November 2016.

5.3.6. As advised by the Contractor of HK/2009/01, all silt screen remains removal works at P1, P3, P4, P5 and C1 water quality monitoring stations were completed on 8 May 2016.

5.3.7. With respect to the marine works undertaken at WCR3 by Contract HK/2009/02, the respective water quality monitoring station C1 associated with Contract HK/2009/01 was updated as in association with Contract HK/2009/01 and Contract HK/2009/02.

5.3.8. With respect to the marine works undertaken at CBTS by Contract HY/2010/08, the respective water quality monitoring station C7 associated with Contract HY/2009/15 was updated as in association with Contract HY/2009/15 and Contract HY/2010/08.

5.3.9. With respect to the marine works undertaken at HKCEC2 by Contract HK/2012/08, the respective water quality monitoring station WSD19, P1, P3, P4, and P5 were associated with Contract HK/2012/08.

Table 5.11 Water quality Monitoring Stations for contracts with respect to remaining DP3 work areas after the completion of DP5 & DP6 in 2012 and intake diversion in 2013

Contract No.	**Remaining DP3 and work area(s)**	**Relevant Water quality monitoring Stations,**	**Division of WQM w.r.t tentative works commenced / to be commenced**
HK/2009/01	WCR3	C1[1]	Apr 2013
HK/2009/02	WCR3, WCR4, TWCR4	RW21-P789[2], C1[1]	Apr 2013
HK/2012/08	HKCEC2W, HKCEC2E	WSD19, P1[3], P3[3], P4[3], P5[3]	Aug 2013
HY/2009/15	TCBR2, TCBR3, TCBR1W, TPCWAE, TPCWAW	C6, C7, Ex-WPCWA SW, Ex-WPCWA SE (plus enhanced DO monitoring)	Nov 2010
HY/2010/08	TCBR3, TCBR4	C6[4], C7 (plus enhanced DO monitoring)	Mar 2014

Remarks:

1. The water quality monitoring station C1 shall be associated with Contract No. HK/2009/02 upon commencement of marine works under DP3 at WCR3 area.

2. 4 intakes (re-provisioned Wanchai WSD intake, Great Eagle Centre, China Resources Centre & Sun Hung Kai Centre constructed adjacent to each other) taken as a single group for silt screen protection and monitoring. Re-provisioned intake reference: P1: HKCEC Phase 1; P3: APA, P4: Shui On; P5: Government Buildings (Wanchai Tower / Revenue Tower / Immigration Tower)
3. The water quality monitoring stations for WSD19, P1, P3, P4, P5 shall be associated with Contract No. HK/2009/01 prior to their transition to Contract HK/2012/08.
4. Enhance DO monitoring station C6 and water quality monitoring station C7 shall be associated with Contract HY/2010/08, upon confirmation of marine construction works completion under Contract HY/2009/15 at CBTS area and Ex-PCWA area since 19 June 2017.

Contract no. HK/2009/01 - Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

5.3.10 Water quality monitoring for Contract no. HK/2009/01 was commenced on 23 July 2010. The proposed division of water quality monitoring stations are summarized in ***Table 5.12*** below.

Table 5.12 Water quality monitoring Stations for Contract no. HK/2009/01

Station Ref.	Location	Easting	Northing
Cooling Water Intake			
C1	HKCEC Extension	835885.6	816223.0

5.3.11 There were 3 action and 7 limit level of turbidity exceedances recorded at C1 on 3, 5, 7, 9, 11, 14, 16, 23 and 25 October 2017.

5.3.12 After checking with the Contractor, no marine construction activity was conducted on 3, 5, 7, 9, 11, 14, 16, 23 and 25 October 2017. In view of no marine construction activity was conducted, the exceedances were considered not related to Project works.

5.3.13 Water quality monitoring results measured in this reporting period are reviewed and summarized. Details of water quality monitoring results and graphical presentation can be referred in ***Appendix 5.4.***

Contract no. HK/2009/02 - Wan Chai Development Wan Chai Development Phase II – Central – Wan Chai Bypass at WanChai East

5.3.14 Water quality monitoring for Contract no. HK/2009/02 was commenced on 8 July 2010. The proposed division of water quality monitoring stations are summarized in ***Table 5.13*** below.

Table 5.13 Water quality Monitoring Stations for Contract no. HK/2009/02

Station Ref.	Location	Easting	Northing
Cooling Water Intake			
C1	HKCEC Extension	835885.6	816223.0
Cooling Water Intake / WSD Salt Water Intake			
RW21-P789	Great Eagle Centre/ Sun Hung Kai Centre/ WSD Wanchai salt water intake / China Resources	836268.0	816020.0

Station Ref.	Location	Easting	Northing
Cooling Water Intake			
C1	HKCEC Extension	835885.6	816223.0
	Building		

5.3.15 There were 3 action and 7 limit level of turbidity exceedances recorded at C1 on 3, 5, 7, 9, 11, 14, 16, 23 and 25 October 2017.

5.3.16 After checking with the Contractor, no marine construction activity was conducted on 3, 5, 7, 9, 11, 14, 16, 23 and 25 October 2017. In view of no marine construction activity was conducted, the exceedances were considered not related to Project works.

5.3.17 There were 1 action level of DO exceedance, 3 action and 6 limit level of turbidity exceedances and 1 limit level of suspended solid exceedance recorded at RW21-P789 on 9, 11, 14, 16, 18, 20, 23 and 25 October 2017.

5.3.18 After checking with the contractor, no marine construction activity was conducted on 9, 11, 14, 16, 18, 20, 23 and 25 October 2017, and the installed silt screen was observed generally in order. In view of the above, the exceedance was considered not project related.

5.3.19 Water quality monitoring results measured in this reporting period are reviewed and summarized. Details of water quality monitoring results and graphical presentation can be referred in ***Appendix 5.4.***

Contract no. HK/2012/08 - Wan Chai Development Phase II – Central- Wan Chai Bypass at Wan Chai West

5.3.20 Water quality monitoring for Contract no. HK/2012/08 was commenced on 5 March 2013. The proposed division of water quality monitoring stations are summarized in ***Table 5.14*** below.

Table 5.14 Water quality Monitoring Stations for Contract no. HK/2012/08

Station Ref.	Location	Easting	Northing
WSD Salt Water Intake			
WSD19	Sheung Wan	833415.0	816771.0
Cooling Water Intake			
P1	HKCEC Phase I	835774.7	816179.4
P3	The Academy of performing Arts	835824.6	816212.0
P4	Shui on Centre	835865.6	816220.0
P5	Government Buildings (Wanchai Tower / Revenue Tower / Immigration Tower)	835895.2	816215.2

5.3.21 There were 1 action level of DO exceedance, 4 action and 10 limit level of turbidity exceedances, and 2 action and 4 limit level of suspended solid exceedances recorded at WSD19 on 3, 7, 9, 11, 14, 16, 18, 20, 23 and 25 October 2017.

5.3.22 After checking with the contractor, no marine construction activity was conducted on 3, 7, 9, 11, 14, 16, 18, 20, 23 and 25 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

5.3.23 There were 1 action and 2 limit level of turbidity exceedances recorded at P1 on 9, 16 and 25 October 2017.

5.3.24 After checking with the contractor, no marine construction activity was conducted on 9, 16 and 25 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

5.3.25 There were 2 action and 3 limit level of turbidity exceedances recorded at P3 on 9, 11, 14, 16 and 23 October 2017.

5.3.26 After checking with the contractor no marine construction activity was conducted 9, 11, 14, 16 and 23 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

5.3.27 There were 3 action and 7 limit level of turbidity exceedances, and 2 action level of suspended solid recorded at P4 on 3, 5, 9, 11, 14, 16, 23 and 25 October 2017.

5.3.28 After checking with the contractor no marine construction activity was conducted 3, 5, 9, 11, 14, 16, 23 and 25 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

5.3.29 There were 4 action and 6 limit level of turbidity exceedances recorded at P5 on 3, 7, 9, 11, 14, 16, 23 and 25 October 2017.

5.3.30 After checking with the contractor no marine construction activity was conducted 3, 7, 9, 11, 14, 16, 23 and 25 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

5.3.31 Water quality monitoring results measured in this reporting period are reviewed and summarized. Details of water quality monitoring results and graphical presentation can be referred in ***Appendix 5.4.***

Contract no. HY/2010/08- Central-Wanchai Bypass Tunnel (Slip Road 8 Section)

5.3.32 The proposed division of water quality monitoring stations are summarized in ***Table 5.15*** and **Table 5.16** below:

Table 5.15 Water quality monitoring Stations for Contract no. HY/2010/08

Station Ref.	Location	Easting	Northing
Cooling Water Intake			
C7	Windsor House	837193.7	816150.0

Table 5.16 Enhance Dissolved Oxygen Monitoring Stations for Contract no. HY/2010/08

Station Ref.	Location
C6	Excelsior Hotel

Remarks:

1. Enhanced DO monitoring at Windsor House Cooling (Station Ref: C7) was temporarily suspended since 22 October 2014 with respect to the formation of temporary reclamation zone TS3 and to be resumed upon removal of the respective temporary reclamation zone.

5.3.33 There were 2 action and 2 limit level of turbidity and 1 limit level of suspended solid exceedances recorded at C7 on 7 and 9 October 2017.

5.3.34 Underwater diaphragm wall cleaning works was conducted adjacent to the monitoring location on 7 and 9 October 2017, and the works was considered as the major contribute to the affected water quality. Meanwhile, the installed silt screen for Windsor House Water Intake was found incomplete according to the submitted Silt Screen Deployment Plan. As such, it was considered that the turbidity and suspended solid exceedances were related to HY/2010/08 Project works.

5.3.35 There was 1 limit level of turbidity exceedance recorded at C7 on 25 October 2017.

5.3.36 Underwater diaphragm wall cleaning works was conducted adjacent to the monitoring location on 25 October 2017 while impermeable barrier deployed was not fully enclosing the works area and affecting the water quality at the concerned Windsor House cooling water intake during monitoring sampling. As such, it was considered that the turbidity exceedance was related to HY/2010/08 Project works.

5.3.37 Water quality monitoring results measured in this reporting period are reviewed and summarized. Details of water quality monitoring results and graphical presentation can be referred in **Appendix 5.4**.

5.4 Waste Monitoring Results

Contract no. HK/2009/01 - Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

5.4.1. No inert C&D waste and non- inert C&D waste disposed in this reporting month. Details of the waste flow table are summarized in ***Table 5.17.***

Table 5.17 Details of Waste Disposal for Contract no. HK/2009/01

Waste Type	Quantity this month	Cumulative Quantity-to-Date	Disposal / Dumping Grounds
Inert C&D materials disposed, m^3	NIL	62116.405	TKO137, TM38
Inert C&D materials recycled, m^3	NIL	5856.5	N/A
Non-inert C&D materials disposed, m^3	NIL	1673.69	SENT Landfill
Non-inert C&D materials recycled, kg	NIL	203993	N/A
Chemical waste disposed, kg	NIL	10250	N/A
Marine Sediment (Type 1 – Open Sea Disposal), m^3	NIL (Bulk Volume)	97428.2 (Bulk Volume)	South of Cheung Chau
Marine Sediment (Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal) , m^3	NIL (Bulk Volume)	52250 (Bulk Volume)	East of Cha Chau
Dredged Sediment Requiring Type 3 – Special Treatment / Disposal contained in Geosynthetic Containers	NIL (Bulk Volume)	6773 (Bulk Volume)	East of Cha Chau

5.4.2. There were no marine sediment Type 1- Open Sea Disposal and no marine sediments Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal disposed in this reporting month.

Contract no. HK/2009/02 - Wan Chai Development Phase II – Central – Wan Chai Bypass at Wan Chai East

5.4.3. No inert C&D waste and Non-inert C&D waste disposed of in this reporting month. Details of the waste flow table are summarized in ***Table 5.18.***

Table 5.18 Details of Waste Disposal for Contract no. HK/2009/02

Waste Type	Quantity this month	Cumulative Quantity-to-Date	Disposal / Dumping Grounds
Inert C&D materials disposed, m^3	NIL	276075.1	TKO137 / TM 38
Inert C&D materials recycled, m^3	NIL	18161	N/A
Non-inert C&D materials disposed, m^3	NIL	1515.103	SENT Landfill
Non-inert C&D materials recycled, m^3	N/A	N/A	N/A
Chemical waste disposed, kg	NIL	13860	SENT Landfill
Marine Sediment (Type 1 – Open Sea Disposal), m^3	NIL	240222 (Bulk volume)	South of Cheung Chau
Marine Sediment (Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal) , m^3	NIL	146445 (Bulk volume)	East of Sha Chau

5.4.4. There were no marine sediment Type 1 – Open Sea Disposal and no Type 1 Open Sea Disposal (Dedicate Sties) & Type 2 – Confined Marine Disposal disposed in this reporting month.

Contract no. HY/2009/15 - Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)

5.4.5. No Inert and non-inert C&D material was recycled in this reporting month. Details of the waste flow table are summarized in ***Table 5.19***

Table 5.19 Details of Waste Disposal for Contract no. HY/2009/15

Waste Type	Quantity this month	Cumulative Quantity-to-Date	Disposal / Dumping Grounds	Remarks
Inert C&D materials disposed, m^3	NIL	141579.2	Tuen Mun Area 38	NIL
	NIL	65216	TKO137 FB	NIL
Inert C&D materials recycled, m^3	NIL	8127.21	HY/2010/08	NIL
	NIL	304	Ex-PCWA	NIL
	NIL	111.9	TS4	NIL
Non-inert C&D materials disposed, m^3	NIL	252.2	SENT Landfill	NIL

Waste Type	Quantity this month	Cumulative Quantity-to-Date	Disposal / Dumping Grounds	Remarks
Non-inert C&D materials recycled, kg	NIL	299361.5	N/A	NIL
Chemical waste disposed, kg	NIL	8,200	N/A	NIL
Marine Sediment (Type 1 – Open Sea Disposal), m^3	NIL (Bulk Volume)	156909 (Bulk Volume)	Cheung Chau South	Dredging from TCBR1E / TCBR1W / TCBR2/ TCBR3 / TCBR4 / Maintenance dredging
Marine Sediment (Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal) , m^3	NIL (Bulk Volume)	327746 (Bulk Volume)	East of Sha Chau / South of the Brothers	Dredging from TCBR1E / TCBR1W / TCBR2/ TCBR3 / TCBR4 / Maintenance dredging
Marine Sediment (Type 3 – Special Treatment / Disposal contained in Geosynthetic Containers) m^3	NIL (Bulk Volume)	12640 (Bulk Volume)	East of Sha Chau / South of the Brothers	Dredging from TCBR1W / Maintenance dredging
Marine Sediment (Type 2 – Confined Marine Disposal), m^3	NIL	9350 (Bulk Volume)	East of Sha Chau	Dredging from Eastern Breakwater of CBTS
Marine Sediment (Type 1 – Open Sea Disposal) , m3	NIL (Bulk Volume)	600 (Bulk Volume)	East Sha Chau / South of The Brothers	Dredging from Phase 3 Mooring Re-arrangement
Marine Sediment (Type 2– Confined Marine Disposal) , m3	NIL (Bulk Volume)	14,780 (Bulk Volume)	South of The Brothers	Dredging from Phase 3 Mooring Re-arrangement
Marine Sediment (Type 3 – Special Treatment / Disposal contained in Geosynehetic Containers) , m3	NIL (Bulk Volume)	2,760 (Bulk Volume)	South of The Brothers	Dredging from Phase 3 Mooring Re-arrangement

5.4.6. There was no Type 1 Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal and Type 1 Open Sea Disposal disposed in this reporting month.

Contract no. HY/2009/19 –Central- WanChai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

5.4.7. No inert C&D waste and non-inert C&D waste disposed in this reporting month. Details of the waste flow table are summarized in ***Table 5.20.***

Table 5.20 Details of Waste Disposal for Contract no. HY/2009/19

Waste Type	Quantity this month	Cumulative Quantity-to-Date	Disposal / Dumping Grounds
Inert C&D materials disposed, m^3	NIL	355921.04	TM38
Inert C&D materials recycled, m^3	NIL	59367	N/A
Non-inert C&D materials disposed, m^3	NIL	1068.6	N/A
Non-inert C&D materials recycled, kg	NIL	333.14	N/A
Chemical waste disposed, L	NIL	2.12	N/A
Marine Sediment (Type 1 – Open Sea Disposal), m^3	NIL	162	South Cheung Chau
Marine Sediment (Type 2 – Confined Marine Disposal) , m^3	NIL	681	East Sha Chau
Marine Sediment (Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal) , m3	NIL	4976.00	East Sha Chau

5.4.8. There was no marine sediment Type1- Open Sea Disposal and there was no Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal disposed in this reporting month.

Contract no. HK/2012/08 –Wan Chai Development Phase II – Central- Wan Chai Bypass at Wan Chai West

5.4.9. There was no Inert C&D waste and no non-inert C&D waste was disposed in this reporting month. Details of the waste flow table are summarized in ***Table 5.21.***

Table 5.21 Details of Waste Disposal for Contract no. HK/2012/08

Waste Type	Quantity this month	Cumulative Quantity-to-Date	Disposal / Dumping Grounds
Inert C&D materials disposed, m^3 *	NIL NIL	4131 273	TM38 TKO137
Inert C&D materials recycled, m^3	NIL	NIL	N/A
Non-inert C&D materials	NIL	400	SENT

Waste Type	Quantity this month	Cumulative Quantity-to-Date	Disposal / Dumping Grounds
disposed, m^3			
Non-inert C&D materials recycled, kg	NIL	NIL	N/A
Chemical waste disposed, L	NIL	NIL	N/A
Marine Sediment (Type 1 – Open Sea Disposal), m^3	NIL (Bulk volume)	31759 (Bulk volume)	South of Cheung Chau
Marine Sediment (Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal) , m3	NIL (Bulk volume)	108542 (Bulk volume)	South of The Brothers (from 27 Aug 2013 onwards)

5.4.10. There was no Marine Sediment Type 1 – Open Sea Disposal (Delicate Sites) & Type 2 – Confined Marine Disposal and Marine Sediment Type 1 – Open Sea Disposal disposed in this reporting month.

Contract no. HY/2010/08 –Central - Wan Chai Bypass (CWB) –Tunnel (Slip Road 8)

5.4.11. No Inert C&D waste was disposed in this reporting month and no non-inert C&D waste disposed in this reporting month. Details of the waste flow table are summarized in ***Table 5.22***

Table 5.22 Details of Waste Disposal for Contract no. HY/2010/08

Waste Type	Quantity this month	Cumulative Quantity-to-Date	Disposal / Dumping Grounds
Inert C&D materials disposed, m^3	NIL NIL	91432.537 19739.4	TM38 TKO137
Inert C&D materials recycled, m^3	NIL	NIL	N/A
Non-inert C&D materials disposed, m^3	NIL	NIL	N/A
Non-inert C&D materials recycled, kg	NIL	NIL	N/A
Chemical waste disposed, L	NIL	NIL	N/A
Marine Sediment (Type 1 – Open Sea Disposal)	NIL	62559.4	South Cheung Chau / Brothers Island *
Marine Sediment (Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine disposal)	NIL	28309.2	Brothers Island
Marine Sediment (Type 3 – Special Treatment)	NIL	7780	Brothers Island

5.4.12. There were no Type 1 – Open Sea Disposal and no Type 1 – Open Sea Disposal (Dedicate Sites) & Type 2 – Confined Marine Disposal disposed in this reporting month, and no Type 3-Special Treatment disposed in this reporting month.

6. Compliance Audit

6.0.1. The Event Action Plan for construction noise, air quality and water quality are presented in ***Appendix 6.1***.

6.1 Noise Monitoring

Contract no. HK/2009/01 - Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

6.1.1 No action or limit level exceedance was recorded in this reporting month.

Contract no. HK/2009/02 - Wan Chai Development Phase II – Central – Wan Chai Bypass at WanChai East

6.1.2 No action or limit level exceedance was recorded in this reporting month.

Contract no. HY/2009/15 - Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)

6.1.3 No exceedance was recorded in the reporting month.

Contract no. HY/2009/19 – Central – Wanchai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

6.1.4 No exceedance was recorded in the reporting month.

Contract no. HY/2010/08 – Central-Wanchai Bypass – Tunnel (Slip Road 8 Section)

6.1.5 No exceedance was recorded in the reporting month.

6.2 Air Monitoring

Contract no. HK/2009/01 - Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

6.2.1 One 1hr TSP action level exceedance was recorded at CMA5b – Pedestrian Plaza on 26 October 2017 and the exceedance was concluded as non-Project related.

Contract no. HK/2009/02 – Wan Chai Development Phase II – Central – Wan Chai Bypass at Wan Chai East (CWB Tunnel)

6.2.2 No action or limit level exceedance was recorded in this reporting month.

Contract no. HY/2009/15 - Central-Wanchai Bypass – Tunnel (Causeway Bay Typhoon Shelter Section)

6.2.3 No action or limit level exceedance was recorded in this reporting month.

Contract no. HY/2009/19 – Central – Wanchai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

6.2.4 One 1hr TSP limit level exceedance was recorded at CMA1b – Harbour Grand Hotel Boundary Wall on 26 October 2017 and the exceedance was concluded as non-Project related.

Contract no. HK/2012/08 Wan Chai Development Phase II - Central-Wan Chai Bypass at Wan Chai West

6.2.5 One 1hr TSP action level exceedance was recorded at CMA5b – Pedestrian Plaza on 26 October 2017 and the exceedance was concluded as non-Project related.

Contract no. HY/2010/08 – Central-Wanchai Bypass – Tunnel (Slip Raod 8 Section)

6.2.6 No action or limit level exceedance was recorded in the reporting month.

6.3 Water Quality Monitoring

Contract no. HK/2009/01 - Wan Chai Development Phase II – Central –Wanchai Bypass at HKCEC

6.3.1 There were 3 action and 7 limit level of turbidity exceedances recorded at C1 on 3, 5, 7, 9, 11, 14, 16, 23 and 25 October 2017.

6.3.2 After checking with the Contractor, no marine construction activity was conducted on 3, 5, 7, 9, 11, 14, 16, 23 and 25 October 2017. In view of no marine construction activity was conducted, the exceedances were considered not related to Project works.

Contract no. HK/2009/02 - Wan Chai Development Phase II – Central – Wan Chai Bypass at WanChai East

6.3.3 There were 3 action and 7 limit level of turbidity exceedances recorded at C1 on 3, 5, 7, 9, 11, 14, 16, 23 and 25 October 2017.

6.3.4 After checking with the Contractor, no marine construction activity was conducted on 3, 5, 7, 9, 11, 14, 16, 23 and 25 October 2017. In view of no marine construction activity was conducted, the exceedances were considered not related to Project works.

6.3.5 There were 1 action level of DO exceedance, 3 action and 6 limit level of turbidity exceedances and 1 limit level of suspended solid exceedance recorded at RW21-P789 on 9, 11, 14, 16, 18, 20, 23 and 25 October 2017.

6.3.6 After checking with the contractor, no marine construction activity was conducted on 9, 11, 14, 16, 18, 20, 23 and 25 October 2017, and the installed silt screen was observed generally in order. In view of the above, the exceedance was considered not project related.

Contract no. HY/2009/19- Central- Wan Chai Bypass Tunnel (North Point Section) and Island Eastern Corridor Link

6.3.7 No action or limit level exceedance was recorded in this reporting month.

Contract no. HK/2012/08- Wan Chai Development Phase II – Central- Wan Chai Bypass at Wan Chai West

6.3.8 There were 1 action level of DO exceedance, 4 action and 10 limit level of turbidity exceedances, and 2 action and 4 limit level of suspended solid exceedances recorded at WSD19 on 3, 7, 9, 11, 14, 16, 18, 20, 23 and 25 October 2017.

6.3.9 After checking with the contractor, no marine construction activity was conducted on 3, 7, 9, 11, 14, 16, 18, 20, 23 and 25 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

6.3.10 There were 1 action and 2 limit level of turbidity exceedances recorded at P1 on 9, 16 and 25 October 2017.

6.3.11 After checking with the contractor, no marine construction activity was conducted on 9, 16 and 25 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

6.3.12 There were 2 action and 3 limit level of turbidity exceedances recorded at P3 on 9, 11, 14, 16 and 23 October 2017.

6.3.13 After checking with the contractor no marine construction activity was conducted 9, 11, 14, 16 and 23 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

6.3.14 There were 3 action and 7 limit level of turbidity exceedances, and 2 action level of suspended solid recorded at P4 on 3, 5, 9, 11, 14, 16, 23 and 25 October 2017.

6.3.15 After checking with the contractor no marine construction activity was conducted 3, 5, 9, 11, 14, 16, 23 and 25 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

6.3.16 There were 4 action and 6 limit level of turbidity exceedances recorded at P5 on 3, 7, 9, 11, 14, 16, 23 and 25 October 2017.

6.3.17 After checking with the contractor no marine construction activity was conducted 3, 7, 9, 11, 14, 16, 23 and 25 October 2017. In view of no marine construction activity, the exceedances were considered not project related.

Contract no. HY/2010/08 –Central - Wan Chai Bypass (CWB) –Tunnel (Slip Road 8)

6.3.18 There were 2 action and 2 limit level of turbidity and 1 limit level of suspended solid exceedances recorded at C7 on 7 and 9 October 2017.

6.3.19 Underwater diaphragm wall cleaning works was conducted adjacent to the monitoring location on 7 and 9 October 2017, and the works was considered as the major contribute to the affected water quality. Meanwhile, the installed silt screen for Windsor House Water Intake was found incomplete according to the submitted Silt Screen Deployment Plan. As such, it was considered that the turbidity and suspended solid exceedances were related to HY/2010/08 Project works.

6.3.20 There was 1 limit level of turbidity exceedance recorded at C7 on 25 October 2017.

6.3.21 Underwater diaphragm wall cleaning works was conducted adjacent to the monitoring location on 25 October 2017 while impermeable barrier deployed was not fully enclosing the works area and affecting the water quality at the concerned Windsor House cooling water intake during monitoring sampling. As such, it was considered that the turbidity exceedance was related to HY/2010/08 Project works.

6.4 Review of the Reasons for and the Implications of Non-compliance

6.4.1 There was no non-compliance from the site audits in the reporting period. The observations and recommendations made in each individual site audit session were presented in Section 8.

6.4.2 A project related turbidity and suspended solid exceedance were recorded at water quality monitoring station C7 on 7 and 9 October 2017. Underwater diaphragm wall cleaning works was conducted adjacent to the monitoring location on 7 and 9 October 2017, and the works was considered as the major contribute to the affected water quality. Meanwhile, the installed silt screen for Windsor House Water Intake was found incomplete according to the submitted Silt Screen Deployment Plan. As such, it was considered that the turbidity and suspended solid exceedances were related to HY/2010/08 Project works.

6.4.3 A project related turbidity exceedance was recorded at water quality monitoring station C7 on 25 October 2017. Underwater diaphragm wall cleaning works was conducted adjacent to the monitoring location on 25 October 2017 while impermeable barrier deployed was not fully enclosing the works area and affecting the water quality at the concerned Windsor House cooling water intake during monitoring sampling. As such, it was considered that the turbidity exceedance was related to HY/2010/08 Project works.

6.5 Summary of action taken in the event of and follow-up on non-compliance

6.5.1 Further to the project related turbidity and suspended solid exceedances recorded at water quality monitoring station C7 on 7 and 9 October 2017, the water turbidity level of repeated measurement at the same monitoring location on the same date and tide were conducted and confirmed the exceedance recorded. Water quality monitoring was conducted on 7 October 2017 during ebb tide at 1205hrs and action level exceedance of turbidity was recorded. Subsequent monitoring was conducted on 7 October 2017 during flood tide at 1700hrs and limit level exceedance of turbidity and suspended solid was subsequently recorded. Additional monitoring in accordance with the Event and Action Plan was conducted on 8 October 2017 and limit level exceedance of turbidity was recorded.

6.5.2 Water quality monitoring was conducted on subsequent sampling date on 9 October 2017 during flood tide at 0935hrs and action level exceedance of turbidity was recorded. Meanwhile, no further suspended solid exceedance was recorded on 9 October 2017 during flood tide at 0935hrs. Water quality monitoring was subsequently conducted on 9 October 2017 during ebb tide at 1357hrs and limit level exceedance of turbidity was recorded. Additional monitoring in accordance with the Event and Action Plan was conducted on 10 October 2017 and no further turbidity exceedance was recorded.

6.5.3 Upon identification of defects on 7 October 2017, rectification measures including reinstatement of the silt screen installed for Windsor House Water Intake; cleaning of water holding tank, and provide mitigation measures including impermeable barrier around underwater cleaning works area, as appropriate under the Contractor HY/2010/08 were implemented by 11 October 2017.

6.5.4 Further to the project related turbidity exceedance recorded at water quality monitoring station C7 on 25 October 2017, the water turbidity level of repeated measurement at the same monitoring location on the same date and tide was conducted and confirmed the exceedance recorded. Additional monitoring in accordance with the Event and Action Plan was conducted on 26 October 2017 and no further turbidity exceedance was recorded.

6.5.5 Rectification measures including i) maintained deployed impermeable barriers without openings, and ii) flushing at the affected water holding tank were implemented under the Contractor of HY/2010/08 by 26 October 2017.

7. Cumulative Construction Impact due to the Concurrent Projects

7.0.1. According to Condition 3.4 of the EP-356/2009, this section addresses the relevant cumulative construction impact due to the concurrent activities of the current projects including the Central Reclamation Phase III, Central-Wanchai Bypass and Island Eastern Corridor Link projects.

7.0.2. According to the Final EM&A Report of Central Reclamation Phase III (CRIII) for Contract HK 12/02, the major construction activities were completed by end of January 2014 and no construction activities were undertaken thereafter and the water quality monitoring was completed in October 2011 and no Project-related exceedance was recorded for air and noise monitoring. It can be concluded that cumulative construction impact due to the concurrent activities of the current projects with the Central Reclamation Phase III (CRIII) was insignificant.

7.0.3. According to the construction programme of Central-Wanchai Bypass at Wanchai West at the Central Reclamation Phase III area include road and drain works, backfilling works and reinstatement of culvert and cooling mains and reinstatement of planter at P1 road were performed in October 2017 reporting period. As no project related exceedance were recorded during the reporting period, cumulative construction impact due to the concurrent activities of the current projects with the Central Reclamation Phase III (CRIII) was considered as insignificant.

7.0.4. According to the construction programme of Wan Chai Development Phase II, Central-Wan Chai Bypass and Island Eastern Corridor Link projects, the major construction activities under Wan Chai Development Phase II were road and drains construction, tunnel construction and backfilling works at Wan Chai West and Wan Chai East. The major construction activities under Central-Wan Chai Bypass and Island Eastern Corridor Link Projects were drainage works and ventilation building construction at Central; temporary reclamation removal works at Causeway Bay, road works and side wall construction at Victoria Park; bridge construction, piling works, foundation works and building construction at North Point area in the reporting period. In addition, other non-Wan Chai Development Phase II, Central-Wan Chai Bypass and Island Eastern Corridor Link projects was observed undertaken at Wan Chai North and North Point area.

7.0.5. No significant air impact from construction activities was anticipated in the reporting month. Besides, no project related exceedance was recorded during the air and noise environmental monitoring events in the reporting month. Thus, it is evaluated that the cumulative construction impact from the concurrent projects including Central Reclamation Phase III (CRIII), Wan Chai Development Phase II (WDII), Central-WanChai Bypass (CWB), Island Eastern Corridor Link projects (IECL) was insignificant.

8. Environmental Site Audit

8.0.1. During this reporting month, weekly environmental site audits were conducted for Contracts no. HK/2009/01, HK/2009/02, HY/2009/15, HY/2009/19, HK/2012/08 and HY/2010/08. No non-conformance was identified during the site audits.

8.0.2. Four site inspections for Contract no. HK/2009/01 were conducted on 29 September 2017, 6, 13 and 20 October 2017 in reporting month. There was no particular findings observed in this reporting month.

8.0.3. Five site inspections for Contract no. HK/2009/02 were carried out on 27 September 2017, 6, 13, 17 and 26 October 2017 in reporting month. Results of these inspections and outcomes are summarized in ***Table 8.2***.

Table 8.2 Summary of Environmental Inspections for Contract no. HK/2009/02

Item	Date	Observations	Action taken by Contractor	Outcome
170927_01	27 Sep 2017	Silt screen at RW21-P789 station shall be properly maintained and ensure it is fully extended to seabed level	Silt screen was deployed orderly and maintained.	Completion as observed on 6 October 2017
171006_01	6 Oct 2017	Floating refuse within the silt curtain at RW21-P789 shall be removed.	Floating refuse within the silt curtain was removed.	Completion as observed on 13 October 2017.
171006_01	6 Oct 2017	Floating refuse within the silt curtain at RW21-P789 shall be removed.	Floating refuse within the silt curtain was removed.	Completion as observed on 13 October 2017.
171006_02	6 Oct 2017	Dust suppression measure for surface grinding at Wanchai Ferry Pier shall be implemented.	No surface grinding works was observed at Wanchai Ferry Pier and no particular dust impact was further observed.	Completion as observed on 13 October 2017.
171013_01	13 Oct 2017	The silt screen at RW21-P789 station shall be properly maintained.	Silt screen system was properly maintained.	Completion as observed on 3 November 2017
171017_01	17 Oct 2017	Water spraying shall be implemented during breaking works at Portion 3 & 4.	No breaking works was observed during inspection while ground surface remained wet and no particular dust impact was observed.	Completion as observed on 26 October 2017

8.0.4. Four site inspections for Contract no. HY/2009/15 were carried out on 27 September 2017, 6, 11 and 17 October 2017 in this reporting month. There was no particular findings observed in this reporting month.

8.0.5. Four site inspections for Contract no. HY/2009/19 were carried out on 4, 11, 17, 25 October 2017 in reporting month. There was no particular findings observed in this reporting month.

8.0.6. Four site inspections for Contract no. HK/2012/08 were carried out on 3, 10, 17 and 24 October 2017 in this reporting period. Results of these inspections and outcomes are summarized in **Table 8.5**.

Table 8.5 Summary of Environmental Inspections for Contract no. HK/2012/08

Item	Date	Observations	Action taken by Contractor	Outcome
171010_01	10-Oct-17	Water spraying on-site shall be strengthen to maintain ground surface wet	Water spraying was implemented on concerned works area	Completion as observed on 17 October 2017
171010_02	10-Oct-17	Public road outside gate exit at Slip Road 1 works area shall be maintained clean	Cleaning was provided to the public road.	Completion as observed on 17 October 2017
171017_01	17-Oct-17	Leaked oil under the excavator at Slip Road 1 shall be removed	Leaked oil under the excavator was removed	Completion as observed on 24 October 2017
171024_01	24-Oct-17	Covering shall be provided to stockpile stored on-site	The concerned stockpile was removed	Completion as observed on 31 October 2017

8.0.7. Five site inspections for Contract no. HY/2010/08 were carried out on 28 September 2017, 6, 11, 18 and 25 October 2017 in this reporting period. Results of these inspections and outcomes are summarized in **Table 8.6**.

Table 8.6 Summary of Environmental Inspections for Contract no. HY/2010/08

Item	Date	Observations	Action taken by Contractor	Outcome
171011_1	11-Oct-17	Contractor shall check and ensure the silt screen deployed on the diverted intake location shall follow the design specified under the submitted silt screen deployment plan (TS3)	Silt screen was deployed according to the submitted silt screen deployment	Completion as observed on 18 October 2017
171018_1	18-Oct-17	Impermeable barrier shall be deployed to protect the temporary cut slope to avoid muddy dispersion	Impermeable barrier was deployed to protect the temporary cut slope	Completion as observed on 25 October 2017

9. Complaints, Notification of Summons and Prosecution

9.0.1. There was no environmental complaint received in this reporting month.

9.0.2. The details of cumulative complaint log and updated summary of complaints are presented in ***Appendix 9.1***

9.0.3. Cumulative statistic on complaints and successful prosecutions are summarized in ***Table 9.1*** and ***Table 9.2*** respectively.

Table 9.1 Cumulative Statistics on Complaints

Reporting Period	No. of Complaints
Commencement works (Mar 2010) to last reporting month	47
October 2017	0
Total	**47**

Table 9.2 Cumulative Statistics on Successful Prosecutions

Environmental Parameters	Cumulative No. Brought Forward	No. of Successful Prosecutions this month (Offence Date)	Cumulative No. Project-to-Date
Air	-	0	0
Noise	-	0	0
Water	-	0	0
Waste	-	0	0
Total	**-**	**0**	**0**

10. Conclusion

10.0.1. The EM&A programme was carried out in accordance with the EM&A Manual requirements, minor alterations to the programme proposed were made in response to changing circumstances.

10.0.2. The scheduled construction activities and the recommended mitigation measures for the coming month are listed in ***Table 10.1***.

Table 10.1 Construction Activities and Recommended Mitigation Measures in Coming Reporting Month

Contract No.	Key Construction Works	Recommended Mitigation Measures
HK/2009/01	• Nil	• Nil
HK/2009/02	• Nil	• Daily visual inspection of silt screen and silt curtain to ensure its operation properly. • Implement silt curtain in accordance with the associated plans submitted to EPD.
HY/2009/15	• Nil	• Daily visual inspection of silt screen and silt curtain to ensure its operation properly • Implement silt curtain in accordance with the associated plans submitted to EPD.
HY/2009/19	• Nil	• Nil
HK/2012/08	• Construction of Box 1 unit and backfilling	• To conform the installation and setting as in the silt screen and silt curtain deployment plan • To space out noisy equipment and position as far as possible from sensitive receiver. • Daily visual inspection of silt screen and silt curtain to ensure its operation properly
HY/2010/08	• Diversion pipe maintenance • Diaphragm Wall Removal Works • Removal of reclamation at TS3E and TS3W	• To conform the installation and setting as in the silt screen and silt curtain deployment plan • Daily visual inspection of silt screen and silt curtain to ensure its operation properly

Figure 2.1

Project Layout



LEGEND:

■ WATER QUALITY MONITORING STATIONS

COOLING WATER INTAKES

C1	HONG KONG CONVENTION AND EXHIBITION CENTRE EXTENSION
C2	TELECOM HOUSE/HK ACADEMY FOR PERFORMING ARTS / SHUI ON CENTRE
C3	HONG KONG CONVENTION AND EXHIBITION CENTRE PHASE I
C4	WAN CHAI TOWER AND GREAT EAGLE CENTRE
C5	SUN HUNG KAI CENTRE
C6	PROPOSED EXHIBITION STATION / WORLD TRADE CENTRE
C7	WINDSOR HOUSE
C8	CITY GARDEN
C9	PROVIDENT CENTRE
RC1	PROPOSED HKCEC EXTENSION
RC5	SUN HUNG KAI CENTRE (REPROVISION)
RC7	WINDSOR HOUSE (TEMPORARY REPROVISION)

WSD SALT WATER INTAKE

WSD21	WAN CHAI
WSD21	WAN CHAI (REPROVISION)
WSD7	KOWLOON SOUTH
WSD9	TAI WAN
WSD10	CHA KWO LING
WSD15	SAI WAN HO
WSD17	QUARRY BAY
WSD19	SHEUNG WAN
WSD20	KENNEDY TOWN

DESIGNATED PROJECTS (DP)

DP1 — CENTRAL-WAN CHAI BYPASS (CWB) INCLUDING ITS ROAD TUNNEL AND SLIP ROADS

DP2 — ROAD P2 AND OTHER ROADS (PRIMARY / DISTRICT DISTRIBUTOR ROADS)

DP3 — PERMANENT AND TEMPORARY RECLAMATION WORKS INCLUDING ASSOCIATED DREDGING WORKS IN WAN CHAI DEVELOPMENT PHASE II (WDII) AREA

~~DP4 — TEMPORARY TYPHOON SHELTER~~ (DP4 NOT TO BE IMPLEMENTED)

DP5 — WAN CHAI EAST SEWAGE OUTFALL

DP6 — DREDGING FOR THE CROSS-HARBOUR WATER MAINS

DP1 IS COVERED BY EP - 356/2009

DP2 IS COVERED BY EP - 376/2009

DP3, DP5 AND DP6 ARE COVERED BY EP - 356/2009

WORKS CONTRACT	DESIGNATED PROJECT INVOLVED	CONSTRUCTION COMMENCEMENT
CEDD CONTRACT NO. HK/2009/01	DP1, DP3, DP6	APRIL 2010
CEDD CONTRACT NO. HK/2009/02	DP1, DP3, DP5	APRIL 2010
CEDD CONTRACT 3	DP1, DP3	END 2011
CEDD CONTRACT 4	DP1, DP3	END 2011
CEDD CONTRACT 5	DP3	2015
HyD CONTRACT NO. HY/2009/11	DP3	18 MARCH 2010
HyD CONTRACT NO. HY/2009/15	DP1, DP3	SEPTEMBER 2010
HyD CONTRACT NO. HY/2009/18	DP1	OCTOBER 2010
HyD CONTRACT NO. HY/2009/19	DP1	NOVEMBER 2010
HyD CONTRACT 12	DP1, DP3	MID 2012

CEDD 土木工程拓展署 Civil Engineering and Development Department

WAN CHAI DEVELOPMENT PHASE II

WAN CHAI DEVELOPMENT PHASE II AND CENTRAL - WAN CHAI BYPASS - SAMPLING, FIELD MEASUREMENT AND TESTING WORKS (STAGE 1)

LOCATIONS OF WATER QUALITY MONITORING STATIONS

AECOM

DRG NO. 60041297/C5/SK001

SCALE A1 1:20000

DIMENSIONS IN METRES



NOTES:
1. SETTING OUT COORDINATES REFER DRG. No. 60095653/NP/1601.
2. THE CONTRACTOR SHALL KEEP OPEN AND PROVIDE ACCESS (PEDESTRIAN AND TRAFFIC) TO THE PUBLIC AT ALL TIMES DURING THE PERIOD OF THE CONTRACTOR'S OCCUPATION OF OIL STREET. THE CONTRACTOR SHALL MAINTAIN THIS PORTION OF SITE IN A CLEAN, PASSABLE AND SAFE STATE AT ALL TIMES.
3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH DRG. No. 60095653/NP/1652.
LEGEND:
SITE BOUNDARY
PORTION NPR1A
PORTION NPR1
PORTION NPR2
PORTION NPR3
PORTION NPR4
PORTION NPR4A
PORTION NPR4B
PORTION NPR5A
PORTION NPR5B
PORTION NPR5C
PORTION NPR5D
PORTION NPR5E
ISLAND EASTERN CORRIDOR
Elevated Road
KING WAH ROAD
WANG ON ROAD
FOOK YUM ROAD
OIL STREET
WATSON ROAD
KING MING ROAD
ELECTRIC ROAD
WHITFIELD ROAD
CLASS STREET
POWER STREET
B | WORKING DRAWING | RC | BCC | DEC 09
A | TENDER ADDENDUM NO. 1 | RC | BCC | OCT 09
– | TENDER DRAWING | RC | BCC | SEP 09
Highways Department 路政署
Major Works Project Management Office
CENTRAL - WAN CHAI BYPASS AND IEC LINK
CENTRAL - WAN CHAI BYPASS - NORTH POINT RECLAMATION
PORTION OF SITE
SHEET 1 OF 2
AECOM
DRG.NO. 60095653/NP/1651B
DESIGNED BY TTF
CONTRACT NO. HY/2009/11
APPROVED CW
DRAWN BY CJH
SCALE A1 1 : 1000 A3 1 : 2000
DIMENSIONS ARE IN METRES
STATUS WORKING DRAWING
© COPYRIGHT RESERVED
p:\project\60095653\drawing\NP\1000\NP_1651.dgn


VICTORIA HARBOUR
Dredging and Backfilling Work
for
Cross Harbour Watermain
EIA-141/2007
DP6
Dredging and Backfillind Works
for HKCEC
EIA-141/2007
DP3
GLOUCESTER ROAD
N
LOCATION PLAN
SCALE 1 : 50000
NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
2. THE RESTRICTION SHOWN IN THIS DRAWING WILL CEASE TO HAVE EFFECT AFTER THE OPERATION OF THE GOVERNMENT HELIPAD AT EASTERN DRIVE EAST.
LEGEND:
CONTRACT BOUNDARY
MOORING RESTRICTION ZONE
NAVIGATION AND MOORING RESTRICTION ZONE
WORKING BARGE, NAVIGATION AND MOORING RESTRICTION ZONE
B TENDER ADDENDUM NO.4 SEP 09
A TENDER ADDENDUM NO.1 SEP 09
- TENDER DRAWING AUG 09
CEDD
土木工程拓展署
Civil Engineering and Development Department
WAN CHAI DEVELOPMENT PHASE II
WAN CHAI DEVELOPMENT PHASE II - EXTERNAL WORKS AT HONG KONG CONVENTION AND EXHIBITION CENTRE
RESTRICTED ZONE FOR CONSTRUCTION VESSELS
(Contract no: HK/2009/01)
AECOM
DRG.NO. 60041297/C1/100/10108
AS 1:6000
METRES
© COPYRIGHT RESERVED


HENNESSY ROAD
JOHNSTON ROAD
INSET 'A'
SCALE 1 : 1000
CENTRAL DISTRICT
CUT LINE B-B
SEE A3 DRAWING NO. 60041297/C1/100/1005
VICTORIA HARBOUR
HONG KONG CONVENTION AND EXHIBITION CENTRE
HKCEC (Western Part)
HKCEC (Middle Part)
HKCEC (Eastern Part)
EIA-141/2007
DP3
MTR PROTECTION ZONE
MTR TSUEN WAN LINE TUNNEL
CONVENTION AVENUE
FENWI CK PIER STREET
HARBOUR ROAD
KEY PLAN
SCALE 1 : 50000
NOTE:
1. FOR NOTES & LEGEND, REFER TO DRAWING NO. 60041297/C1/100/1004.
WAN CHAI DEVELOPMENT PHASE II
WAN CHAI DEVELOPMENT PHASE II - CENTRAL - WAN CHAI BYPASS AT HONG KONG CONVENTION AND EXHIBITION CENTRE
SITE BOUNDARY SETTING OUT PLAN
(Contract no. Hk/2009/01)
Civil Engineering and Development Department
AECOM
DRG.NO. 60041297/C1/100/1006C
AS 1:2000
METRES
© COPYRIGHT RESERVED



Project Title: Wan Chai Development Phase II – Central Wan Chai Bypass at Wan Chai West (Contract No. HK/2012/08) – Marine Works
工程項目名稱: 灣仔發展計劃第二期 - 中環灣仔繞道-灣仔西段(合約編號:HK/2012/08)-海事工程
Environmental Permit No. : FEP-08/356/2009
環境許可證編號 : FEP-08/356/2009

Figure 1b : General Layout of the Project
圖 1b : 工程項目佈局圖

(This figure was prepared based on Figure 1b of Application for Further Environmental Permit (Application No.: FEP 172/2016))
(本圖是根據申請新的環境許可證 (申請書編號 FEP-172/2016) 圖 1b 編製)


LEGEND:
WORKS AREA
DREDGING AREA FOR MITGATION OF ODOUR(DP3)
SITE BOUNDARY
N
TCBR1E
TCBR2 AND TCBR3
TCBR4
TCBR1W
DP3
TPCWAE
TPCWAW
中國建築工程(香港)有限公司
CHINA STATE CONSTRUCTION ENGRG. (HONG KONG) LTD.
Highways Department
CONTRACT NO. HY/2009/15
CENTRAL-WAN CHAI BYPASS -TUNNEL
(CAUSEWAY BAY TYPHOON SHELTER SECTION)
TITLE
LOCATION PLAN OF WORKS AREA
DRG. NO.
CWBT/EPD/001B
SCALE
1:1000 @ A0
STATUS
DIMENSIONS ARE IN MILLIMETERS
COPYRIGHT RESERVED



圖1- 合約編號 HY/2010/08中環灣仔繞道-8號連接路段隧道

SCALE 1 : 3000

FIGURE 1 - CONTRACT NO. HY/2010/08 - CENTRAL - WAN CHAI BYPASS - TUNNEL (SLIP ROAD 8 SECTION)

T:\HY_2010_08\Misc\ARE\Docs\Figure for Website\T2 Figure 1.dgn 08-Apr-13

ACTIVITY	DURATION	START	FINISH
OVERALL STAGE : (Days 1 to 830)	830	26/01/10	06/05/12
DREDGING & RECLAMATIONS PHASE 1 (WCR1)	146	22/05/10	19/10/10
DREDGING & LAYING OF SUBMARINE OUTFALL PIPE ON SEA	410	21/09/10	02/02/12

Section of Works	A	Major Work at Area WCR1
XI	A1	Construct western and eastern temporary seawall
XI	A2	Dredging and construct new seawall
XI	A3	Reclamation to level +3.5mPD
IXB	A4	Construct diaphragm wall and barrette pile of tunnel "Portion 1"
IXB	A5	Construct tunnel "Portion 1" structures including excavation and backfilling with CLSW
IVA, IVB, IVC V, VI, VII	A6	Construct all drainage system, pipeworks of intakes and cooling system within Area WCR1

Section of Works	B	Major Work in Associated Area
IVA, IVB, IVC	B1	Construct P7, P8 and P9 new pumping stations
V	B2	Construct WSD's pumping station
VI	B3	Construct connection chamber in Wan Chai East Preliminary Treatment Plant
VA, IVB, IVC V, VI, VII	B4	Construct all drainage system, pipeworks of intakes and cooling system on public road
VI	B5	Dredging and construct the submarine outfall pipes
VIIIA	B6	Construct new Wan Chai Ferry Pier
III	B7	Construct new permanent helipad at Expo Drive
III	B8	Construct new public landing and passenger terminal building at Expo Drive

Section of Works	C	Other Miscellaneous Works
III	C1	Construct new taxi and coach/bus parking space at Expo Drive East
III	C2	Modification work on existing seawall and provide new EVA at Expo Drive
III	C3	Road re-alignment work on existing PTI at Expo Drive
II	C4	Road improvement work at junction of Harbour Road / Fenwick Road and Fleming Road / Gloucester Road
III	C5	Demolition of existing above ground structure at Expo Drive
V	C6	Demolition of existing staircase of footbridge at Wan Shing Street
IXA	C7	Demolition of existing temporary helipad at ex-PCWA

Section of Works	D	Other Temporary Works
XI	D1	Divert existing 1800 mm diameter drain pipe



REV	DATE	DESCRIPTION
C	[illegible]	[illegible] SCHEDULE UPDATED & TEMPORARY SEAWALL LAYOUT REVISED
B	[illegible]	[illegible]
A	[illegible]	[illegible]

CLIENT

ENGINEER'S REPRESENTATIVE

CONTRACTOR

PROJECT
CONTRACT NO. HK/2009/02
WAN CHAI DEVELOPMENT PHASE II
CENTRAL - WAN CHAI BYPASS AT WAN CHAI EAST

DRAWING TITLE
DETAILED WORKS SCHEDULE AND LOCATION PLAN - STAGE 1

	DESIGN	DRAWN	CHECKED
INITIAL	-	[illegible]	-
DATE	-	[illegible]	-

DRAWING NO. [illegible]K202902/SK0031 REV C

SCALE 1:2000 (A1)



合約編號 HY/2009/19 - 中環灣仔繞道 - 北角段隧道及東區走廊連接路

CONTRACT NO. HY/2009/19 - CENTRAL-WAN CHAI BYPASS - TUNNEL (NORTH POINT SECTION) AND ISLAND EASTERN CORRIDOR LINK

SCALE 1 : 3000

Plotted by: ZUUL_NL 2011-1-12

P:\projects\60094653\Drawing\SKETCH\SK3241.dgn

Figure 2.2

Project Organization Chart

Project Organization Chart

Project Proponent

Civil Engineering & Development Department

Mr. L. K. Tsang
Senior Engineer
Tel: 9325 0853
Fax: 2577 5040

Project Proponent

Highways Department

Mr. Tony Cheung
Senior Engineer
Tel: 2762 4951
Fax: 2714 5289

Environmental Protection Department

Mr. Billy Ma
Environmental Protection Officer
Tel: 2835 2390
Fax: 2591 0558

Engineer's Representative for WDII

AECOM

Mr. Frankie Fan
Principal Resident Engineer
Tel: 2587 1778
Fax: 2587 1877

Engineer's Representative for CWB

AECOM

Mr. Peter Poon
Principal Resident Engineer
Tel: 3912 3388
Fax: 3912 3328

Independent Environmental Checker

Ramboll Environ Hong Kong Limited

Mr. David Yeung
Independent Environmental Checker
Tel: 3465 2888
Fax: 3565.2899

HK/2009/01 Contractor

Chun Wo – Leader JV

Mr.Andy Yu
Site Agent
Tel: 2162 9909 Fax: 2634 1626

HK/2009/02 Contractor

Chun Wo – CRGL JV

Mr. Paul Yu
Project Manager
Tel: 3658 3002 Fax: 2827 9996

HK/2012/08 Contractor

China State –Build King Joint Venture

Mr. Keith Tse
Site Agent
Tel: 9037 1839 Fax: 2877 1522

HY/2009/15 Contractor

China State Co. Engineering Ltd.
Mr. Rex Lau
Contractor's Representative
Tel: 3557 6405
Fax: 2865 5229

HY/2009/19 Contractor

Chun Wo- CRGL JV

Mr. David Lau
Site Agent
Tel: 3758 8879
Fax: 2570 8013

HY/2010/08 Contractor

China State Construction Engineering (HK) Ltd.

Mr. Thomas Lui
Site Agent
Tel: 3557 6452
Fax: 2566 8061

Environmental Team

Lam Geotechnics Limited

Mr. Raymond Dai
Environmental Team Leader
Tel: 2882 3939 Fax: 2882 3331

Figure 4.1

Locations of Monitoring Stations

Legend

Water Quality Monitoring Stations

RW21-P789 (Wanchai WSD intake/ Great Eagle Centre/ China Resources Centre/ Sun Hung Kai Centre)

C1 Hong Kong Convention and Exhibition Centre Extension

P1 Hong Kong Convention and Exhibition Centre Phase 1

P3 HK Academy For Performing Art

P4 Shui On Centre

P5 Government buildings (Wanchai Tower/ Revenue Tower/ Immigration Tower)

C6 Proposed Exhibition Station/ World Trade Centre

C7 Windsor House



FIGURE	LOCATIONS OF WATER QUALITY MONITORING STATIONS

Legend

Water Quality Monitoring Stations

RW21-P789E (Wanchai WSD intake/ Great Eagle Centre/ China Resources Centre/ Sun Hung Kai Centre)

RW21-P789W (Wanchai WSD intake/ Great Eagle Centre/ China Resources Centre/ Sun Hung Kai Centre)

C1 Hong Kong Convention and Exhibition Centre Extension

P1 Hong Kong Convention and Exhibition Centre Phase 1

P3 HK Academy For Performing Art

P4 Shui On Centre

P5 Government buildings (Wanchai Tower/ Revenue Tower/ Immigration Tower)

C7 Windsor House



FIGURE	LOCATIONS OF WATER QUALITY MONITORING STATIONS

Legend

Enhance DO Monitoring Stations
Ex-PCWA SE Ex-Public Cargo Wanchai Area SouthEast Station
Ex-PCWA SW Ex-Public Cargo Wanchai Area Southwest Station
C6 Proposed Exhibition Station/ World Trade Centre
C7 Windsor House



FIGURE	LOCATIONS OF ENHANCE DO MONITORING STATIONS



FIGURE	LOCATIONS OF WATER QUALITY MONITORING STATIONS



LOCATIONS OF AIR QUALITY AND NOISE MONITORING STATIONS

Appendix 3.1

Environmental Mitigation Implementation Schedule

Environmental Mitigation Implementation Schedule

Implementation Schedule for Air Quality Control

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Construction Phase								
For the Whole Project								
S3.6.5	Four times a day watering of the work site with active operations.	Work site / during construction	Contractor		√			EIAO-TM
S3.8.1	Implementation of dust suppression measures stipulated in Air Pollution Control (Construction Dust) Regulation. The following mitigation measures, good site practices and a comprehensive dust monitoring and audit programme are recommended to minimise cumulative dust impacts. • Strictly limit the truck speed on site to below 10 km per hour and water spraying to keep the haul roads in wet condition; • Watering during excavation and material handling; • Provision of vehicle wheel and body washing facilities at the exit points of the site, combined with cleaning of public roads where necessary; and • Tarpaulin covering of all dusty vehicle loads transported to, from and between site locations.	Work site / during construction	Contractor		√			

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S3.5.6	For the dredging activities carried out in the vicinity of Police Officers' Club, the dredging operation will be restricted to only 1 small close grab dredger to minimise the odour impact during the dredging activity. The dredging rate should be reduced as much as practicable for the area in close proximity to the Police Officers' Club. The sediments contain highly contaminated mud which may be disposed with the use of geosynthetic containers (details shall refer to Section 6), grab dredger has to be used for filling up the geosynthetic containers on barges. the dredging rate for the removal of the sediments at the south-west corner of the typhoon shelter shall be slowed down or restricted to specific non-popular hours in weekdays when it is necessary during construction.	Corner of CBTS/implementation of harbour-front enhancement	CEDD[1]		√			EIAO-TM
S3.8.8	Carry out dredging at the corner of CBTS to remove the sediment and clean the slime attached on the CBTS shoreline seawall	Corner of CBTS & CBTS shoreline seawall/implementation of harbour-front enhancement	CEDD[2]		√			EIAO-TM
Operation Phase								
For the Whole Project								

[1] CEDD will identify an implementation agent.

[2] CEDD will identify an implementation agent.

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S3.10.2	Monthly (from July to September) monitoring of odour impacts, for a period of 5 years, is proposed during the operational phase of the Project to ascertain the effectiveness of the Enhancement Package over time, and to monitor any on-going odour impacts at the ASRs.	Planned ASRs (CBTS Breakwater)/First 5-year period of operation phase	CEDD[1]			√		EIAO-TM
For DP1 – CWB (Within the Project Boundary)								
S3.6.53 – S3.6.54	The design parameters of the East and Central Ventilation Buildings as set in Tables 3.10 and 3.11	East and Central Ventilation Buildings / During operation of the Trunk Road	HyD			√		
S3.10.2	Air quality monitoring for the operation performance of the East Ventilation Building and associated East Vent Shaft will be conducted.	East Vent Shaft / During operation of the East Ventilation Building and associated East Vent Shaft	HyD			√		EIAO-TM

- Des - Design, C - Construction, O – Operation, and Dec – Decommissioning

Table A13.2 Implementation Schedule for Noise Control

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Construction Phase								
For the Whole Project								

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S4.9.4	Good Site Practice: • Only well-maintained plant shall be operated on-site and plant shall be serviced regularly during the construction program. • Silencers or mufflers on construction equipment shall be utilized and shall be properly maintained during the construction program. • Mobile plant, if any, shall be sited as far away from NSRs as possible. • Machines and plant (such as trucks) that may be in intermittent use shall be shut down between works periods or shall be throttled down to a minimum. • Plant known to emit noise strongly in one direction shall, wherever possible, be orientated so that the noise is directed away from the nearby NSRs. • Material stockpiles and other structures shall be effectively utilized, wherever practicable, in screening noise from on-site construction activities.	Work Sites / During Construction	Contractor		√			EIAO-TM, NCO
For DP1 – CWB (Within the Project Boundary)								

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S4.8.3 – S4.8.5	Use of quiet powered mechanical equipment, movable noise barrier and temporary noise barrier for the following tasks: • Slip road 8 tunnel • Construction of diaphragm wall and substructures of the tunnel approach ramp • Excavation • Construction of slabs • Backfill • Demolition and construction of substructures for the IEC • Demolition works of existing piers and crossheads of the marine section of the existing IEC Use of PME grouping for the following tasks: • At-grade road construction • Substructure for IECL connection	Work Sites / During Construction	Contractor		√			EIAO-TM, NCO
For DP2 – WDII Major Roads (Road P2)								
S4.8.3 – S4.8.4	Use of quiet powered mechanical equipment, movable noise barrier and temporary noise barrier for the following tasks: • Temporary road diversion • Resurfacing • At-grade roadwork	Work Sites / During Construction	Contractor		√			EIAO-TM, NCO
For DP3 – Reclamation Works								
S4.8.3 – S4.8.4	Use of quiet powered mechanical equipment for the following task: • Filling behind seawall • Seawall construction	Work Sites / During Construction	Contractor		√			EIAO-TM, NCO

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
For DP5 – Wan Chai East Sewage Outfall								
S4.8.3 – S4.8.4	Use of quiet powered mechanical equipment for the following tasks: • Submarine pipelines (marine section) Use of quiet powered mechanical equipment and movable noise barrier for the following tasks: • Installation of a new pipeline (land section)	Work Sites / During Construction	Contractor		√			EIAO-TM, NCO
For DP6 – Cross-Harbour Water Mains from Wan Chai to Tsim Sha Tsui								
S4.8.3 – S4.8.4	Use of quiet powered mechanical equipment for the following tasks: • Submarine pipelines (marine section) •	Work Sites / During Construction	Contractor		√			EIAO-TM, NCO

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Operation Phase								
For DP1 – CWB (Within the Project Boundary)								

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S4.8.14 – S4.8.18	• For Existing NSRs • about 235m length of noise semi-enclosure with transparent panel covering the westbound slip road from the IEC • about 230m length of noise semi-enclosure with transparent panel covering the main carriageways (eastbound and westbound) of the CWB and IEC • about 135m length of 5.5m high cantilevered noise barrier with 3m cantilever inclined at 45° with transparent panel on the eastbound slip road to the IEC • about 95m length of 5.5m high cantilevered noise barrier with 1m cantilever inclined at 45° with transparent panel on the eastbound slip road to the IEC • about 350m length of 3.5m high vertical noise barrier with transparent panel on the eastbound slip road to the IEC • low noise road surfacing for the trunk road (except tunnel section and beneath the landscaped deck at the eastern portal area) with speed limit of 70 km/hour	Near North Point / Before commencement of operation of road project	HyD	√	√	√		EIAO-TM
	For Future/Planned NSRs • about 265m length of noise semi-enclosure with transparent panel covering the westbound slip road from the IEC	In between the Electric Centre (next to City Garden) and CDA(1) site / Before occupation of Planned NSRs in CDA and CDA(1) sites.	HyD	√	√ #			

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	• The openable windows of the temple, if any, should be orientated so as to avoid direct line of sight to the existing Victoria Park Road as far as practicable.	Near Causeway Bay Fire Station / During detailed design of the re-provisioned Tin Hau Temple	Project Proponent for the re-provisioned Tin Hau Temple	√				

* Des - Design, C - Construction, O – Operation, and Dec - Decommissioning

Only the steel frame for this section of noise semi-enclosure would be erected in advance during the construction of the westbound slip road.

Table A13.3 Implementation Schedule for Water Quality Control

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Construction Phase								
For DP3 – Reclamation Works, DP5 (Wan Chai East Sewage Outfall), DP6 (Cross-Harbour Water Mains from Wan Chai to Tsim Sha Tsui), DP1 – CWB (within the Project Boundary)								
S5.8	A phased reclamation approach is planned for the WDII. Containment of fill within each of the reclamation phases by seawalls is proposed, with the seawall constructed first (above high water mark) with filling carried out behind the completed seawalls. Any gaps that may need to be provided for marine access will be shielded by silt curtains to control sediment plume dispersion away from the site. Filling for seawall construction should be carried out behind the silt curtain	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO
S5.8	Dredging shall be carried out by closed grab dredger for the following works: • Seawall construction in all the reclamation areas; • Construction of the CWB Tunnel • Construction of the proposed WSD water mains; and • Construction of the proposed Wan Chai East sewage outfall pipelines.	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO
S5.8, Figure 5.3	Dredging for the Wan Chai East sewage outfall pipelines shall not be carried out concurrently with the following activities: • Dredging along the proposed cross-harbour water mains; • Dredging along the seawall in the Wan Chai Reclamation (WCR) zone (area between HKCEC Extension and PCWA).	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S5.8	The water body behind the temporary reclamations within the Causeway Bay typhoon shelter shall not be fully enclosed.	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO
S5.8	As a mitigation measure, to avoid the accumulation of water borne pollutants within the temporary embayment between CRIII and HKCEC1, an impermeable barrier, suspended from a floating boom on the water surface and extending down to the seabed, will be erected by the contractor before the HKCEC1 commences. The barrier will channel the stormwater discharge flows from Culvert L to the outside of the embayment. The contractor will maintain this barrier until the reclamation works in HKCEC2W are carried out and the new Culvert L extension is constructed.	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO
S5.8, Figure 5.3	The total dredging rates in each of the marine works zones shall not be more than the maximum production rates stated in the table below. These are the production rates without considering the effect of silt curtain.	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO

Reclamation Area		Maximum Dredging Rate		Maximum Dredging Rate (m^3 per week)
		m^3 per day	m^3 per hour (for 16 hrs per day)	
Dredging along seawall or breakwater				
North Point Shoreline Zone (NPR)		6,000	375	42,000
Causeway Bay Shoreline Zone	TBW	1,500	94	10,500
	TCBR	6,000	375	42,000
PCWA Zone		5,000	313	35,000

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	<table><tr><td colspan="2">Wan Chai Shoreline Zone (WCR)</td><td>6,000</td><td>375</td><td>42,000</td></tr><tr><td rowspan="2">HKCEC Shoreline Zone (HKCEC)</td><td>HKCEC Stage 1 & 3</td><td>1,500</td><td>94</td><td>10,500</td></tr><tr><td>HKCEC Stage 2</td><td>6,000</td><td>375</td><td>42,000</td></tr><tr><td colspan="2">Cross Harbour Water Mains</td><td>1,500</td><td>94</td><td>10,500</td></tr><tr><td colspan="2">Wan Chai East Submarine Sewage Pipeline</td><td>1,500</td><td>94</td><td>10,500</td></tr></table> Note: 1,500 m^3 per day shall be applied for construction of the western seawall of WCR1.							
S5.8, Figure 5.3	Dredging along the seawall at WCR1 shall be undertaken initially at 1,500m^3 per day for construction of the western seawall (which is in close proximity of the WSD intake), followed by partial seawall construction at the western seawall (above high water mark) to protect the adjacent intakes as much as possible from further dredging activities.	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO
S5.8, Figure 5.3	For dredging within the Causeway Bay typhoon shelter, seawall shall be partially constructed to protect the nearby seawater intakes from further dredging activities. For example, at TCBR1W, the southern and eastern seawalls shall be constructed first (above high water mark) so that the seawater intakes at the inner water would be protected from the impacts from the remaining dredging activities along the northern boundary.	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO
S5.8, Figure 5.3	Silt curtains shall be deployed around the closed grab dredgers during seawall dredging and seawall trench filling in the areas of HKCEC, WCR, TCBR and NP.	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO
S5.8, Figure 5.3	Silt screens shall be applied to seawater intakes at interim construction stages as stated below: <table><tr><th>Interim Construction Stage</th><th>Location of Applications</th></tr><tr><td>**Scenario 2A** in early 2009 with concurrent dredging activities at HKCEC, WCR, TPCWA, TBW, NP and Water Mains Zone</td><td>**WSD saltwater intakes** at Sai Wan Ho, Quarry Bay, Sheung Wan, Wan Chai, Kowloon South **Cooling water intakes** for Hong Kong Convention and Exhibition Centre Extension, Hong Kong Convention and Exhibition Centre Phase I, Telecom House / HK Academy for Performing Arts / Shun On Centre, Wan Chai Tower / Revenue Tower / Immigration Tower and Sun Hung Kai Centre</td></tr><tr><td>**Scenario 2B** in late 2009/2010 with concurrent dredging activities at Sewage Pipelines Zone and TCBR.</td><td>**WSD saltwater intakes** at Sheung Wan, Wan Chai **Cooling water intakes** for Queensway Government Offices, Excelsior Hotel, World Trade Centre and Windsor House.</td></tr><tr><td>**Scenario 2C** in 2011 with concurrent dredging activities at HKCEC and TCBR.</td><td>**WSD saltwater intakes** at Sheung Wan and Reprovisioned WSD Wan Chai saltwater intake. **Cooling water intakes** for MTR South, Excelsior Hotel & World Trade Centre and reprovisioned Windsor House.</td></tr></table>	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO

Contract no. HK/2015/01
Wan Chai Development Phase II and Central-Wanchai Bypass
- Sampling, Field Measurement and Testing Works (Stage 3)
Monthly EM&A Report

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S5.8	Other mitigation measures include: • mechanical grabs, if used, shall be designed and maintained to avoid spillage and sealed tightly while being lifted. For dredging of any contaminated mud, closed watertight grabs must be used; • all vessels shall be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash; • all hopper barges and dredgers shall be fitted with tight fitting seals to their bottom openings to prevent leakage of material; • construction activities shall not cause foam, oil, grease, scum, litter or other objectionable matter to be present on the water within the site or dumping grounds; • loading of barges and hoppers shall be controlled to prevent splashing of dredged material into the surrounding water. Barges or hoppers shall not be filled to a level that will cause the overflow of materials or polluted water during loading or transportation; and	Work site / During the construction period	Contractor		√			ProPECC PN 1/94; WPCO (TM-DSS)

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	• before commencement of the reclamation works, the holder of Environmental Permit has to submit plans showing the phased construction of the reclamation, design and operation of the silt curtain.							
S5.8	Silt screens are recommended to be deployed at the seawater intakes during the reclamation works period. Installation of silt screens at the seawater intake points may cause a potential for accumulation and trapping of pollutants, floating debris and refuse behind the silt screens and may lead to potential water quality deterioration at the seawater intake points. Major sources of pollutants and floating refuse include the runoff and storm water discharges from the nearby coastal areas. As a mitigation measure to avoid the pollutant and refuse entrapment problems and to ensure that the impact monitoring results are representative, regular maintenance of the silt screens and refuse collection shall be performed at the monitoring stations at regular intervals on a daily basis. The Contractor shall be responsible for keeping the water behind the silt screen free from floating rubbish and debris during the impact monitoring period.	Work site / During the construction period	Contractor		√			EIAO-TM, WPCO

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S5.8	Dredging of contaminated mud is recommended as a mitigation measures for control of operational odour impact from the Causeway Bay typhoon shelter. In recognition of the potential impacts caused by dredging activities close to the seawater intakes, only 1 small close grab dredger shall be operated within the typhoon shelter (for the dredging to mitigate odour impact) at any time to minimize the potential impact. Double silt curtains shall be deployed to fully enclose the closed grab dredger during the dredging operation. In addition, an impermeable barrier, suspended from a floating boom on the water surface and extended down to the seabed, shall be erected to isolate the adjacent intakes as much as possible from dredging activities. For example, if dredging is to be carried out at the southwest corner of the typhoon shelter, physical barriers shall be erected to west of the cooling water intake for Excelsior Hotel so that the intake would be shielded from most of the SS generated from the dredging operation to the west of the intake. For area in close proximity of the cooling water intake point, the dredging rate shall be reduced as much as practicable. Site audit and water quality monitoring shall be carried out at the seawater intakes during the dredging operations. Daily monitoring of SS at the cooling water intake shall be carried out, and 24 hour monitoring of turbidity at the intakes shall be implemented during the dredging activities. If the monitoring results indicate that the dredging operation has caused significant changes in water quality conditions at the seawater intakes, appropriate actions shall be taken to stop the dredging and mitigation measures such as slowing down the dredging rate shall be implemented.	Causeway Bay typhoon shelter/Implementation of harbour-front enhancement.	CEDD[3]		√			WPCO

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
For the Whole Project								
S5.8	• Construction Runoff and Drainage • use of sediment traps, wheel washing facilities for vehicles leaving the site, and adequate maintenance of drainage systems to prevent flooding and overflow; • Permanent drainage channels shall incorporate sediment basins or traps and baffles to enhance deposition rates. The design of efficient silt removal facilities shall be based on the guidelines in Appendix A1 of ProPECC PN 1/94; • a sediment tank constructed from pre-formed individual cells of approximately 6 - 8 m3 capacity can be used for settling ground water prior to disposal; • oil interceptors shall be provided in the drainage system for the tunnels and regularly cleaned to prevent the release of oils and grease into the storm water drainage system after accidental spillages. The interceptor shall have a bypass to prevent flushing during periods of heavy rain; • precautions and actions to be taken when a rainstorm is imminent or forecast, and during or after rainstorms. Particular attention shall be paid to the control of any silty surface runoff during storm events; • on-site drainage system shall be installed prior to the commencement of other construction activities. Sediment traps shall be installed in order to minimise the sediment loading of the effluent prior to discharge; • All temporary and permanent drainage pipes and culverts provided to facilitate runoff discharge shall be adequately designed for the controlled release of storm flows. All sediment control measures shall be regularly inspected and maintained to ensure proper and efficient operation at all times and particularly following rain storms. The temporarily diverted drainage shall be reinstated to its original condition when the construction work is finished or the temporary diversion is no longer	• Work site / During the constructi on period	Contractor		√			ProPECC PN 1/94; WPCO (TM-DSS)

[3] CEDD will identify an implementation agent.

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	required. • All fuel tanks and store areas shall be provided with locks and be sited on sealed areas, within bunds of a capacity equal to 110% of the storage capacity.							
	• Minimum distances of 100 m shall be maintained between the storm water discharges and the existing or planned WSD flushing water intakes during construction phase.							
S5.8	*Sewage from Construction Work Force* Construction work force sewage discharges on site shall be connected to the existing trunk sewer or sewage treatment facilities. The construction sewage shall be handled by portable chemical toilets prior to the commission of the on-site sewer system. Appropriate numbers of portable toilets shall be provided by a licensed contractor to serve the large number of construction workers over the construction site. The Contractor shall also be responsible for waste disposal and maintenance practices.	Work site / During the construction period	Contractor		√			ProPECC PN 1/94; WPCO (TM-DSS)
S5.8	*Floating Debris and Refuse* Collection and removal of floating refuse shall be performed at regular intervals on a daily basis. The contractor shall be responsible for keeping the water within the site boundary and the neighbouring water free from rubbish.	Work site and adjacent water / During the construction period.	Contractor		√			WPCO

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S5.8	*Storm Water Discharges* Minimum distances of 100 m shall be maintained between the existing or planned stormwater discharges and the existing or planned WSD flushing water intakes.	Work site and adjacent water / During the design and construction period.	Contractor	√	√			WPCO
Operation Phase								
DP1 – CWB (within the Project Boundary)								
S5.8	For the operation of CWB, a surface water drainage system would be provided to collect road runoff. The following operation stage mitigation measures are recommended to ensure road runoff would comply with the TM under the WPCO: • The drainage from tunnel sections shall be directed through petrol interceptors to remove oil and grease before being discharged to the nearby foul water manholes. • Petrol interceptors shall be regularly cleaned and maintained in good working condition. • Oily contents of the petrol interceptors shall be properly handled and disposed of, in compliance with the requirements of the Waste Disposal Ordinance. • Sewage arising from ancillary facilities of CWB (for examples, car park,	CWB/During design and operational period	HyD/TD[3]	√		√		WPCO

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	control room, ventilation and administration buildings and tunnel portals) shall be connected to public sewerage system. Sufficient capacity in public sewerage shall be made available to the proposed facilities. • Road drainage shall also be provided with adequately designed silt trap to minimize discharge of silty runoff. • The design of the operational stage mitigation measures for CWB shall take into account the guidelines published in ProPECC PN 5/93 "Drainage Plans subject to Comment by the EPD." All operational discharges from the CWB into drainage or sewerage systems are required to be licensed by EPD under the WPCO.							

* Des - Design, C - Construction, O – Operation, and Dec - Decommissioning

[3] if employ Management, Operation and Maintenance (MOM) Contract

Table A13.4 Implementation Schedule for Waste Management

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Construction Phase								
For DP3 – Reclamation Works								
S6.7.2	***Marine Sediments*** The dredged marine sediments would be loaded onto barges, transported to and disposed of at the designated disposal sites at South of Cheung Chau, East of Ninepin, East of Tung Lung Chau, South of Tsing Yi or East of Sha Chau to be allocated by the MFC depending on their level of contamination or at other disposal sites after consultation with the MFC and EPD. In accordance with the ETWB TCW No. 34/2002, the contaminated material must be dredged and transported with great care. The mitigation measures recommended in Section 5 of the EIA Report shall be incorporated. The dredged contaminated sediment must be effectively isolated from the environment upon final disposal and shall be disposed of at the Type 2 confined marine disposal contaminated mud pit.	Work site / During the construction period	Contractor		√			ETWB TCW No. 34/2002
S6.7.3	Based on the biological screening results, the Category H (>10xLCEL) sediment which failed the biological testing would require Type 3 special disposal. The volume of Category H sediment from the Causeway Bay typhoon shelter which would require special disposal arrangements is estimated to be approximately 0.05 Mm^3. A feasible containment method is proposed whereby the dredged sediments are sealed in geosynthetic containers and, at the disposal site, the containers would be dropped into the designated contaminated mud pit where they would be covered by further mud disposal and later by the mud pit capping, thereby meeting the requirements for fully confined mud disposal.							

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S6.7.5	It will be the responsibility of the Contractor to satisfy the appropriate authorities that the contamination levels of the marine sediment to be dredged have been analysed and recorded. According to the ETWB TCW No. 34/2002, this will involve the submission of a formal Sediment Quality Report to the DEP, at least 3 months prior to the dredging contract being tendered							
S6.7.6	During transportation and disposal of the dredged marine sediments requiring Type 1 and Type 2 disposal, the following measures shall be taken to minimise potential impacts on water quality: • Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and hopper dredgers before the vessel is moved.							

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	• Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the DEP. • Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.							
S6.6.12	***Floating Refuse*** During the construction phase, the project proponent's contractor will be responsible for the collection of any refuse within their works area. Floating booms will be provided on the water surface to confine the refuse from the working barges as well as to avoid the accumulation of pollutants within temporary embayment as mentioned in Table 13.3.	Work site / During the construction period	Contractor		√			
For the Whole Project								

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S6.7.7	*Good Site Practices* Recommendations for good site practices during the construction activities include: • nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site; • training of site personnel in proper waste management and chemical waste handling procedures; • provision of sufficient waste disposal points and regular collection for disposal; • appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers; • regular cleaning and maintenance programme for drainage systems, sumps and oil interceptors; and • a recording system for the amount of wastes generated, recycled and disposed of (including the disposal sites).	Work site / During the construction period	Contractor		√			Waste Disposal Ordinance (Cap.354)

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S6.7.8	*Waste Reduction Measures* Waste reduction is best achieved at the planning and design stage, as well as by ensuring the implementation of good site practices. Recommendations to achieve waste reduction include: • segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal; • to encourage collection of aluminium cans, PET bottles and paper, separate labelled bins shall be provided to segregate these wastes from other general refuse generated by the work force; • any unused chemicals or those with remaining functional capacity shall be recycled; • use of reusable non-timber formwork, such as in casting the tunnel box sections, to reduce the amount of C&D material. • prior to disposal of C&D waste, it is recommended that wood, steel and other metals shall be separated for re-use and / or recycling to minimise the quantity of waste to be disposed of to landfill; • proper storage and site practices to minimise the potential for damage or contamination of construction materials; and • plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste.	Work site / During planning and design stage, and construction stage	Contractor	√	√			

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S6.7.10	*General Refuse* General refuse shall be stored in enclosed bins or compaction units separate from C&D material. A licensed waste collector shall be employed by the contractor to remove general refuse from the site, separately from C&D material. A collection area shall be provided where wastes can be stored and loaded prior to removal from site. An enclosed and covered area is recommended to reduce the occurrence of 'wind blow' light material.	Work site / During the construction period	Contractor		√			Public Health and Municipal Services Ordinance (Cap. 132)
S6.7.11	*Chemical Wastes* After use, chemical wastes (for example, cleaning fluids, solvents, lubrication oil and fuel) shall be handled according to the Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes. Spent chemicals shall be collected by a licensed collector for disposal at the CWTF or other licensed facility in accordance with the Waste Disposal (Chemical Waste) (General) Regulation.	Work site / During the construction period	Contractor		√			Waste Disposal (Chemical Waste) (General) Regulation Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes
S6.7.12	*Construction and Demolition Material* C&D material shall be sorted on-site into inert C&D material (that is, public fill) and C&D waste. All the suitable inert C&D material shall be broken down to 250 mm in size for reuse as public fill in the WDII reclamation. C&D waste, such as wood, glass, plastic, steel and other metals shall be reused or recycled and, as a last resort, disposed of to landfill. A suitable area shall be designated to facilitate the sorting process and a temporary stockpiling area will be required for the separated materials.	Work site / During the construction period	Contractor		√			ETWB TCW No. 33/2002, 31/2004, 19/2005

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S6.7.13	In order to monitor the disposal of public fill and C&D waste at public filling facilities and landfills, respectively, and to control fly tipping, a trip-ticket system shall be included as one of the contractual requirements and implemented by the Environmental Team undertaking the environmental monitoring and audit work. An Independent Environment Checker shall be responsible for auditing the results of the system.	Work site / During the construction period	Contractor and Independent Environmental Checker		√			ETWB TCW No. 31/2004
S6.7.14	*Bentonite Slurry* The disposal of residual used bentonite slurry shall follow the good practice guidelines stated in ProPECC PN 1/94 "Construction Site Drainage" and listed as follows: • If the disposal of a certain residual quantity cannot be avoided, the used slurry may be disposed of at the marine spoil grounds subject to obtaining a marine dumping licence from EPD on a case-by-case basis. • If the used bentonite slurry is intended to be disposed of through the public drainage system, it shall be treated to the respective effluent standards applicable to foul sewers, storm drains or the receiving waters as set out in the Technical Memorandum of Standards for Effluents Discharged into Drainage and Sewerage Systems, Inland and Coastal Waters. • If the used bentonite slurry is intended to be disposed to public fill reception facilities, it will be mixed with dry soil on site before disposal.	Work site / During the construction period	Contractor		√			ProPECC PN 1/94

* Des - Design, C - Construction, O – Operation, and Dec - Decommissioning

Table A13.5 Implementation Schedule for Land Contamination

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Construction Phase								
For the Whole Project								
S.12.6	• The contaminated site shall be cleaned up before commencement of site clearance and construction work at the concerned area which may disturb the ground.	A King Marine / Before commencement of construction activities at A King Marine.	Project proponent for the re-provisioned Tin Hau Temple	√				*"Guidance Notes for Investigation and Remediation of Contaminated Sites of Petrol Filling Stations, Boatyards, and Car Repair/Dismantling Workshops"* published by EPD, HKSAR EPD ProPECC Note No. 3/94
S7.10	During soil remediation works, the Contractor for the excavation works shall take note of the following points for excavation: • Excavation profiles must be properly designed and executed; • In case the soil to be excavated is situated beneath the groundwater table, it may be necessary to lower the groundwater table by installing well points or similar means; • Quantities of soil to be excavated must be estimated; • It maybe necessary to split quantities of soil according to soil type, degree and nature of contamination. • Temporary storage of soil at intermediate depot or on-site	A King Marine / During soil remediation works	Contractor	√				Air Pollution Control Ordinance Noise Control Ordinance Waste Disposal Ordinance Waste Disposal (Chemical Waste) (General) Regulation

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	maybe required. The storage site shall include protection facilities for leaching into the ground. eg. Liner maybe required.							
	• Supply of suitable clean backfill materials is needed after excavation. • Care must be taken of existing buildings and utilities. • Precautions must be taken to control of ground settlement • Speed controls for vehicles shall be imposed on dusty site areas. • Vehicle wheel and body washing facilities at the site's exit points shall be established and used. The following environmental mitigation measures shall be strictly followed during the operation and/or maintenance of the CS/S facilities:							Water Pollution Control Ordinance

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	Air Quality Mitigation Measures • The loading, unloading, handling, transfer or storage of cement shall be carried out in an enclosed system. • The loading, unloading, handling, transfer or storage of other materials which may generate airborne dust emissions such as untreated soil and oversize materials sorted out from the screening plant and stabilized soil stockpiled in the designated handling area, shall be carried out in such a manner to prevent or minimise dust emissions. These materials shall be adequately wetted prior to and during the loading, unloading and handling operations. • All practicable measures, including speed controls for vehicles, shall be taken to prevent or minimize the dust emission caused by vehicle movement. • Tarpaulin or low permeable sheet shall be put on dusty vehicle loads transported between site locations.							
	Noise Mitigation Measures • The mixing facilities shall be sited as far as practicable to the nearby noise sensitive receivers. • Simultaneous operation of mixing facilities and other equipment shall be avoided. • Mixing process and other associated material handling activities shall be properly scheduled to minimise potential cumulative noise impact on the nearby noise sensitive receivers. • Construction Noise Permit shall be applied for the operation of powered mechanical equipment during restricted hours (if any).							

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
	Water Quality Mitigation Measures • Stockpile of untreated soil shall be covered as far as practicable to prevent the contaminated material from leaching out. The leachate shall be discharged following the requirements of WPCO. *Waste Mitigation Measures* • Treated oversize materials will be used as filling material for backfilling within the site. Sorted materials of size smaller than 5 cm will be collected and transferred to the mixing plant for further decontamination treatment. • Stabilized soils shall be broken into suitable size for backfilling or reuse on site. • A high standard of housekeeping shall be maintained within the mixing plant area. • If necessary, there shall be clear and separated areas for stockpiling of untreated and treated materials.							

* Des - Design, C - Construction, O – Operation, and Dec - Decommissioning

Table A13.6 Implementation Schedule for Marine Ecology

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Construction Phase								
For the Whole Project - Schedule 3 DP								
S.9.7.2	Alternative design of the Trunk Road constructed in tunnel shall be adopted to avoid permanent reclamation in CBTS and ex-PWCA Basin.	-	CEDD/HyD	√				EIAO TM Annex 16 (Section 8.4) & EIAO Guidance Note No. 3/2002.
For DP3 – Reclamation Works								
S.9.7.3	Translocation of those potentially affected coral colonies to the nearby suitable habitats such as Junk Bay is recommended. A detailed translocation plan (including translocation methodology, monitoring of transplanted corals, etc.) should be drafted and approval by AFCD during the detailed design stage of the Project.	Ex-PCWA Basin and along seawall next to a public pier which is about 250 m away from the CBTS	CEDD/HyD	√				EIAO TM Annex 16 (Section 8.4) & EIAO Guidance Note No. 3/2002.

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S.9.7.4	During dredging and filling operations, a number of mitigation measures to control water quality shall be adopted to confine sediment plume within reclamation area and protect marine fauna in proximity to the reclamation. The mitigation measures include the following: • Installation of silt curtains during dredging activities • Use of tightly-closed grab dredger • Reduction of dredging rate • Control of grab descending speed • Construction of leading edges of seawall in the early stages of the reclamation works	Work site / during construction phase	Contractor		√			EIAO TM Annex 16 (Section 8.4) & EIAO Guidance Note No. 3/2002.
	• Adoption of multiple-phase construction schedule							

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
S.9.7.6	To minimize potential disturbance impacts on the foraging ardeid population in the CBTS, particularly in the area near the A King Shipyard, appropriate mitigation measures shall be adopted particularly during the construction phase. The following measures are recommended: • Use of Quiet Mechanical Plant during the construction phase shall be adopted wherever possible. • Adoption of multiple-phase construction schedule. • General measures to reduce noise generated during the construction phase (see noise impact assessment) shall be effectively implemented.	Work site / during construction phase	Contractor		√			EIAO TM Annex 16 (Section 8.4) & EIAO Guidance Note No. 3/2002.
S.9.7.7	Seawalls shall be constructed in advance around the reclamation areas within the area of the CBTS to screen adjacent feeding ground from construction phase activities, reduce noise disturbance to the associated seabirds and also to restrict access to this habitat adjacent to works areas by ship traffic.	Work site / during construction phase	Contractor		√			EIAO TM Annex 16 (Section 8.4) & EIAO Guidance Note No. 3/2002.
S.9.7.8	Loss of artificial seawall habitats shall be reinstated by the construction of about 1 km vertical wave absorbing seawall along the coastlines of the new reclamation around the HKCEC and at North Point. The new seawalls are expected to provide large area of hard substrata for settlement and recruitment of intertidal fauna similar to those previously recorded from existing intertidal habitats.	Work site / during construction phase	Contractor		√			EIAO TM Annex 16 (Section 8.4) & EIAO Guidance Note No. 3/2002.

*Des - Design, C - Construction, O – Operation, and Dec - Decommissioning

Table A13.7 Implementation Schedule for Landscape and Visual

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Construction Phase								
For the Whole Project								
Table 10.5	CM1 Topsoil, where identified, shall be stripped and stored for re-use in the construction of the soft landscape works, where practical.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM2 Existing trees to be retained on site shall be carefully protected during construction.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM3 Trees unavoidably affected by the works shall be transplanted where practical.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM4 Compensatory tree planting shall be provided to compensate for felled trees.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM5 Control of night-time lighting.	Work site / During Construction Phase	Contractor		√			EIAO TM
Table 10.5	CM6 Erection of decorative screen hoarding compatible with the surrounding setting.	Work site / During Construction Phase	Contractor		√			EIAO TM
For DP1 – CWB (Within the Project Boundary)								
Table 10.5	CM1 Topsoil, where identified, shall be stripped and stored for re-use in the construction of the soft landscape works, where practical.	Work site / During Construction Phase	Contractor		√			EIAO TM
Table 10.5	CM2 Existing trees to be retained on site shall be carefully protected during construction.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM3 Trees unavoidably affected by the works shall be transplanted where practical.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM4 Compensatory tree planting shall be provided to compensate for felled trees.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM5 Control of night-time lighting.	Work site / During Construction Phase	Contractor		√			EIAO TM

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Table 10.5	CM6 Erection of decorative screen hoarding compatible with the surrounding setting.	Work site / During Construction Phase	Contractor		√			EIAO TM
For DP2 – WDII Major Roads (Road P2)								
Table 10.5	CM1 Topsoil, where identified, shall be stripped and stored for re-use in the construction of the soft landscape works, where practical.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM2 Existing trees to be retained on site shall be carefully protected during construction.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM3 Trees unavoidably affected by the works shall be transplanted where practical.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM4 Compensatory tree planting shall be provided to compensate for felled trees.	Work site / During Construction Phase	Contractor	√	√			EIAO TM
Table 10.5	CM5 Control of night-time lighting.	Work site / During Construction Phase	Contractor		√			EIAO TM
Table 10.5	CM6 Erection of decorative screen hoarding compatible with the surrounding setting.	Work site / During Construction Phase	Contractor		√			EIAO TM
For DP3 – Reclamation Works								
Table 10.5	CM5 Control of night-time lighting.	Work site / During Construction Phase	Contractor		√			EIAO TM
Table 10.5	CM6 Erection of decorative screen hoarding compatible with the surrounding setting.	Work site / During Construction Phase	Contractor		√			EIAO TM
For DP5 – Wan Chai East Sewage Outfall								
Refer to EIA-058/2001 Table 10.13	CM2 Minimisation of works areas.	Work site / During Construction Phase	Contractor		√			EIAO TM
Refer to EIA-058/2001 Table 10.13	CM3 Erection of decorative hoardings.	Work site / During Construction Phase	Contractor		√			EIAO TM

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Refer to EIA-058/2001 Table 10.13	CM4 Control night-time lighting.	Work site / During Construction Phase	Contractor		√			EIAO TM
Refer to EIA-058/2001 Table 10.13	CM5 Minimisation of disruption to public by effective programming of the works.	Work site / During Construction Phase	Contractor		√			EIAO TM
For DP6 – Cross-Harbour Water Mains from Wan Chai to Tsim Sha Tsui								
Refer to EIA-058/2001 Table 10.13	CM2 Minimisation of works areas.	Work site / During Construction Phase	Contractor		√			EIAO TM
Refer to EIA-058/2001 Table 10.13	CM3 Erection of decorative hoardings.	Work site / During Construction Phase	Contractor		√			EIAO TM
Refer to EIA-058/2001 Table 10.13	CM4 Control night-time lighting.	Work site / During Construction Phase	Contractor		√			EIAO TM
Refer to EIA-058/2001 Table 10.13	CM5 Minimisation of disruption to public by effective programming of the works.	Work site / During Construction Phase	Contractor		√			EIAO TM
Operation Phase								
For the Whole Project - Schedule 3 DP								
Table 10.6, Figure 10.5.1-10.5.5	OM1 Aesthetic design of buildings and road-related structures, including viaducts, vent buildings, subways, footbridges and noise barriers and enclosure.	Work site / During Design Stage and Operation Phases	CEDD/HyD	√	√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM2 Shrub and Climbing Plants to soften proposed structures.	Work site / During Design Stage and Operation Phases	CEDD/HyD	√	√	√		ETWB TCW 2/2004

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Table 10.6, Figure 10.5.1-10.5.5	OM3 Buffer Tree and Shrub Planting to screen proposed roads and associated structures.	Work site / During Design Stage and Operation Phases	CEDD/HyD/	√	√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM4 Aesthetic design of proposed waterfront promenade.	Work site / During Design Stage and Operation Phases	CEDD[4]	√	√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM5 Aesthetic streetscape design.	Work site / During Design Stage and Operation Phases	CEDD/HyD	√	√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM6 Aesthetic design of roadside amenity areas.	Work site / During Design Stage and Operation Phases	CEDD/HyD	√	√	√		ETWB TCW 2/2004
For DP1 – CWB (Within the Project Boundary)								
Table 10.6, Figure 10.5.1-10.5.5	OM1 Aesthetic design of buildings and road-related structures, including viaducts, vent buildings, subways, footbridges and noise barriers and enclosure.	Work site / During Design Stage and Operation Phases	HyD	√	√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM2 Shrub and Climbing Plants to soften proposed structures	Work site / During Design Stage and Operation Phases	HyD	√	√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM3 Buffer Tree and Shrub Planting to screen proposed roads and associated structures.	Work site / During Design Stage and Operation Phases	HyD	√	√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM5 Aesthetic streetscape design.	Work site / During Design Stage and Operation Phases	HyD	√	√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM6 Aesthetic design of roadside amenity areas.	Work site / During Design Stage and Operation Phases	HyD	√	√	√		ETWB TCW 2/2004
For DP2 – WDII Major Roads (Road P2)								

[4] CEDD will identify an implementation agent

EIA Ref	Environmental Protection Measures / Mitigation Measures	Location / Timing	Implementation Agent	Implementation Stages*				Relevant Legislation and Guidelines
				Des	C	O	Dec	
Table 10.6, Figure 10.5.1-10.5.5	OM1 Aesthetic design of buildings and road-related structures, including viaducts, vent buildings, subways, footbridges and noise barriers and enclosure.	Work site / During Design Stage and Operation Phases	CEDD/HyD		√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM3 Buffer Tree and Shrub Planting to screen proposed roads and associated structures.	Work site / During Design Stage and Operation Phases	CEDD/HyD		√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM5 Aesthetic streetscape design.	Work site / During Design Stage and Operation Phases	CEDD/HyD		√	√		ETWB TCW 2/2004
Table 10.6, Figure 10.5.1-10.5.5	OM6 Aesthetic design of roadside amenity areas	Work site / During Design Stage and Operation Phases	CEDD/HyD		√	√		ETWB TCW 2/2004
For DP3 – Reclamation Works								
Table 10.6, Figure 10.5.1-10.5.5	OM4 Aesthetic design of proposed waterfront promenade.	Work site / During Design Stage and Operation Phases	CEDD[5]	√	√	√		ETWB TCW 2/2004

*Des - Design, C - Construction, O – Operation, and Dec - Decommissioning

[5] CEDD will identify an implementation agent

Appendix 4.1

Action and Limit Level

Action and Limit Level

Action and Limit Level for Noise Monitoring

Time Period	Action Level	Limit Level
07:00 – 19:00 hours on normal weekdays	When one documented complaint is received.	75 dB(A)[Note 1]

Note 1:
- 70dB(A) and 65 dB(A) for schools during normal teaching periods and school examination periods, respectively.
- If works are to be carried out during the restricted hours, the conditions stipulated in the Construction Noise Permit (CNP) issued by the Noise Control Authority have to be followed.

Action and Limit Level for Air Quality Monitoring

Monitoring Location	1-hour TSP Level in $\mu g/m^3$		24-hour TSP Level in $\mu g/m^3$	
	Action Level	Limit Level	Action Level	Limit Level
CMA1b	320.1	500	176.7	260
CMA2a	323.4	500	169.5	260
CMA3a	311.3	500	171.0	260
CMA4a	312.5	500	171.2	260
CMA5b	332.0	500	181.0	260
CMA6a	300.1	500	187.3	260

Action and Limit Level for Water Quality Monitoring

Parameters	Dry Season		Wet Season	
	Action	Limit	Action	Limit
WSD Salt Water Intake				
SS in mg L^{-1}	13.00	14.43	16.26	19.74
Turbidity in NTU	8.04	9.49	10.01	11.54
DO in mg/L	3.66	3.28	3.17	2.63
Cooling Water Intake				
SS in mg L^{-1}	15.00	22.13	18.42	27.54
Turbidity in NTU	9.10	10.25	11.35	12.71
DO in mg/L	3.36	2.73	3.02	2.44

Remarks:
- Action and Limit Level for the wet season are applied after the EPD approval of Updated EM&A Manual on 29 April 2011.

Action and Limit Level for Enhance DO Monitoring

Parameters	Depth	Dry Season		Wet Season	
		Action	Limit	Action	Limit
C6	Surface and Middle	3.13	2.00	2.60	2.00
	Bottom	4.14	3.33	2.91	2.34
C7	Surface and Middle	3.87	3.09	3.31	2.57
	Bottom	3.91	3.53	2.75	2.48
Ex-WPCWA SW	Surface and Middle	3.84	3.73	3.19	3.10
	Bottom	4.71	4.63	3.31	3.25
Ex-WPCWA SE	Surface and Middle	4.26	3.61	3.55	3.00
	Bottom	5.36	5.35	3.76	3.76

Action and Limit Levels for Odour Patrol

Parameters	Action	Limit
Odour Nuisance (from odour intensity analysis or odour patrol)	• When two documented complaint are received; or • Odour Intensity of 2 is measured from odour intensity analysis.	• Five or more consecutive genuine documented complaints within a week; or • Odour Intensity of 3 or above is measured from odour intensity analysis.

Appendix 4.2

Copies of Calibration Certificates

綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.
香港黃竹坑道37號利達中心12樓
12/F., Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
E-mail: smec@cigismec.com Website: www.cigismec.com
Tel: (852) 2873 6860
Fax: (852) 2555 7533

CERTIFICATE OF CALIBRATION

Certificate No.: 17CA0426 01-02 **Page** 1 **of** 2

Item tested

Description:	Sound Level Meter (Type 1)	,	Microphone
Manufacturer:	Larson Davis	,	PCB
Type/Model No.:	LxT1	,	377B02
Serial/Equipment No.:	0003737	,	171529
Adaptors used:	-	,	-

Item submitted by

Customer Name:	Lam Environmental Service Ltd.
Address of Customer:	-
Request No.:	-
Date of receipt:	26-Apr-2017

Date of test: 28-Apr-2017

Reference equipment used in the calibration

Description:	Model:	Serial No.	Expiry Date:	Traceable to:
Multi function sound calibrator	B&K 4226	2288444	18-Jun-2017	CIGISMEC
Signal generator	DS 360	61227	01-Apr-2018	CEPREI

Ambient conditions

Temperature:	21 ± 1 °C
Relative humidity:	50 ± 10 %
Air pressure:	1010 ± 5 hPa

Test specifications

1, The Sound Level Meter has been calibrated in accordance with the requirements as specified in BS 7580: Part 1: 1997 and the lab calibration procedure SMTP004-CA-152.

2, The electrical tests were performed using an electrical signal substituted for the microphone which was removed and replaced by an equivalent capacitance within a tolerance of ±20%.

3, The acoustic calibration was performed using an B&K 4226 sound calibrator and corrections was applied for the difference between the free-field and pressure responsess of the Sound Level Meter.

Test results

This is to certify that the Sound Level Meter conforms to BS 7580: Part 1: 1997 for the conditions under which the test was performed.

Details of the performed measurements are presented on page 2 of this certificate.

Actual Measurement data are documented on worksheets.

Approved Signatory: Huang Jian Min/Feng Jun Qi **Date:** 04-May-2017 **Company Chop:** SOILS AND MATERIALS ENGINEERING COMPANY LTD. 綜合試驗有限公司

Comments: The results reported in this certificate refer to the condition of the instrument on the date of calibration and carry no implication regarding the long-term stability of the instrument.

綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.
香港黃竹坑道37號利達中心12樓
12/F., Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
E-mail: smec@cigismec.com Website: www.cigismec.com
Tel: (852) 2873 6860
Fax: (852) 2555 7533

CERTIFICATE OF CALIBRATION

(Continuation Page)

Certificate No.: 17CA0426 01-02 **Page** 2 **of** 2

1, Electrical Tests

The electrical tests were perfomed using an equivalent capacitance substituted for the microphone. The results are given in below with test status and the estimated uncertainties. The "Pass" means the result of the test is inside the tolerances stated in the test specifications. The "-" means the result of test is outside these tolerances.

Test:	Subtest:	Status:	Expanded Uncertainty (dB)	Coverage Factor
Self-generated noise	A	Pass	0.3	
	C	Pass	0.8	2.1
	Lin	Pass	1.6	2.2
Linearity range for Leq	At reference range , Step 5 dB at 4 kHz	Pass	0.3	
	Reference SPL on all other ranges	Pass	0.3	
	2 dB below upper limit of each range	Pass	0.3	
	2 dB above lower limit of each range	Pass	0.3	
Linearity range for SPL	At reference range , Step 5 dB at 4 kHz	Pass	0.3	
Frequency weightings	A	Pass	0.3	
	C	Pass	0.3	
	Lin	Pass	0.3	
Time weightings	Single Burst Fast	Pass	0.3	
	Single Burst Slow	Pass	0.3	
Peak response	Single 100μs rectangular pulse	N/A	N/A	
R.M.S. accuracy	Crest factor of 3	Pass	0.3	
Time weighting I	Single burst 5 ms at 2000 Hz	Pass	0.3	
	Repeated at frequency of 100 Hz	Pass	0.3	
Time averaging	1 ms burst duty factor $1/10^3$ at 4kHz	Pass	0.3	
	1 ms burst duty factor $1/10^4$ at 4kHz	Pass	0.3	
Pulse range	Single burst 10 ms at 4 kHz	Pass	0.4	
Sound exposure level	Single burst 10 ms at 4 kHz	Pass	0.4	
Overload indication	SPL	Pass	0.3	
	Leq	Pass	0.4	

2, Acoustic tests

The complete sound level meter was calibrated on the reference range using a B&K 4226 acoustic calibrator with 1000Hz and SPL 94 dB. The sensitivity of the sound level meter was adjusted. The test result at 125 Hz and 8000 Hz are given in below with test status and the estimated uncertainties.

Test:	Subtest	Status	Expanded Uncertainty (dB)	Coverage Factor
Acoustic response	Weighting A at 125 Hz	Pass	0.3	
	Weighting A at 8000 Hz	Pass	0.5	

3, Response to associated sound calibrator

N/A

The expanded uncertainties have been calculated in accordance with the ISO Publication "Guide to the expression of uncertainty in measurement", and gives an interval estimated to have a level of confidence of 95%. A coverage factor of 2 is assumed unless explicitly stated.

- End -

Calibrated by: Lai Sheng Jie **Date:** 28-Apr-2017

Checked by: Fung Chi Yip **Date:** 04-May-2017

The standard(s) and equipment used in the calibration are traceable to national or international recognised standards and are calibrated on a schedule to maintain the required accuracy level.

綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.
香港黃竹坑道37號利達中心12樓
12/F., Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
E-mail: smec@cigismec.com Website: www.cigismec.com
Tel: (852) 2873 6860
Fax: (852) 2555 7533

HOKLAS 028 CAL

CERTIFICATE OF CALIBRATION

Certificate No.: 16CA1117 01-02 **Page:** 1 of 2

Item tested

Description:	Acoustical Calibrator (Class 1)
Manufacturer:	Rion Co., Ltd.
Type/Model No.:	NC-73
Serial/Equipment No.:	10707358
Adaptors used:	-

Item submitted by

Curstomer:	Lam Geotechnics Ltd.
Address of Customer:	-
Request No.:	-
Date of receipt:	17-Nov-2016

Date of test: 18-Nov-2016

Reference equipment used in the calibration

Description:	Model:	Serial No.	Expiry Date:	Traceable to:
Lab standard microphone	B&K 4180	2412857	14-Apr-2017	SCL
Preamplifier	B&K 2673	2239857	28-Apr-2017	CEPREI
Measuring amplifier	B&K 2610	2346941	26-Apr-2017	CEPREI
Signal generator	DS 360	61227	18-Apr-2017	CEPREI
Digital multi-meter	34401A	US36087050	18-Apr-2017	CEPREI
Audio analyzer	8903B	GB41300350	19-Apr-2017	CEPREI
Universal counter	53132A	MY40003662	19-Apr-2017	CEPREI

Ambient conditions

Temperature:	23 ± 1 °C
Relative humidity:	50 ± 10 %
Air pressure:	1005 ± 5 hPa

Test specifications

1, The Sound Calibrator has been calibrated in accordance with the requirements as specified in IEC 60942 1997 Annex B and the lab calibration procedure SMTP004-CA-156.

2, The calibrator was tested with its axis vertical facing downwards at the specific frequency using insert voltage technique.

3, The results are rounded to the nearest 0.01 dB and 0.1 Hz and have not been corrected for variations from a reference pressure of 1013.25 hectoPascals as the maker's information indicates that the instrument is insensitive to pressure changes.

Test results

This is to certify that the sound calibrator conforms to the requirements of annex B of IEC 60942: 1997 for the conditions under which the test was performed. This does not imply that the sound calibrator meets IEC 60942 under any other conditions.

Details of the performed measurements are presented on **page 2** of this certificate.

Approved Signatory: Huang Jian Min/Feng Jun Qi **Date:** 21-Nov-2016 **Company Chop:** SOILS AND MATERIALS ENGINEERING COMPANY LTD. 綜合試驗有限公司

Comments: The results reported in this certificate refer to the conditon of the instrument on the date of calibration and carry no implication regarding the long-term stability of the instrument.

綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.
香港黃竹坑道37號利達中心12樓
12/F., Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
E-mail: smec@cigismec.com Website: www.cigismec.com
Tel: (852) 2873 6860
Fax: (852) 2555 7533

CERTIFICATE OF CALIBRATION

(Continuation Page)

1, Measured Sound Pressure Level

The output Sound Pressure Level in the calibrator head was measured at the setting and frequency shown using a calibrated laboratory standard microphone and insert voltage technique. The results are given in below with the estimated uncertainties.

(Output level in dB re 20 μPa)

Frequency Shown Hz	Output Sound Pressure Level Setting dB	Measured Output Sound Pressure Level dB	Estimated Expanded Uncertainty dB
1000	94.00	94.12	0.10

2, Sound Pressure Level Stability - Short Term Fluctuations

The Short Term Fluctuations was determined by measuring the maximum and minimum of the fast weighted DC output of the B&K 2610 measuring amplifier over a 20 second time interval as required in the standard. The Short Term Fluctuation was found to be:

At 1000 Hz **STF = 0.002 dB**

Estimated expanded uncertainty 0.005 dB

3, Actual Output Frequency

The determination of actual output frequency was made using a B&K 4180 microphone together with a B&K 2673 preamplifier connected to a B&K 2610 measuring amplifier. The AC output of the B&K 2610 was taken to an universal counter which was used to determine the frequency averaged over 20 second of operation as required by the standard. The actual output frequency at 1 KHz was:

At 1000 Hz **Actual Frequency = 991.6 Hz**

Estimated expanded uncertainty 0.1 Hz Coverage factor k = 2.2

4, Total Noise and Distortion

For the Total Noise and Distortion measurement, the unfiltered AC output of the B&K 2610 measuring amplifier was connected to an Agilent Type 8903 B distortion analyser. The TND result at 1 KHz was:

At 1000 Hz **TND = 0.6 %**

Estimated expanded uncertainty 0.7 %

The expanded uncertainties have been calculated in accordance with the ISO Publication "Guide to the expression of uncertainty in measurement", and gives an interval estimated to have a level of confidence of 95%. A coverage factor of 2 is assumed unless explicitly stated.

- End -

Calibrated by: Fung Chi Yip **Checked by:** Lam Tze Wai

Date: 18-Nov-2016 **Date:** 21-Nov-2016

The standard(s) and equipment used in the calibration are traceable to national or international recognised standards and are calibrated on a schedule to maintain the required accuracy level.

Calibration Certificate

Certificate Number 2016009653

Customer:

Model Number	CAL200	***Procedure Number***	D0001.8386		
Serial Number	13437	***Technician***	Scott Montgomery		
Test Results	**Pass**	***Calibration Date***	2 Nov 2016		
Initial Condition	As Manufactured	***Calibration Due***			
		Temperature	25	°C	± 0.3 °C
Description	Larson Davis CAL200 Acoustic Calibrator	***Humidity***	28	%RH	± 3 %RH
		Static Pressure	101.2	kPa	± 1 kPa

Evaluation Method The data is aquired by the insert voltage calibration method using the reference microphone's open circuit sensitivity. Data reported in dB re 20 µPa.

Compliance Standards Compliant to Manufacturer Specifications per D0001.8190 and the following standards:
IEC 60942:2003 ANSI S1.40-2006

Issuing lab certifies that the instrument described above meets or exceeds all specifications as stated in the referenced procedure (unless otherwise noted). It has been calibrated using measurement standards traceable to the SI through the National Institute of Standards and Technology (NIST), or other national measurement institutes, and meets the requirements of ISO/IEC 17025:2005.
Test points marked with a ‡ in the uncertainties column do not fall within this laboratory's scope of accreditation.

The quality system is registered to ISO 9001:2008.

This calibration is a direct comparison of the unit under test to the listed reference standards and did not involve any sampling plans to complete. No allowance has been made for the instability of the test device due to use, time, etc. Such allowances would be made by the customer as needed.

The uncertainties were computed in accordance with the ISO Guide to the Expression of Uncertainty in Measurement (GUM). A coverage factor of approximately 2 sigma (k=2) has been applied to the standard uncertainty to express the expanded uncertainty at approximately 95% confidence level.

Standards Used

Description	Cal Date	Cal Due	Cal Standard
Agilent 34401A DMM	09/07/2016	09/07/2017	001021
Sound Level Meter / Real Time Analyzer	04/07/2016	04/07/2017	001051
Microphone Calibration System	08/17/2016	08/17/2017	005446
1/2" Preamplifier	10/06/2016	10/06/2017	006506
Larson Davis 1/2" Preamplifier 7-pin LEMO	08/22/2016	08/22/2017	006507
1/2 inch Microphone - RI - 200V	03/15/2016	03/15/2017	006510
Pressure Transducer	07/01/2016	07/01/2017	007368

Larson Davis, a division of PCB Piezotronics, Inc
1681 West 820 North
Provo, UT 84601, United States
716-684-0001

ACCREDITED Cert. #3622.01

LARSON DAVIS
A PCB PIEZOTRONICS DIV.

REPORT OF EQUIPMENT PERFORMANCE CHECK / CALIBRATION

Information supplied by customer:

CONTACT:	**MR. SAM LAM**	**WORK ORDER:**	**HK1710557**
CLIENT:	**LAM GEOTECHNICS LIMITED**		
DATE RECEIVED:	**11/07/2017**		
DATE OF ISSUE:	**18/07/2017**		
ADDRESS:	**11/F, CENTRE POINT, 181-185, GLOUCESTER ROAD, WANCHAI, HONG KONG**		
PROJECT:	---		

METHOD OF PERFORMANCE CHECK/ CALIBRATION:
Ref: APHA22nd ed 2130B

COMMENTS
It is certified that the item under performance check/calibration has been calibrated/checked by corresponding calibrated equipment in the laboratory.
Maximum Tolerance and calibration frequency stated in the report, unless otherwise stated, the internal acceptance criteria of Pilot Testing Limited will be followed.

Scope of Test:	Turbidity
Equipment Type:	Turbidimeter
Brand Name:	Xin Rui
Model No.:	WGZ-3B
Serial No.:	1403009
Equipment No.:	---
Date of Calibration:	17/07/2017

Remarks:
This is the Final Report. Results apply to sample(s) as submitted. All pages of this report have been checked and approved for release.

Approved Signatory: _____ Issue Date: 18/07/2017

Ms. Wong Po Yan, Pauline
Assistant Laboratory Manager

Address: No.B12, 5th Floor, Block B, Tonic Industrial Centre, No.19 Lam Hing Street, Kowloon Bay, Kowloon
Phone +852 2527 6691 | Email info@pilot-testing.com

REPORT OF EQUIPMENT PERFORMANCE CHECK / CALIBRATION

WORK ORDER: HK1710557
DATE OF ISSUE: 18/07/2017
CLIENT: LAM GEOTECHNICS LIMITED

Equipment Type:	Turbidimeter
Brand Name:	Xin Rui
Model No.:	WGZ-3B
Serial No.:	1403009
Equipment No.:	---
Date of Calibration:	17/07/2017
Date of next Calibation:	17/10/2017

Parameters:
Turbidity

Method Ref: APHA 22nd ed. 2130B

Expected Reading (NTU)	Display Reading (NTU)	Tolerance
0	0.00	---
4	3.88	-3.0%
10	9.81	-1.9%
40	39.2	-2.1%
100	101	1.1%
400	400	0.0%
1000	1000	0.0%
	Tolerance Limit (±)	10%

Remark: "Displayed Reading" presents the figures shown on item under calibration/checking regardless of equipment precision or significant figures.

Address: No.B12, 5th Floor, Block B, Tonic Industrial Centre, No.19 Lam Hing Street, Kowloon Bay, Kowloon
Phone +852 2527 6691 | Email info@pilot-testing.com

REPORT OF EQUIPMENT PERFORMANCE CHECK / CALIBRATION

Information supplied by customer:

CONTACT:	**MR. SAM LAM**	**WORK ORDER:**	**HK1710600**
CLIENT:	**LAM GEOTECHNICS LIMITED**		
DATE RECEIVED:	**28/07/2017**		
DATE OF ISSUE:	**31/07/2017**		
ADDRESS:	**11/F, CENTRE POINT, 181-185, GLOUCESTER ROAD, WANCHAI, HONG KONG**		
PROJECT:	---		

METHOD OF PERFORMANCE CHECK/ CALIBRATION:
Ref: APHA22nd ed 2130B

COMMENTS
It is certified that the item under performance check/calibration has been calibrated/checked by corresponding calibrated equipment in the laboratory.
Maximum Tolerance and calibration frequency stated in the report, unless otherwise stated, the internal acceptance criteria of Pilot Testing Limited will be followed.

Scope of Test:	Turbidity
Equipment Type:	Turbidimeter
Brand Name:	Xin Rui
Model No.:	WGZ-3B
Serial No.:	1309192
Equipment No.:	---
Date of Calibration:	31/07/2017

Remarks:
This is the Final Report. Results apply to sample(s) as submitted. All pages of this report have been checked and approved for release.

Approved Signatory: _____ Issue Date: 31/07/2017

Ms. Wong Po Yan, Pauline
Assistant Laboratory Manager

Address: No.B12, 5th Floor, Block B, Tonic Industrial Centre, No.19 Lam Hing Street, Kowloon Bay, Kowloon
Phone +852 2527 6691 | Email info@pilot-testing.com

REPORT OF EQUIPMENT PERFORMANCE CHECK / CALIBRATION

WORK ORDER: HK1710600
DATE OF ISSUE: 31/07/2017
CLIENT: LAM GEOTECHNICS LIMITED

Equipment Type:	Turbidimeter
Brand Name:	Xin Rui
Model No.:	WGZ-3B
Serial No.:	1309192
Equipment No.:	---
Date of Calibration:	31/07/2017
Date of next Calibation:	31/10/2017

Parameters:
Turbidity

Method Ref: APHA 22nd ed. 2130B

Expected Reading (NTU)	Display Reading (NTU)	Tolerance
0	0.00	---
4	4.00	0.0%
10	9.92	-0.8%
40	40.6	1.5%
100	97.8	-2.2%
400	425	6.3%
1000	1000	0.0%
	Tolerance Limit (±)	10%

Remark: "Displayed Reading" presents the figures shown on item under calibration/checking regardless of equipment precision or significant figures.

Address: No.B12, 5th Floor, Block B, Tonic Industrial Centre, No.19 Lam Hing Street, Kowloon Bay, Kowloon
Phone +852 2527 6691 | Email info@pilot-testing.com

REPORT OF EQUIPMENT PERFORMANCE CHECK / CALIBRATION

Information supplied by customer:

CONTACT:	**MR. SAM LAM**	**WORK ORDER:**	**HK1710434**
CLIENT:	**LAM GEOTECHNICS LIMITED**		
DATE RECEIVED:	**02/06/2017**		
DATE OF ISSUE:	**06/06/2017**		
ADDRESS:	**11/F, CENTRE POINT, 181-185, GLOUCESTER ROAD, WANCHAI, HONG KONG**		
PROJECT:	---		

METHOD OF PERFORMANCE CHECK/ CALIBRATION:
Ref: APHA22nd ed 2130B

COMMENTS
It is certified that the item under performance check/calibration has been calibrated/checked by corresponding calibrated equipment in the laboratory.
Maximum Tolerance and calibration frequency stated in the report, unless otherwise stated, the internal acceptance criteria of Pilot Testing Limited will be followed.

Scope of Test:	Turbidity
Equipment Type:	Turbidimeter
Brand Name:	Xin Rui
Model No.:	WGZ-3B
Serial No.:	1512036
Equipment No.:	---
Date of Calibration:	05/06/2017

Remarks:
This is the Final Report. Results apply to sample(s) as submitted. All pages of this report have been checked and approved for release.

Approved Signatory: _____ Issue Date: 06/06/2017

Ms. Wong Po Yan, Pauline
Assistant Laboratory Manager

Address: No.B12, 5th Floor, Block B, Tonic Industrial Centre, No.19 Lam Hing Street, Kowloon Bay, Kowloon
Phone +852 2527 6691 | Email info@pilot-testing.com

REPORT OF EQUIPMENT PERFORMANCE CHECK / CALIBRATION

WORK ORDER: HK1710434
DATE OF ISSUE: 06/06/2017
CLIENT: LAM GEOTECHNICS LIMITED

Equipment Type:	Turbidimeter
Brand Name:	Xin Rui
Model No.:	WGZ-3B
Serial No.:	1512036
Equipment No.:	---
Date of Calibration:	05/06/2017
Date of next Calibation:	05/09/2017

Parameters:
Turbidity

Method Ref: APHA 22nd ed. 2130B

Expected Reading (NTU)	Display Reading (NTU)	Tolerance
0	0.00	---
4	4.01	0.2%
10	9.87	-1.3%
40	39.4	-1.5%
100	101	0.6%
400	400	0.0%
1000	1000	0.0%
	Tolerance Limit (±)	10%

Remark: "Displayed Reading" presents the figures shown on item under calibration/checking regardless of equipment precision or significant figures.

Address: No.B12, 5th Floor, Block B, Tonic Industrial Centre, No.19 Lam Hing Street, Kowloon Bay, Kowloon
Phone +852 2527 6691 | Email info@pilot-testing.com

REPORT OF EQUIPMENT PERFORMANCE CHECK / CALIBRATION

Information supplied by customer:

CONTACT:	**MR. SAM LAM**	**WORK ORDER:**	**HK1710724**
CLIENT:	**LAM GEOTECHNICS LIMITED**		
DATE RECEIVED:	**01/09/2017**		
DATE OF ISSUE:	**04/09/2017**		
ADDRESS:	**11/F, CENTRE POINT, 181-185, GLOUCESTER ROAD, WANCHAI, HONG KONG**		
PROJECT:	---		

METHOD OF PERFORMANCE CHECK/ CALIBRATION:
Ref: APHA22nd ed 2130B

COMMENTS
It is certified that the item under performance check/calibration has been calibrated/checked by corresponding calibrated equipment in the laboratory.
Maximum Tolerance and calibration frequency stated in the report, unless otherwise stated, the internal acceptance criteria of Pilot Testing Limited will be followed.

Scope of Test:	Turbidity
Equipment Type:	Turbidimeter
Brand Name:	Xin Rui
Model No.:	WGZ-3B
Serial No.:	1512036
Equipment No.:	---
Date of Calibration:	01/09/2017

Remarks:
This is the Final Report. Results apply to sample(s) as submitted. All pages of this report have been checked and approved for release.

Approved Signatory: _____ Issue Date: 04/09/2017

Ms. Wong Po Yan, Pauline
Assistant Laboratory Manager

Address: No.B12, 5th Floor, Block B, Tonic Industrial Centre, No.19 Lam Hing Street, Kowloon Bay, Kowloon
Phone +852 2527 6691 | Email info@pilot-testing.com

REPORT OF EQUIPMENT PERFORMANCE CHECK / CALIBRATION

WORK ORDER: HK1710724
DATE OF ISSUE: 04/09/2017
CLIENT: LAM GEOTECHNICS LIMITED

Equipment Type:	Turbidimeter
Brand Name:	Xin Rui
Model No.:	WGZ-3B
Serial No.:	1512036
Equipment No.:	---
Date of Calibration:	01/09/2017
Date of next Calibation:	01/12/2017

Parameters:
Turbidity

Method Ref: APHA 22nd ed. 2130B

Expected Reading (NTU)	Display Reading (NTU)	Tolerance
0	0.00	---
4	4.18	4.5%
10	9.93	-0.7%
40	37.9	-5.3%
100	108	8.0%
400	383	-4.3%
1000	976	-2.4%
	Tolerance Limit (±)	10%

Remark: "Displayed Reading" presents the figures shown on item under calibration/checking regardless of equipment precision or significant figures.

Address: No.B12, 5th Floor, Block B, Tonic Industrial Centre, No.19 Lam Hing Street, Kowloon Bay, Kowloon
Phone +852 2527 6691 | Email info@pilot-testing.com

PILOT TESTING

EQUIPMENT PERFORMANCE CHECK / CALIBRATION REPORT

Report No.	:	HK1710621
Project Name	:	EQUIPMENT PERFORMANCE CHECK/CALIBRATION REPORT
Date of Issue	:	04/08/2017
Customer	:	LAM ENVIRONMENTAL SERVICES LIMITED
Address	:	11/F., CENTRE POINT, 181-185 GLOUCESTER ROAD, WAN CHAI, HONG KONG
Calibration Job No.	:	HK1710621
Test Item No.	:	HK1710621-01
Test Item Details		
Test Item Description	:	Sonde
Manufacturer	:	YSI
Model No.	:	Professional Plus
Serial No.	:	14E100105
Performance Method	:	Checked according to in-house method CAL005 (References: Temperature (Section 6 of International Accreditation New Zealand Technical Guide No. 3 Second edition March 2008: Working Thermometer Calibration Procedure), pH value (APHA 21e 4500H:B), Salinity (Refer to Conductivity APHA 19e 2510B) , Dissolved oxygen (APHA 19e 4500-O,C))
Test Item Receipt Date	:	02/08/2017
Test Item Calibration Date	:	03/08/2017

Notes :
1. This report shall not be reproduced, except in full, without prior approval from Pilot Testing Limited.
2. Results relate to item(s) as received.
3. ± indicates the tolerance limit
4. N/A = Not applicable
5. APHA - American Public Health Association, American Water Works Association and Water Environment Federation, Standard Methods for the Examination of Water and Wastewater, APHA-AWWA-WEF. USA
6. DO, pH, salinity and temperature performance check was conducted by Pilot Testing Limited.
7. Because of high sensitivity and ease of measurement, the conductivity method (according to APHA 19e 2510) is used to determine salinity.

Approved Signatory : 

Ms. Wong Po Yan, Pauline
(Assistant Laboratory Manager)

Issue Date: 04/08/2017

Pilot Testing Limited
Address: Room B12, Block B, 5/F, Tonic Industrial Centre, 19 Lam Hing Street, Kowloon Bay, Kowloon
Tel: (852) 2527 6691 email: test@pilot-testing.com

PILOT TESTING

REPORT OF EQUIPMENT PERFORMANCE CHECK/CALIBRATION

WORK ORDER: HK1710621
DATE OF ISSUE: 04/08/2017
CLIENT: LAM ENVIRONMENTAL SERVICES LIMITED

Equipment Type	Sonde
Manufacturer	YSI
Model No.	Professional Plus
Serial No.	14E100105
Date of Calibration	03-Aug-17
Date of next Calibation	03-Nov-17

Parameters:

Temperature (Method Ref: Section 6 of International Accreditation New Zealand Technical Guide No.3 Second edition March 2008: Working Thermometer Calibration Procedure)

Reference Reading (°C)	Display Reading (°C)	Deviation (°C)
6.5	6.4	-0.1
15.6	15.5	-0.1
26.0	25.6	-0.4
	Tolerance Limit	±2.0

pH Value (Method Ref: APHA21e, 4500H:B)

Expected Reading (pH unit)	Reference Reading (pH unit)	Display Reading (pH unit)	Deviation (pH unit)
4.0	3.88	3.77	-0.11
7.0	6.90	6.98	0.08
10.0	9.86	9.81	-0.05
	Tolerance Limit		±0.20

Conductivity (Method Ref: APHA 19e, 2510)

KCl concentration (mol/L)	Reference Reading (ms/cm)	Display Reading (ms/cm)	Deviation (%)
0.0000	0.00	0.00	--
0.1000	12.0	11.9	-0.83
0.2000	24.1	23.8	-1.24
0.5000	54.7	53.8	-1.65
	Tolerance Limit		±2.0

Dissolved Oxygen (DO) (Method Ref: APHA 19e, 4500-O, C)

Reference DO reading (mg/L)	DO reading od DO probe (mg/L)	Deviation (mg/L)
9.00	8.89	-0.11
6.62	6.71	0.09
4.64	4.55	-0.09
	Tolerance Limit	±0.20

Remarks:
(1) Maxium tolerance and calibration frequency stated in the report, unless otherewise stated, the internal acceptance criteria of Pilot Testing Limited will be followed.
(2) Displayed reading presents the figures shown on item under calibration/checking regardless of equipment precision or significant figures.
(3) Because of high sensitivity and ease of measurement, the conductivity method (accoridng to APHA 19e 2510) is used to determine salinity.

- End of Report -

PILOT TESTING

EQUIPMENT PERFORMANCE CHECK / CALIBRATION REPORT

Report No.	:	HK1710517
Project Name	:	EQUIPMENT PERFORMANCE CHECK/CALIBRATION REPORT
Date of Issue	:	04/07/2017
Customer	:	LAM ENVIRONMENTAL SERVICE LIMITED
Address	:	11/F., CENTRE POINT, 181-185 GLOUCESTER ROAD, WAN CHAI, HONG KONG
Calibration Job No.	:	HK1710517
Test Item No.	:	HK1710517-01
Test Item Details		
Test Item Description	:	Sonde
Manufacturer	:	YSI
Model No.	:	Professional Plus
Serial No.	:	17E100236
Performance Method	:	Checked according to in-house method CAL005 (References: Temperature (Section 6 of International Accreditation New Zealand Technical Guide No. 3 Second edition March 2008: Working Thermometer Calibration Procedure), pH value (APHA 21e 4500H:B), Salinity (Refer to Conductivity APHA 19e 2510B) , Dissolved oxygen (APHA 19e 4500-O,C))
Test Item Receipt Date	:	29/06/2017
Test Item Calibration Date	:	29/06/2017

Notes :
1. This report shall not be reproduced, except in full, without prior approval from Pilot Testing Limited.
2. Results relate to item(s) as received.
3. ± indicates the tolerance limit
4. N/A = Not applicable
5. APHA - American Public Health Association, American Water Works Association and Water Environment Federation, Standard Methods for the Examination of Water and Wastewater, APHA-AWWA-WEF. USA
6. DO, pH, salinity and temperature performance check was conducted by Pilot Testing Limited.
7. Because of high sensitivity and ease of measurement, the conductivity method (according to APHA 19e 2510) is used to determine salinity.

Approved Signatory :

Ms. Wong Po Yan, Pauline
(Assistant Laboratory Manager)

Issue Date: 04/07/2017

PILOT TESTING

REPORT OF EQUIPMENT PERFORMANCE CHECK/CALIBRATION

WORK ORDER: HK1710517
DATE OF ISSUE: 04/07/2017
CLIENT: LAM ENVIRONMENTAL SERVICE LIMITED

Equipment Type	Sonde
Manufacturer	YSI
Model No.	Professional Plus
Serial No.	17E100236
Date of Calibration	29-Jun-17
Date of next Calibation	29-Sep-17

Parameters:

Temperature (Method Ref: Section 6 of International Accreditation New Zealand Technical Guide No.3 Second edition March 2008: Working Thermometer Calibration Procedure)

Reference Reading (°C)	Display Reading (°C)	Deviation (°C)
6.9	6.8	-0.1
13.4	13.3	-0.1
25.4	25.6	0.2
	Tolerance Limit	±2.0

pH Value (Method Ref: APHA21e, 4500H:B)

Expected Reading (pH unit)	Reference Reading (pH unit)	Display Reading (pH unit)	Deviation (pH unit)
4.0	4.00	3.97	-0.03
7.0	6.98	7.07	0.09
10.0	9.94	9.96	0.02
	Tolerance Limit		±0.20

Conductivity (Method Ref: APHA 19e, 2510)

KCl concentration (mol/L)	Reference Reading (ms/cm)	Display Reading (ms/cm)	Deviation (%)
0.0000	0.00	0.00	--
0.1000	13.00	12.90	-0.77
0.2000	24.60	24.20	-1.63
0.5000	57.40	56.80	-1.05
	Tolerance Limit		±2.0

Dissolved Oxygen (DO) (Method Ref: APHA 19e, 4500-O, C)

Reference DO reading (mg/L)	DO reading od DO probe (mg/L)	Deviation (mg/L)
7.59	7.43	-0.16
5.36	5.46	0.10
4.48	4.52	0.04
	Tolerance Limit	±0.20

Remarks:
(1) Maxium tolerance and calibration frequency stated in the report, unless otherewise stated, the internal acceptance criteria of Pilot Testing Limited will be followed.
(2) Displayed reading presents the figures shown on item under calibration/checking regardless of equipment precision or significant figures.
(3) Because of high sensitivity and ease of measurement, the conductivity method (accoridng to APHA 19e 2510) is used to determine salinity.

- End of Report -

PILOT TESTING

EQUIPMENT PERFORMANCE CHECK / CALIBRATION REPORT

Report No.	:	HK1710708
Project Name	:	EQUIPMENT PERFORMANCE CHECK/CALIBRATION REPORT
Date of Issue	:	07/09/2017
Customer	:	LAM ENVIRONMENTAL SERVICES LIMITED
Address	:	11/F., CENTRE POINT, 181-185 GLOUCESTER ROAD, WAN CHAI, HONG KONG

Calibration Job No.	:	HK1710708
Test Item No.	:	HK1710708-01
Test Item Details		
Test Item Description	:	Sonde
Manufacturer	:	YSI
Model No.	:	Professional Plus
Serial No.	:	16J100298
Performance Method	:	Checked according to in-house method CAL005 (References: Temperature (Section 6 of International Accreditation New Zealand Technical Guide No. 3 Second edition March 2008: Working Thermometer Calibration Procedure), pH value (APHA 21e 4500H:B), Salinity (Refer to Conductivity APHA 19e 2510B) , Dissolved oxygen (APHA 19e 4500-O,C))
Test Item Receipt Date	:	29/08/2017
Test Item Calibration Date	:	06/09/2017

Notes :
1. This report shall not be reproduced, except in full, without prior approval from Pilot Testing Limited.
2. Results relate to item(s) as received.
3. ± indicates the tolerance limit
4. N/A = Not applicable
5. APHA - American Public Health Association, American Water Works Association and Water Environment Federation, Standard Methods for the Examination of Water and Wastewater, APHA-AWWA-WEF. USA
6. DO, pH, salinity and temperature performance check was conducted by Pilot Testing Limited.
7. Because of high sensitivity and ease of measurement, the conductivity method (according to APHA 19e 2510) is used to determine salinity.

Approved Signatory : Issue Date: 07/09/2017

Ms. Wong Po Yan, Pauline
(Assistant Laboratory Manager)

PILOT TESTING

REPORT OF EQUIPMENT PERFORMANCE CHECK/CALIBRATION

WORK ORDER: HK1710708
DATE OF ISSUE: 07/09/2017
CLIENT: LAM ENVIRONMENTAL SERVICES LIMITED

Equipment Type	Sonde
Manufacturer	YSI
Model No.	Professional Plus
Serial No.	16J100298
Date of Calibration	06-Sep-17
Date of next Calibation	06-Dec-17

Parameters:

Temperature (Method Ref: Section 6 of International Accreditation New Zealand Technical Guide No.3 Second edition March 2008: Working Thermometer Calibration Procedure)

Reference Reading (°C)	Display Reading (°C)	Deviation (°C)
5.7	5.7	0.0
14.5	14.5	0.0
23.4	23.4	0.0
	Tolerance Limit	±2.0

pH Value (Method Ref: APHA21e, 4500H:B)

Expected Reading (pH unit)	Reference Reading (pH unit)	Display Reading (pH unit)	Deviation (pH unit)
4.0	4.02	4.00	-0.02
7.0	7.03	7.00	-0.03
10.0	10.19	10.05	-0.14
	Tolerance Limit		±0.20

Conductivity (Method Ref: APHA 19e, 2510)

KCl concentration (mol/L)	Reference Reading (ms/cm)	Display Reading (ms/cm)	Deviation (%)
0.0000	0.00	0.00	--
0.1000	13.2	13.3	0.76
0.2000	25.2	25.1	-0.40
0.5000	54.7	54.7	0.00
	Tolerance Limit		±2.0

Dissolved Oxygen (DO) (Method Ref: APHA 19e, 4500-O, C)

Reference DO reading (mg/L)	DO reading od DO probe (mg/L)	Deviation (mg/L)
7.23	7.40	0.17
6.63	6.52	-0.11
5.43	5.40	-0.03
	Tolerance Limit	±0.20

Remarks:
(1) Maxium tolerance and calibration frequency stated in the report, unless otherewise stated, the internal acceptance criteria of Pilot Testing Limited will be followed.
(2) Displayed reading presents the figures shown on item under calibration/checking regardless of equipment precision or significant figures.
(3) Because of high sensitivity and ease of measurement, the conductivity method (accoridng to APHA 19e 2510) is used to determine salinity.

- End of Report -

TISCH Environmental

TISCH ENVIRONMENTAL, INC.
145 SOUTH MIAMI AVE
VILLAGE OF CLEVES, OH
45002
513.467.9000
877.263.7610 TOLL FREE
513.467.9009 FAX

ORIFICE TRANSFER STANDARD CERTIFICATION WORKSHEET TE-5025A

Date - May 20, 2016 Rootsmeter S/N 0438320 Ta (K) - 293
Operator Tisch Orifice I.D. - 3166 Pa (mm) - 748.03

PLATE OR Run #	VOLUME START (m3)	VOLUME STOP (m3)	DIFF VOLUME (m3)	DIFF TIME (min)	METER DIFF Hg (mm)	ORFICE DIFF H2O (in.)
1	NA	NA	1.00	1.4270	3.2	2.00
2	NA	NA	1.00	1.0220	6.4	4.00
3	NA	NA	1.00	0.9100	7.9	5.00
4	NA	NA	1.00	0.8730	8.8	5.50
5	NA	NA	1.00	0.7180	12.7	8.00

DATA TABULATION

Vstd	(x axis) Qstd	(y axis)
0.9967	0.6985	1.4150
0.9925	0.9711	2.0010
0.9904	1.0883	2.2372
0.9892	1.1332	2.3464
0.9840	1.3705	2.8299

Qstd slope (m) = 2.10714
intercept (b) = -0.05158
coefficient (r) = 0.99978

y axis = SQRT[H2O(Pa/760)(298/Ta)]

Va	(x axis) Qa	(y axis)
0.9957	0.6977	0.8851
0.9915	0.9701	1.2517
0.9893	1.0872	1.3995
0.9882	1.1320	1.4678
0.9830	1.3691	1.7702

Qa slope (m) = 1.31946
intercept (b) = -0.03226
coefficient (r) = 0.99978

y axis = SQRT[H2O(Ta/Pa)]

CALCULATIONS

Vstd = Diff. Vol[(Pa-Diff. Hg)/760](298/Ta)
Qstd = Vstd/Time

Va = Diff Vol [(Pa-Diff Hg)/Pa]
Qa = Va/Time

For subsequent flow rate calculations:

Qstd = 1/m{[SQRT(H2O(Pa/760)(298/Ta))]- b}
Qa = 1/m{[SQRT H2O(Ta/Pa)]- b}

Calibration Data for High Volume Sampler (TSP Sampler)

Location	:	CMA1b	**Calibration Date**	:	27-Sep-17
Equipment no.	:	HVS001	**Calibration Due Date**	:	27-Nov-17

CALIBRATION OF CONTINUOUS FLOW RECORDER

Ambient Condition					
Temperature, T_a	303	Kelvin	**Pressure, P_a**	1010	mmHg

Orifice Transfer Standard Information					
Equipment No.	**Ori001**	**Slope, m_c**	2.02533	**Intercept, bc**	-0.03593
Last Calibration Date	20-Mar-17	$(H \times P_a / 1013.3 \times 298 / T_a)^{1/2}$			
Next Calibration Date	20-Mar-18	$m_c \times Q_{std} + b_c$			

Calibration of TSP

Calibration Point	**Manometer Reading H (inches of water)** (up)	(down)	(difference)	**Q_{std}** (m^3 / min.) **X-axis**	**Continuous Flow Recorder, W** (CFM)	**IC** ($W(P_a/1013.3 \times 298/T_a)^{1/2}/35.31$) **Y-axis**
1	1.4	1.4	2.8	0.8358	28	27.7228
2	2.3	2.3	4.6	1.0662	34	33.6634
3	3.6	3.6	7.2	1.3295	44	43.5643
4	4.6	4.6	9.2	1.5005	50	49.5049
5	5.7	5.7	11.4	1.6683	57	56.4356

By Linear Regression of Y on X

Slope, m	=	34.7539	Intercept, b	=	-2.3088
Correlation Coefficient*	=	0.9973			
Calibration Accepted	=	Yes/~~No~~**			

* if Correlation Coefficient < 0.990, check and recalibration again.

** Delete as appropriate.

Remarks : As per client's provided information, the equipment reference no. of the calibrated High Volume Sampler has been re-assigned from EL452 to HVS001 with respect to the update in quality management system.

Calibrated by	:	Jackey MA	**Checked by**	:	Pauline Wong
Date	:	27-Sep-17	**Date**	:	27-Sep-17

Calibration Data for High Volume Sampler (TSP Sampler)

Location	:	CMA2a	**Calibration Date**	:	27-Sep-17
Equipment no.	:	HVS002	**Calibration Due Date**	:	27-Nov-17

CALIBRATION OF CONTINUOUS FLOW RECORDER

Ambient Condition					
Temperature, T_a	303	Kelvin	**Pressure, P_a**	1010	mmHg

Orifice Transfer Standard Information					
Equipment No.	**Ori001**	**Slope, m_c**	2.02533	**Intercept, bc**	-0.03593
Last Calibration Date	20-Mar-17	$(H \times P_a / 1013.3 \times 298 / T_a)^{1/2}$			
Next Calibration Date	20-Mar-18	$m_c \times Q_{std} + b_c$			

Calibration of TSP

Calibration Point	**Manometer Reading H (inches of water)** (up)	(down)	(difference)	**Q_{std}** (m^3 / min.) **X-axis**	**Continuous Flow Recorder, W** (CFM)	**IC** $(W(P_a/1013.3 \times 298/T_a)^{1/2}/35.31)$ **Y-axis**
1	1.6	1.6	3.2	0.8922	28	27.7228
2	2.5	2.5	5.0	1.1109	32	31.6832
3	4.0	4.0	8.0	1.4004	42	41.5841
4	5.1	5.1	10.2	1.5790	50	49.5049
5	6.4	6.4	12.8	1.7667	58	57.4257

By Linear Regression of Y on X

Slope, m	=	34.5756	Intercept, b	=	-5.0881
Correlation Coefficient*	=	0.9903			
Calibration Accepted	=	Yes/~~No~~**			

* if Correlation Coefficient < 0.990, check and recalibration again.

** Delete as appropriate.

Remarks : As per client's provided information, the equipment reference no. of the calibrated High Volume Sampler has been re-assigned from EL449 to HVS002 with respect to the update in quality management system.

Calibrated by	:	Jackey MA	**Checked by**	:	Pualine Wong
Date	:	27-Sep-17	**Date**	:	27-Sep-17

Calibration Data for High Volume Sampler (TSP Sampler)

Location	:	CMA3a	**Calibration Date**	:	28-Sep-17
Equipment no.	:	HVS012	**Calibration Due Date**	:	28-Nov-17

CALIBRATION OF CONTINUOUS FLOW RECORDER

Ambient Condition					
Temperature, T_a	303	Kelvin	**Pressure, P_a**	1009	mmHg

Orifice Transfer Standard Information					
Equipment No.	**Ori001**	**Slope, m_c**	2.02533	**Intercept, bc**	-0.03593
Last Calibration Date	20-Mar-17	$(H \times P_a / 1013.3 \times 298 / T_a)^{1/2}$			
Next Calibration Date	20-Mar-18	$m_c \times Q_{std} + b_c$			

Calibration of TSP

Calibration Point	Manometer Reading H (inches of water) (up)	(down)	(difference)	Q_{std} (m^3 / min.) X-axis	Continuous Flow Recorder, W (CFM)	IC $(W(P_a/1013.3 \times 298/T_a)^{1/2}/35.31)$ Y-axis
1	1.3	1.3	2.6	0.8056	32	31.6675
2	2.1	2.1	4.2	1.0191	38	37.6051
3	3.3	3.3	6.6	1.2730	44	43.5428
4	4.3	4.3	8.6	1.4506	49	48.4908
5	4.9	4.9	9.8	1.5473	54	53.4389

By Linear Regression of Y on X

Slope, m = 27.9609 Intercept, b = 8.8606

Correlation Coefficient* = 0.9940

Calibration Accepted = Yes/~~No~~**

* if Correlation Coefficient < 0.990, check and recalibration again.

** Delete as appropriate.

Remarks : As per client's provided information, the equipment reference no. of the calibrated High Volume Sampler has been re-assigned from EL333 to HVS012 with respect to the update in quality management system.

Calibrated by	:	Jackey MA	**Checked by**	:	Pauline Wong
Date	:	28-Sep-17	**Date**	:	28-Sep-17

Calibration Data for High Volume Sampler (TSP Sampler)

Location	:	CMA4a	**Calibration Date**	:	28-Sep-17
Equipment no.	:	HVS004	**Calibration Due Date**	:	28-Nov-17

CALIBRATION OF CONTINUOUS FLOW RECORDER

Ambient Condition					
Temperature, T_a	303	Kelvin	**Pressure, P_a**	1009	mmHg

Orifice Transfer Standard Information					
Equipment No.	**Ori001**	**Slope, m_c**	2.02533	**Intercept, bc**	-0.03593
Last Calibration Date	20-Mar-17	$(H \times P_a / 1013.3 \times 298 / T_a)^{1/2}$			
Next Calibration Date	20-Mar-18	$m_c \times Q_{std} + b_c$			

Calibration of TSP

Calibration Point	Manometer Reading H (inches of water) (up)	(down)	(difference)	Q_{std} (m^3 / min.) X-axis	Continuous Flow Recorder, W (CFM)	IC $(W(P_a/1013.3 \times 298/T_a)^{1/2}/35.31)$ Y-axis
1	1.4	1.4	2.8	0.8354	24	23.7506
2	2.3	2.3	4.6	1.0657	32	31.6675
3	3.6	3.6	7.2	1.3288	42	41.5636
4	4.7	4.7	9.4	1.5158	48	47.5012
5	5.8	5.8	11.6	1.6819	52	51.4596

By Linear Regression of Y on X

Slope, m = 33.4431 Intercept, b = -3.8033

Correlation Coefficient* = 0.9977

Calibration Accepted = Yes/~~No~~**

* if Correlation Coefficient < 0.990, check and recalibration again.

** Delete as appropriate.

Remarks : As per client's provided information, the equipment reference no. of the calibrated High Volume Sampler has been re-assigned from EL390 to HVS004 with respect to the update in quality management system.

Calibrated by	:	Jackey MA	**Checked by**	:	Pauline Wong
Date	:	28-Sep-17	**Date**	:	28-Sep-17

Calibration Data for High Volume Sampler (TSP Sampler)

Location	:	CMA5b	**Calibration Date**	:	28-Sep-17
Equipment no.	:	HVS010	**Calibration Due Date**	:	28-Nov-17

CALIBRATION OF CONTINUOUS FLOW RECORDER

Ambient Condition					
Temperature, T_a	303	Kelvin	**Pressure, P_a**	1009	mmHg

Orifice Transfer Standard Information					
Equipment No.	**Ori001**	**Slope, m_c**	2.02533	**Intercept, bc**	-0.03593
Last Calibration Date	20-Mar-17	$(H \times P_a / 1013.3 \times 298 / T_a)^{1/2}$			
Next Calibration Date	20-Mar-18	$= m_c \times Q_{std} + b_c$			

Calibration of TSP

Calibration Point	**Manometer Reading H (inches of water)** (up)	(down)	(difference)	**Q_{std}** (m^3 / min.) **X-axis**	**Continuous Flow Recorder, W** (CFM)	**IC** $(W(P_a/1013.3 \times 298/T_a)^{1/2}/35.31)$ **Y-axis**
1	1.3	1.3	2.6	0.8056	38	37.6051
2	2.1	2.1	4.2	1.0191	43	42.5532
3	3.2	3.2	6.4	1.2539	50	49.4804
4	4.3	4.3	8.6	1.4506	55	54.4285
5	5.3	5.3	10.6	1.6086	60	59.3765

By Linear Regression of Y on X

Slope, m = 27.1605 Intercept, b = 15.3477

Correlation Coefficient* = 0.9990

Calibration Accepted = Yes/~~No~~**

* if Correlation Coefficient < 0.990, check and recalibration again.

** Delete as appropriate.

Remarks : As per client's provided information, the equipment reference no. of the calibrated High Volume Sampler has been re-assigned from EL222 to HVS010 with respect to the update in quality management system.

Calibrated by	:	Jackey MA	**Checked by**	:	Pauline Wong
Date	:	28-Sep-17	**Date**	:	28-Sep-17

Calibration Data for High Volume Sampler (TSP Sampler)

Location	:	CMA6a	**Calibration Date**	:	28-Sep-17
Equipment no.	:	HVS013	**Calibration Due Date**	:	28-Nov-17

CALIBRATION OF CONTINUOUS FLOW RECORDER

Ambient Condition					
Temperature, T_a	303	Kelvin	**Pressure, P_a**	1009	mmHg

Orifice Transfer Standard Information					
Equipment No.	**Ori001**	**Slope, m_c**	2.02533	**Intercept, bc**	-0.03593
Last Calibration Date	20-Mar-17	$(H \times P_a / 1013.3 \times 298 / T_a)^{1/2}$			
Next Calibration Date	20-May-17	$= m_c \times Q_{std} + b_c$			

Calibration of TSP

Calibration Point	Manometer Reading H (inches of water) (up)	(down)	(difference)	Q_{std} (m^3 / min.) X-axis	Continuous Flow Recorder, W (CFM)	IC $(W(P_a/1013.3 \times 298/T_a)^{1/2}/35.31)$ Y-axis
1	1.5	1.5	3.0	0.8640	28	27.7090
2	2.5	2.5	5.0	1.1103	36	35.6259
3	3.9	3.9	7.8	1.3824	44	43.5428
4	4.9	4.9	9.8	1.5473	51	50.4700
5	5.8	5.8	11.6	1.6819	57	56.4077

By Linear Regression of Y on X

Slope, m	=	34.4436	Intercept, b	=	-2.6180
Correlation Coefficient*	=	0.9965			
Calibration Accepted	=	Yes/~~No~~**			

* if Correlation Coefficient < 0.990, check and recalibration again.

** Delete as appropriate.

Remarks : As per client's provided information, the equipment reference no. of the calibrated High Volume Sampler has been re-assigned from EL551 to HVS013 with respect to the update in quality management system.

Calibrated by	:	Jackey MA	**Checked by**	:	Pauline Wong
Date	:	28-Sep-17	**Date**	:	28-Sep-17

Appendix 5.1

Monitoring Schedules for Reporting Month and Coming Reporting Month

Contract No. HK/2015/01
Wan Chai Development Phase II and Central-Wan Chai Bypass
Sampling, Field Measurement and Testing Works (Stage 3)

Environmental Monitoring Schedule
October 2017

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
24-Sep	25-Sep	26-Sep	27-Sep	28-Sep	29-Sep	30-Sep
					24hr TSP	1hr TSP
				Impact WQM Mid-ebb 5:41 Mid-flood 18:13		Impact WQM Mid-ebb 8:18 Mid-flood 16:24
1-Oct	2-Oct	3-Oct	4-Oct	5-Oct	6-Oct	7-Oct
		24hr TSP	1hr TSP		Noise (daytime) (M1a, M2b, M3a, M4b, M5b, M6)	24hr TSP
		Impact WQM Mid-ebb 10:30 Mid-flood 17:32		Impact WQM Mid-ebb 11:54 Mid-flood 18:18		Impact WQM Mid-ebb 13:17 Mid-flood 19:21
8-Oct	9-Oct	10-Oct	11-Oct	12-Oct	13-Oct	14-Oct
	1hr TSP		Noise (daytime) (M3a, M4b, M5b, M6)		24hr TSP Noise (daytime) (M1a, M2b)	1hr TSP
	Impact WQM Mid-flood 8:49 Mid-ebb 14:41		Impact WQM Mid-flood 10:57 Mid-ebb 21:54			Impact WQM Mid-ebb 7:50 Mid-flood 15:17
15-Oct	16-Oct	17-Oct	18-Oct	19-Oct	20-Oct	21-Oct
		Noise (daytime) (M3a, M4b, M5b, M6)		24hr TSP Noise (daytime) (M1a, M2b)	24hr TSP (CMA5b) 1hr TSP	
	Impact WQM Mid-ebb 9:53 Mid-flood 16:39		Impact WQM Mid-ebb 11:24 Mid-flood 17:39		Impact WQM Mid-ebb 12:41 Mid-flood 18:33	
22-Oct	23-Oct	24-Oct	25-Oct	26-Oct		
	Noise (daytime) (M1a)	Noise (daytime) (M2b, M3a, M4b, M5b, M6)	24hr TSP	1hr TSP		
	Impact WQM Mid-flood 8:38 Mid-ebb 14:25		Impact WQM Mid-ebb 2:28 Mid-flood 10:18			

Contract No. HK/2015/01
Wan Chai Development Phase II and Central-Wan Chai Bypass
Sampling, Field Measurement and Testing Works (Stage 3)
Tentative Environmental Monitoring Schedule
November 2017

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
					27-Oct Impact WQM Mid-ebb 4:21 Mid-flood 16:54	28-Oct
29-Oct	30-Oct Noise (daytime) Impact WQM Mid-ebb 8:05 Mid-flood 15:47	31-Oct 24hr TSP Noise (daytime)	1-Nov 1hr TSP Impact WQM Mid-ebb 9:50 Mid-flood 16:38	2-Nov	3-Nov Impact WQM Mid-ebb 11:27 Mid-flood 17:36	4-Nov
5-Nov	6-Nov 24hr TSP Noise (daytime) Impact WQM Mid-flood 7:53 Mid-ebb 13:39	7-Nov 1hr TSP Noise (daytime)	8-Nov Impact WQM Mid-ebb 2:49 Mid-flood 9:50	9-Nov	10-Nov Impact WQM Mid-ebb 4:49 Mid-flood 12:14	11-Nov 24hr TSP
12-Nov	13-Nov 1hr TSP Noise (daytime) Impact WQM Mid-ebb 8:28 Mid-flood 15:21	14-Nov Noise (daytime)	15-Nov Impact WQM Mid-ebb 10:16 Mid-flood 16:31	16-Nov	17-Nov 24hr TSP Impact WQM Mid-ebb 11:41 Mid-flood 17:28	18-Nov 1hr TSP
19-Nov	20-Nov Noise (daytime) Impact WQM Mid-ebb 0:58 Mid-flood 7:52	21-Nov Noise (daytime)	22-Nov Impact WQM Mid-ebb 1:37 Mid-flood 9:15	23-Nov 24hr TSP	24-Nov 1hr TSP Impact WQM Mid-ebb 2:47 Mid-flood 11:02	25-Nov

Appendix 5.2

Noise Monitoring Results and Graphical Presentations

Noise Monitoring Result

Day Time (0700 - 1900hrs on normal weekdays)

Location: M1a - Footbridge at EX-Wanchai Harbour Road Sports Centre

Date	Time	Weather	Measurement Noise Level			Baseline Level	Construction Noise Level	Limit Level
			Leq	L10	L90	Leq	Leq	Leq
			Unit: dB(A), (30-min)					
6/10/2017	10:25	Fine	74.7	76.7	71.6	72	71	75
13/10/2017	10:10	Fine	75.4	77.0	72.8	72	73	75
19/10/2017	13:15	Fine	76.5	78.2	74.2	72	74	75
23/10/2017	10:35	Fine	75.8	77.9	72.3	72	73	75

Location: M2b - Noon-day gun area

Date	Time	Weather	Measurement Noise Level			Baseline Level	Construction Noise Level	Limit Level
			Leq	L10	L90	Leq	Leq	Leq
			Unit: dB(A), (30-min)					
6/10/2017	11:10	Fine	66.5	68.0	64.7	68	67	75
13/10/2017	10:55	Fine	68.8	71.1	65.9	68	63	75
19/10/2017	14:10	Fine	67.5	68.1	65.0	68	68	75
24/10/2017	14:00	Fine	67.4	69.2	65.3	68	67	75

Location: M3a - Tung Lo Wan Fire Station

Date	Time	Weather	Measurement Noise Level			Baseline Level	Construction Noise Level	Limit Level
			Leq	L10	L90	Leq	Leq	Leq
			Unit: dB(A), (30-min)					
6/10/2017	13:00	Fine	68.3	70.6	63.9	69	68	75
11/10/2017	14:00	Fine	65.5	66.8	63.6	69	66	75
17/10/2017	09:10	Cloudy	65.0	66.4	62.6	69	65	75
24/10/2017	08:55	Fine	65.2	66.6	62.7	69	65	75

Location: M4b - Victoria Centre

Date	Time	Weather	Measurement Noise Level			Baseline Noise Level	Construction Noise Level	Limit Level
			Leq	L10	L90	Leq	Leq	Leq
			Unit: dB(A), (30min)					
6/10/2017	13:40	Fine	66.6	68.1	64.6	67	67	75
11/10/2017	14:40	Fine	67.7	69.4	65.3	67	57	75
17/10/2017	09:50	Cloudy	66.3	67.9	64.1	67	66	75
24/10/2017	09:35	Fine	65.5	66.8	63.7	67	66	75

Location: M5b - City Garden

Date	Time	Weather	Measurement Noise Level			Baseline Level	Construction Noise Level	Limit Level
			Leq	L10	L90	Leq	Leq	Leq
			Unit: dB(A), (30min)					
6/10/2017	14:15	Fine	72.6	73.5	71.3	68	71	75
11/10/2017	15:25	Fine	70.2	71.2	68.9	68	66	75
17/10/2017	10:30	Cloudy	71.6	72.8	70.0	68	69	75
24/10/2017	10:30	Fine	70.8	71.7	69.0	68	68	75

Location: M6 - HK Baptist Church Henrietta Secondary School

Date	Time	Weather	Measurement Noise Level			Baseline Level	Construction Noise Level	Limit Level
			Leq	L10	L90	Leq	Leq	Leq
			Unit: dB(A), (30-min)					
6/10/2017	15:00	Fine	66.5	67.7	64.3	71	67	70
11/10/2017	16:00	Fine	66.2	68.6	64.5	71	66	70
17/10/2017	11:10	Cloudy	68.0	69.2	66.5	71	68	70
24/10/2017	11:05	Fine	67.6	68.7	66.4	71	68	70

Graphic Presentation of Noise Monitoring Result

Day Time (0700 - 1900hrs on normal weekdays)







Graphic Presentation of Noise Monitoring Result

Day Time (0700 - 1900hrs on normal weekdays)







Appendix 5.3

Air Quality Monitoring Results and Graphical Presentations

Location: CMA1b - Harbour Grand Hotel Boundary Wall

Report on 24-hour TSP monitoring

Action Level (μ g/m3) - 176.7

Limit Level (μ g/m3) - 260

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, $\mu g/m^3$
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
29-Sep-17	8:00	Fine	22368	2.8362	2.9743	10634.36	10658.36	24.00	1.11	1.11	1.11	1599	86.4
3-Oct-17	8:00	Fine	22331	2.8527	2.9128	10661.36	10685.36	24.00	1.11	1.11	1.11	1597	37.6
7-Oct-17	8:00	Fine	21742	2.8556	2.9560	10688.36	10712.36	24.00	1.11	1.11	1.11	1598	62.8
13-Oct-17	8:00	Fine	22325	2.8714	2.9955	10715.36	10739.36	24.00	1.11	1.11	1.11	1601	77.5
19-Oct-17	8:00	Fine	22539	2.8459	2.9221	10742.36	10766.36	24.00	1.12	1.12	1.12	1608	47.4
25-Oct-17	8:00	Fine	22630	2.8768	3.0329	10769.36	10793.36	24.00	1.12	1.12	1.12	1613	96.7

Report on 1-hour TSP monitoring

Action Level (μ g/m3) - 320.1

Limit Level (μ g/m3) - 500

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, $\mu g/m^3$
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
30-Sep-17	8:02	Rainy	22366	2.8669	2.8717	10658.36	10659.36	1.00	1.11	1.11	1.11	67	72.1
30-Sep-17	10:00	Rainy	22343	2.8542	2.8596	10659.36	10660.36	1.00	1.11	1.11	1.11	67	81.2
30-Sep-17	13:00	Rainy	22347	2.8607	2.8636	10660.36	10661.36	1.00	1.11	1.11	1.11	67	43.6
4-Oct-17	10:05	Fine	22350	2.8347	2.8446	10685.36	10686.36	1.00	1.11	1.11	1.11	67	148.6
4-Oct-17	13:00	Fine	22487	2.8259	2.8306	10686.36	10687.36	1.00	1.11	1.11	1.11	67	70.6
4-Oct-17	15:07	Fine	22500	2.8446	2.8485	10687.36	10688.36	1.00	1.11	1.11	1.11	67	58.6
9-Oct-17	9:35	Fine	22432	2.8473	2.8586	10712.36	10713.36	1.00	1.19	1.19	1.19	71	158.2
9-Oct-17	10:42	Fine	22438	2.8499	2.8613	10713.36	10714.36	1.00	1.19	1.19	1.19	71	159.6
9-Oct-17	14:08	Fine	22484	2.8565	2.8790	10714.36	10715.36	1.00	1.19	1.19	1.19	71	314.9
14-Oct-17	8:12	Fine	22566	2.8404	2.8534	10739.36	10740.36	1.00	1.11	1.11	1.11	67	194.8
14-Oct-17	11:00	Fine	22551	2.8337	2.8425	10740.36	10741.36	1.00	1.11	1.11	1.11	67	131.9
14-Oct-17	13:00	Fine	22561	2.8542	2.8748	10741.36	10742.36	1.00	1.11	1.11	1.11	67	308.7
20-Oct-17	8:02	Fine	22519	2.8261	2.8291	10766.36	10767.36	1.00	1.12	1.12	1.12	67	44.7
20-Oct-17	11:00	Fine	22662	2.8393	2.8416	10767.36	10768.36	1.00	1.12	1.12	1.12	67	34.3
20-Oct-17	15:30	Fine	22648	2.8338	2.8436	10768.36	10769.36	1.00	1.12	1.12	1.12	67	146.1
26-Oct-17	8:02	Fine	22620	2.8619	2.8693	10793.36	10794.36	1.00	1.12	1.12	1.12	67	110.1
26-Oct-17	10:35	Fine	22611	2.8618	2.8710	10794.36	10795.36	1.00	1.12	1.12	1.12	67	136.9
26-Oct-17	13:00	Fine	22771	2.8193	2.8745	10795.36	10796.36	1.00	1.12	1.12	1.12	67	821.6

Location: CMA2a - Causeway Bay Community Centre

Report on 24-hour TSP monitoring
Action Level (μg/m3) - 169.5
Limit Level (μg/m3) - 260

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, μg/m^3
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
29-Sep-17	8:00	Fine	22126	2.8900	2.9720	20206.24	20230.24	24.00	1.31	1.31	1.31	1882	43.6
3-Oct-17	8:00	Fine	22332	2.8549	2.9169	20233.24	20257.24	24.00	1.19	1.20	1.20	1721	36.0
7-Oct-17	8:00	Fine	21744	2.8596	2.9273	20260.24	20284.24	24.00	1.20	1.20	1.20	1722	39.3
13-Oct-17	8:00	Fine	22481	2.8407	2.9811	20287.24	20311.24	24.00	1.20	1.20	1.20	1725	81.4
19-Oct-17	8:00	Fine	22540	2.8605	2.9372	20314.24	20338.24	24.00	1.20	1.20	1.20	1732	44.3
25-Oct-17	8:00	Fine	22631	2.8424	2.9920	20341.24	20365.24	24.00	1.32	1.32	1.32	1898	78.8

Report on 1-hour TSP monitoring
Action Level (μg/m3) - 323.4
Limit Level (μg/m3) - 500

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, μg/m^3
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
30-Sep-17	8:05	Rainy	22367	2.8656	2.8691	20230.24	20231.24	1.00	1.20	1.20	1.20	72	48.8
30-Sep-17	9:45	Rainy	22342	2.8478	2.8522	20231.24	20232.24	1.00	1.20	1.20	1.20	72	61.4
30-Sep-17	13:00	Rainy	22346	2.8256	2.8293	20232.24	20233.24	1.00	1.20	1.20	1.20	72	51.6
4-Oct-17	10:13	Fine	22336	2.8488	2.8538	20257.24	20258.24	1.00	1.20	1.20	1.20	72	69.7
4-Oct-17	13:00	Fine	22488	2.8427	2.8467	20258.24	20259.24	1.00	1.20	1.20	1.20	72	55.7
4-Oct-17	15:02	Fine	22501	2.8596	2.8640	20259.24	20260.24	1.00	1.20	1.20	1.20	72	61.3
9-Oct-17	9:39	Fine	22441	2.8393	2.8491	20284.24	20285.24	1.00	1.19	1.19	1.19	72	136.7
9-Oct-17	10:42	Fine	22328	2.8663	2.8734	20285.24	20286.24	1.00	1.19	1.19	1.19	72	99.1
9-Oct-17	14:00	Fine	22483	2.8477	2.8548	20286.24	20287.24	1.00	1.19	1.19	1.19	72	99.1
14-Oct-17	8:02	Fine	22567	2.8240	2.8327	20311.24	20312.24	1.00	1.20	1.20	1.20	72	121.0
14-Oct-17	11:00	Fine	22552	2.8349	2.8407	20312.24	20313.24	1.00	1.20	1.20	1.20	72	80.7
14-Oct-17	13:00	Fine	22562	2.8474	2.8562	20313.24	20314.24	1.00	1.20	1.20	1.20	72	122.4
20-Oct-17	8:05	Fine	22520	2.8259	2.8303	20338.24	20339.24	1.00	1.20	1.20	1.20	72	60.9
20-Oct-17	11:00	Fine	22663	2.8400	2.8421	20339.24	20340.24	1.00	1.20	1.20	1.20	72	29.1
20-Oct-17	15:35	Fine	22649	2.8407	2.8491	20340.24	20341.24	1.00	1.20	1.20	1.20	72	116.3
26-Oct-17	8:05	Fine	22621	2.8401	2.8488	20365.24	20366.24	1.00	1.32	1.32	1.32	79	110.1
26-Oct-17	10:40	Fine	22612	2.8515	2.8632	20366.24	20367.24	1.00	1.32	1.32	1.32	79	148.0
26-Oct-17	13:00	Fine	22769	2.7609	2.7645	20367.24	20368.24	1.00	1.32	1.32	1.32	79	45.5

Location: CMA3a - CWB PRE Site Office Area

Report on 24-hour TSP monitoring
Action Level (μg/m3) - 171
Limit Level (μg/m3) - 260

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, μg/m^3
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
29-Sep-17	8:00	Fine	22376	2.8739	2.9304	7699.87	7723.87	24.00	1.12	1.12	1.12	1608	35.1
3-Oct-17	8:00	Fine	22333	2.8604	2.8737	7726.88	7750.88	24.00	1.11	1.12	1.12	1606	8.3
7-Oct-17	8:00	Fine	22491	2.8232	2.8700	7753.89	7777.89	24.00	0.98	0.98	0.98	1411	33.2
13-Oct-17	8:00	Fine	22326	2.8419	2.9610	7780.89	7804.89	24.00	1.12	1.12	1.12	1611	73.9
19-Oct-17	8:00	Fine	22541	2.8441	2.9207	7807.89	7831.89	24.00	1.12	1.13	1.13	1622	47.2
25-Oct-17	8:00	Fine	22629	2.8663	3.0154	7834.90	7858.90	24.00	1.13	1.13	1.13	1629	91.5

Report on 1-hour TSP monitoring
Action Level (μg/m3) - 311.3
Limit Level (μg/m3) - 500

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, μg/m^3
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
30-Sep-17	8:30	Rainy	22364	2.8636	2.8666	7723.87	7724.87	1.00	1.12	1.12	1.12	67	44.8
30-Sep-17	9:32	Rainy	22341	2.8579	2.8606	7724.87	7725.87	1.00	1.12	1.12	1.12	67	40.3
30-Sep-17	13:00	Rainy	22345	2.8546	2.8584	7725.87	7726.87	1.00	1.12	1.12	1.12	67	56.8
4-Oct-17	9:20	Fine	21760	2.8559	2.8585	7750.88	7751.88	1.00	0.98	0.98	0.98	59	44.2
4-Oct-17	13:00	Fine	21757	2.8455	2.8473	7751.88	7752.88	1.00	0.98	0.98	0.98	59	30.6
4-Oct-17	14:30	Fine	21741	2.8815	2.8856	7752.88	7753.88	1.00	0.98	0.98	0.98	59	69.7
9-Oct-17	9:05	Fine	22433	2.8446	2.8492	7777.89	7778.89	1.00	1.05	1.05	1.05	63	73.3
9-Oct-17	10:28	Fine	22439	2.8665	2.8727	7778.89	7779.89	1.00	1.05	1.05	1.05	63	98.7
9-Oct-17	13:37	Fine	22327	2.8544	2.8638	7779.89	7780.89	1.00	1.11	1.11	1.11	67	140.5
14-Oct-17	8:45	Fine	22559	2.8514	2.8559	7804.89	7805.89	1.00	1.12	1.12	1.12	67	67.0
14-Oct-17	10:55	Fine	22555	2.8255	2.8306	7805.89	7806.89	1.00	1.12	1.12	1.12	67	75.9
14-Oct-17	13:00	Fine	22563	2.8329	2.8395	7806.89	7807.89	1.00	1.12	1.12	1.12	67	98.2
20-Oct-17	8:30	Fine	22518	2.8295	2.8321	7831.89	7832.89	1.00	1.13	1.13	1.13	68	38.4
20-Oct-17	10:45	Fine	22664	2.8539	2.8569	7832.89	7833.89	1.00	1.13	1.13	1.13	68	44.4
20-Oct-17	15:00	Fine	22651	2.8464	2.8575	7833.89	7834.89	1.00	1.13	1.13	1.13	68	164.1
26-Oct-17	8:30	Fine	22604	2.8340	2.8424	7858.90	7859.90	1.00	1.13	1.13	1.13	68	123.9
26-Oct-17	10:25	Fine	22613	2.8617	2.8694	7859.90	7860.90	1.00	1.13	1.13	1.13	68	113.6
26-Oct-17	13:00	Fine	22783	2.7877	2.7947	7860.90	7861.90	1.00	1.13	1.13	1.13	68	103.2

Location: CMA4a - SPCA

Report on 24-hour TSP monitoring
Action Level (μg/m3) - 171.2
Limit Level (μg/m3) - 260

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, $\mu g/m^3$
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
29-Sep-17	8:00	Fine	22383	2.8385	2.8870	24511.73	24535.73	24.00	1.20	1.20	1.20	1726	28.1
3-Oct-17	8:00	Fine	22334	2.8516	2.8832	24538.73	24562.73	24.00	1.20	1.20	1.20	1724	18.3
7-Oct-17	8:00	Fine	22499	2.8481	2.9473	24565.73	24589.73	24.00	1.20	1.20	1.20	1725	57.5
13-Oct-17	8:00	Fine	22482	2.8343	2.9325	24592.73	24616.73	24.00	1.20	1.20	1.20	1728	56.8
19-Oct-17	8:00	Fine	22542	2.8371	2.9065	24619.73	24643.73	24.00	1.20	1.21	1.21	1736	40.0
25-Oct-17	8:00	Fine	22628	2.8481	2.9875	24646.73	24670.73	24.00	1.21	1.21	1.21	1741	80.1

Report on 1-hour TSP monitoring
Action Level (μg/m3) - 312.5
Limit Level (μg/m3) - 500

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, $\mu g/m^3$
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
30-Sep-17	8:30	Rainy	22365	2.8593	2.8610	24535.73	24536.73	1.00	1.20	1.20	1.20	72	23.7
30-Sep-17	9:35	Rainy	22340	2.8556	2.8576	24536.73	24537.73	1.00	1.20	1.20	1.20	72	27.8
30-Sep-17	13:00	Rainy	22344	2.8382	2.8420	24537.73	24538.73	1.00	1.20	1.20	1.20	72	52.9
4-Oct-17	9:21	Fine	22352	2.8545	2.8587	24562.73	24563.73	1.00	1.20	1.20	1.20	72	58.4
4-Oct-17	13:00	Fine	22338	2.8491	2.8535	24563.73	24564.73	1.00	1.26	1.26	1.26	75	58.4
4-Oct-17	14:33	Fine	21108	2.8912	2.8963	24564.73	24565.73	1.00	1.20	1.20	1.20	72	70.9
9-Oct-17	9:11	Fine	22442	2.8355	2.8398	24589.73	24590.73	1.00	1.20	1.20	1.20	72	59.9
9-Oct-17	10:28	Fine	22329	2.8325	2.8391	24590.73	24591.73	1.00	1.20	1.20	1.20	72	91.9
9-Oct-17	13:25	Fine	22318	2.8272	2.8320	24591.73	24592.73	1.00	1.20	1.20	1.20	72	66.9
14-Oct-17	8:45	Fine	22560	2.8344	2.8382	24616.73	24617.73	1.00	1.20	1.20	1.20	72	52.7
14-Oct-17	10:40	Fine	22554	2.8160	2.8193	24617.73	24618.73	1.00	1.20	1.20	1.20	72	45.8
14-Oct-17	13:00	Fine	22547	2.8461	2.8517	24618.73	24619.73	1.00	1.20	1.20	1.20	72	77.7
20-Oct-17	8:30	Fine	22517	2.8358	2.8383	24643.73	24644.73	1.00	1.32	1.32	1.32	79	31.5
20-Oct-17	10:47	Fine	22668	2.8205	2.8251	24644.73	24645.73	1.00	1.32	1.32	1.32	79	58.0
20-Oct-17	14:45	Fine	22652	2.8594	2.8727	24645.73	24646.73	1.00	1.32	1.32	1.32	79	167.8
26-Oct-17	8:30	Fine	22603	2.8394	2.8431	24670.73	24671.73	1.00	1.21	1.21	1.21	72	51.0
26-Oct-17	10:32	Fine	22614	2.8672	2.8721	24671.73	24672.73	1.00	1.24	1.24	1.24	74	66.0
26-Oct-17	13:00	Fine	22770	2.7837	2.7857	24672.73	24673.73	1.00	1.21	1.21	1.21	72	27.6

Location: CMA5b - Pedestrian Plaza

Report on 24-hour TSP monitoring
Action Level (μg/m3) - 181
Limit Level (μg/m3) - 260

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, $\mu g/m^3$
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
29-Sep-17	8:00	Fine	22125	2.8659	3.0064	9071.93	9095.93	24.00	0.91	0.91	0.91	1312	107.1
3-Oct-17	8:00	Fine	22330	2.8531	2.9833	9098.93	9122.93	24.00	0.91	0.91	0.91	1310	99.4
7-Oct-17	8:00	Fine	22498	2.8602	3.0446	9125.93	9149.93	24.00	0.91	0.91	0.91	1311	140.6
13-Oct-17	8:00	Fine	22465	2.8588	3.0811	9152.93	9176.93	24.00	0.91	0.91	0.91	1315	169.1
20-Oct-17	16:15	Fine	22644	2.8534	2.9593	9206.54	9230.54	24.00	0.78	0.78	0.78	1123	94.3
25-Oct-17	8:00	Fine	22546	2.8559	3.0173	9230.54	9254.54	24.00	0.78	0.78	0.78	1128	143.0

Remarks: Due to interruption of electricity, the 24hr TSP was rescheduled from 19 October 2017 to 20 October 2017.

Report on 1-hour TSP monitoring
Action Level (μg/m3) - 332
Limit Level (μg/m3) - 500

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, $\mu g/m^3$
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
30-Sep-17	8:40	Rainy	22363	2.8495	2.8542	9095.93	9096.93	1.00	0.84	0.84	0.84	50	93.3
30-Sep-17	10:15	Rainy	22322	2.8625	2.8665	9096.93	9097.93	1.00	0.91	0.91	0.91	55	73.3
30-Sep-17	13:00	Rainy	22348	2.8573	2.8625	9097.93	9098.93	1.00	0.84	0.84	0.84	50	103.3
4-Oct-17	9:03	Fine	22353	2.8568	2.8660	9122.93	9123.93	1.00	0.91	0.91	0.91	55	168.3
4-Oct-17	10:46	Fine	22337	2.8445	2.8487	9123.93	9124.93	1.00	0.77	0.77	0.77	46	90.9
4-Oct-17	13:00	Fine	22486	2.8302	2.8359	9124.93	9125.93	1.00	0.91	0.91	0.91	55	104.3
9-Oct-17	8:53	Fine	22434	2.8589	2.8704	9149.93	9150.93	1.00	0.91	0.91	0.91	55	210.9
9-Oct-17	9:54	Fine	22440	2.8635	2.8772	9150.93	9151.93	1.00	0.91	0.91	0.91	55	251.3
9-Oct-17	13:04	Fine	22437	2.8501	2.8597	9151.93	9152.93	1.00	0.91	0.91	0.91	55	176.1
14-Oct-17	9:02	Fine	22558	2.8336	2.8443	9176.93	9177.93	1.00	0.84	0.84	0.84	51	211.4
14-Oct-17	10:15	Fine	22553	2.8451	2.8532	9177.93	9178.93	1.00	0.84	0.84	0.84	51	160.0
14-Oct-17	13:00	Fine	22550	2.8444	2.8612	9178.93	9179.93	1.00	0.91	0.91	0.91	55	306.3
20-Oct-17	8:45	Fine	22516	2.8437	2.8484	9203.54	9204.54	1.00	0.78	0.78	0.78	47	100.4
20-Oct-17	10:35	Fine	22665	2.8455	2.8513	9204.54	9205.54	1.00	0.78	0.78	0.78	47	123.9
20-Oct-17	13:00	Fine	22661	2.8526	2.8567	9205.54	9206.54	1.00	0.78	0.78	0.78	47	87.6
26-Oct-17	8:50	Fine	22619	2.8494	2.8587	9254.54	9255.54	1.00	0.78	0.78	0.78	47	198.0
26-Oct-17	10:10	Fine	22615	2.8294	2.8480	9255.54	9256.54	1.00	1.07	1.07	1.07	64	290.7
26-Oct-17	17:00	Fine	22772	2.8011	2.8301	9256.54	9257.54	1.00	1.00	1.00	1.00	60	485.5

Location: CMA6a - WD2 PRE Office

Report on 24-hour TSP monitoring

Action Level - 187.3 µg/m3

Limit Level - 260 µg/m3

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, $\mu g/m^3$
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
29-Sep-17	8:00	Fine	22123	2.8529	2.9091	2819.27	2843.27	24.00	1.24	1.24	1.24	1785	31.5
3-Oct-17	8:00	Fine	22063	2.8354	2.8835	2847.27	2871.27	24.00	1.15	1.16	1.16	1664	28.9
7-Oct-17	8:00	Fine	22490	2.8417	2.8926	2874.27	2898.27	24.00	1.13	1.13	1.13	1625	31.3
13-Oct-17	8:00	Fine	22468	2.8478	2.9625	2903.15	2927.15	24.00	1.13	1.13	1.13	1628	70.5
19-Oct-17	8:00	Fine	22543	2.8517	2.9184	2930.15	2954.15	24.00	1.14	1.14	1.14	1636	40.8
25-Oct-17	8:00	Fine	22646	2.8541	2.9500	2957.15	2981.15	24.00	1.14	1.14	1.14	1641	58.4

Report on 1-hour TSP monitoring

Action Level - 300.1 μ g/m^3

Limit Level - 500 μ g/m3

Date	Sampling Time	Weather Condition	Filter paper no.	Filter Weight, g		Elapse Time, hr		Sampling Time, hr	Flow Rate, m^3/min			Total Volume, m^3	TSP Level, $\mu g/m^3$
				Initial	Final	Initial	Final		Initial, Q_{si}	Final, Q_{sf}	Average		
30-Sep-17	9:05	Rainy	22339	2.8469	2.8491	2843.27	2844.27	1.00	1.13	1.13	1.13	68	32.5
30-Sep-17	10:30	Rainy	22321	2.8615	2.8627	2845.27	2846.27	1.00	1.13	1.13	1.13	68	17.7
30-Sep-17	13:00	Rainy	22335	2.8494	2.8540	2846.27	2847.27	1.00	1.18	1.13	1.16	69	66.3
4-Oct-17	8:55	Fine	21761	2.8410	2.8422	2871.27	2872.27	1.00	1.13	1.13	1.13	68	17.7
4-Oct-17	10:50	Fine	21759	2.8762	2.8772	2872.27	2873.27	1.00	1.13	1.13	1.13	68	14.8
4-Oct-17	13:00	Fine	21756	2.8372	2.8425	2873.27	2874.27	1.00	1.13	1.13	1.13	68	78.2
9-Oct-17	8:30	Fine	22444	2.8492	2.8526	2898.27	2899.27	1.00	1.13	1.13	1.13	68	50.3
9-Oct-17	13:00	Fine	22475	2.8588	2.8645	2901.15	2902.15	1.00	1.13	1.13	1.13	68	84.3
9-Oct-17	16:10	Fine	22467	2.8675	2.8728	2902.15	2903.15	1.00	1.13	1.13	1.13	68	78.3
14-Oct-17	9:05	Fine	22564	2.8522	2.8594	2927.15	2928.15	1.00	1.13	1.13	1.13	68	106.1
14-Oct-17	10:07	Fine	22557	2.8239	2.8286	2928.15	2929.15	1.00	1.13	1.13	1.13	68	69.2
14-Oct-17	13:00	Fine	22548	2.7995	2.8052	2929.15	2930.15	1.00	1.13	1.13	1.13	68	84.0
20-Oct-17	8:45	Fine	22671	2.8281	2.8306	2954.15	2955.15	1.00	1.14	1.14	1.14	68	36.7
20-Oct-17	10:30	Fine	22666	2.8463	2.8497	2955.15	2956.15	1.00	1.14	1.14	1.14	68	49.9
20-Oct-17	13:00	Fine	22660	2.8487	2.8525	2956.15	2957.15	1.00	1.14	1.14	1.14	68	55.7
26-Oct-17	8:50	Fine	22618	2.8464	2.8546	2981.15	2982.15	1.00	1.14	1.14	1.14	68	120.0
26-Oct-17	10:05	Fine	22607	2.8590	2.8663	2982.15	2983.15	1.00	1.14	1.14	1.14	68	106.8
26-Oct-17	13:00	Fine	22784	2.8058	2.8127	2983.15	2984.15	1.00	1.14	1.14	1.14	68	101.0

Graphic Presentation of 1 hour TSP Result







Graphic Presentation of 1 hour TSP Result







Graphic Presentation of 24 hour TSP Result







Graphic Presentation of 24 hour TSP Result







Appendix 5.4

Water Quality Monitoring Results and Graphical Presentations

Water Monitoring Result at C7 - Windsor House
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	15:10	Fine	Middle	-	31.60	31.60	31.75	7.97	7.97	7.97	28.00	28.00	28.00	67.8	68.7	68.4	4.27	4.32	4.30	4.05	4.03	4.04	6	7.00
	15:12		Middle	-	31.90	31.90		7.96	7.96		28.00	28.00		68.5	68.5		4.31	4.30		4.04	4.05		8	
30/9/2017	15:05	Cloudy	Middle	-	30.10	30.10	30.10	7.71	7.71	7.73	28.48	28.48	28.48	91.8	91.2	91.6	5.92	5.89	5.91	3.57	3.58	3.59	<2	<2
	15:07		Middle	-	30.10	30.10		7.74	7.74		28.48	28.48		91.1	92.1		5.88	5.94		3.62	3.60		<2	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C1 - HKCEC Extension
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	18:30	Fine	Middle	3.0	29.90	29.90	29.90	8.11	8.11	8.11	28.78	28.78	28.79	62.7	63.9	63.0	4.05	4.13	4.07	3.28	3.27	3.31	6	6.00
	18:32		Middle	3.0	29.90	29.90		8.11	8.11		28.79	28.79		62.6	62.8		4.04	4.05		3.34	3.35		6	
30/9/2017	17:25	Cloudy	Middle	3.0	29.30	29.30	29.30	7.94	7.94	7.95	29.55	29.53	29.55	95.1	95.2	94.9	6.18	6.19	6.17	5.57	5.52	5.55	8	7.50
	17:27		Middle	3.0	29.30	29.30		7.95	7.95		29.55	29.55		94.8	94.3		6.16	6.13		5.54	5.57		7	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P1 - HKCEC Phase I
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	18:10	Fine	Middle	3.0	30.60	30.60	30.65	8.11	8.11	8.11	28.78	28.78	28.79	67.1	67.4	67.4	4.28	4.30	4.30	4.76	4.82	4.85	9	8.50
	18:12		Middle	3.0	30.70	30.70		8.11	8.11		28.79	28.79		67.4	67.5		4.30	4.31		4.89	4.93		8	
30/9/2017	17:05	Cloudy	Middle	3.0	29.70	29.70	29.80	7.78	7.78	7.81	29.33	29.33	29.34	96.2	96.7	95.7	6.21	6.24	6.17	2.08	2.08	2.08	3	4.00
	17:07		Middle	3.0	29.90	29.90		7.83	7.83		29.34	29.34		95.2	94.6		6.14	6.10		2.08	2.09		5	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P3 - APA
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	18:15	Fine	Middle	3.0	30.00	30.00	30.00	8.11	8.11	8.11	28.85	28.85	28.62	64.8	64.7	64.9	4.18	4.17	4.19	5.58	5.67	5.68	8	8.50
	18:17		Middle	3.0	30.00	30.00		8.11	8.11		28.39	28.39		64.7	65.4		4.17	4.22		5.70	5.76		9	
30/9/2017	17:10	Cloudy	Middle	3.0	29.50	29.50	29.55	7.85	7.85	7.86	29.35	29.35	29.35	95.3	95.9	95.6	6.17	6.22	6.19	3.97	3.99	3.95	6	5.50
	17:12		Middle	3.0	29.60	29.60		7.87	7.87		29.35	29.35		95.5	95.6		6.19	6.19		3.92	3.92		5	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P4 - SOC
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	18:20	Fine	Middle	3.0	30.00	30.00	30.00	8.10	8.10	8.10	28.75	28.75	28.75	65.2	65.3	65.9	4.22	4.22	4.26	3.56	3.58	3.60	6	6.50
	18:22		Middle	3.0	30.00	30.00		8.10	8.10		28.75	28.75		66.7	66.5		4.30	4.29		3.63	3.62		7	
30/9/2017	17:15	Cloudy	Middle	3.0	29.30	29.30	29.30	7.89	7.89	7.90	29.46	29.46	29.47	99.4	99.7	99.4	6.45	6.48	6.46	6.06	6.03	6.03	6	6.00
	17:17		Middle	3.0	29.30	29.30		7.91	7.91		29.47	29.47		99.3	99.3		6.45	6.45		6.01	6.00		6	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P5 - WCT / RT / IT
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	18:25	Fine	Middle	3.0	29.80	29.80	29.85	8.10	8.10	8.11	28.66	28.66	28.66	63.4	63.5	62.9	4.10	4.10	4.06	4.97	4.90	4.89	8	7.50
	18;27		Middle	3.0	29.90	29.90		8.11	8.11		28.65	28.65		62.0	62.5		4.01	4.03		4.85	4.84		7	
30/9/2017	17:20	Cloudy	Middle	3.0	29.30	29.30	29.30	7.92	7.92	7.93	29.50	29.50	29.50	96.6	96.7	96.8	6.28	6.29	6.31	5.14	5.08	5.07	7	6.50
	17:22		Middle	3.0	29.30	29.30		7.93	7.93		29.50	29.50		97.1	96.8		6.31	6.36		5.00	5.04		6	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at RW21-P789 - GEC/CRB/SHK
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	15:00	Fine	Middle	3.5	31.20	31.20	31.45	8.04	8.04	8.04	28.29	28.29	28.30	67.3	67.6	67.6	4.23	4.25	4.25	3.75	3.75	3.76	6	7.00
	15:02		Middle	3.5	31.70	31.70		8.04	8.04		28.31	28.31		67.8	67.8		4.26	4.26		3.77	3.76		8	
30/9/2017	14:30	Cloudy	Middle	3.5	29.80	29.80	29.85	7.56	7.59	7.63	29.20	29.20	29.20	86.4	88.2	87.1	5.58	5.69	5.63	2.60	2.59	2.64	<2	<2
	14:32		Middle	3.5	29.90	29.90		7.68	7.68		29.20	29.20		86.9	87.0		5.61	5.62		2.70	2.65		<2	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at WSD19 - Sheung Wan
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	17:05	Fine	Middle	4.0	30.30	30.30	30.60	8.14	8.14	8.13	28.88	28.88	28.87	69.2	69.4	69.1	4.41	4.42	4.40	9.89	9.97	9.91	10	9.50
	17:07		Middle	4.0	30.90	30.90		8.11	8.11		28.86	28.86		68.5	69.4		4.36	4.41		9.91	9.87		9	
30/9/2017	15:35	Cloudy	Middle	4.0	29.80	29.80	29.70	7.69	7.69	7.72	29.30	29.00	29.23	99.2	99.2	98.6	6.40	6.40	6.36	2.94	3.02	3.02	4	5.00
	15:37		Middle	4.0	29.60	29.60		7.75	7.75		29.30	29.30		98.1	97.8		6.33	6.31		3.05	3.05		6	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C7 - Windsor House
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	3:32	Fine	Middle	-	28.80	28.80	28.80	7.86	7.86	7.87	28.70	28.70	28.70	82.6	84.1	83.6	5.22	5.28	5.25	1.62	1.64	1.63	3	2.50
	3:33		Middle	-	28.80	28.80		7.88	7.88		28.70	28.70		82.8	84.8		5.19	5.32		1.67	1.60		2	
30/9/2017	9:30	Cloudy	Middle	-	29.00	29.00	28.90	7.06	7.06	7.03	29.22	29.22	29.22	82.5	83.0	83.3	5.41	5.40	5.45	4.42	4.51	4.54	4	5.00
	9:32		Middle	-	28.80	28.80		7.00	7.00		29.22	29.22		83.6	83.9		5.49	5.51		4.55	4.67		6	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C1 - HKCEC
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	5:05	Fine	Middle	3.0	28.00	28.00	27.95	8.08	8.08	8.08	28.64	28.64	28.64	85.7	83.3	84.0	5.47	5.31	5.36	2.30	2.00	2.06	3	3.00
	5:06		Middle	3.0	27.90	27.90		8.08	8.08		28.64	28.64		82.2	84.8		5.24	5.40		1.98	1.97		<2	
30/9/2017	11:00	Cloudy	Middle	2.5	29.00	29.00	28.95	7.83	7.83	7.83	28.96	28.96	28.97	82.0	82.6	82.6	5.38	5.42	5.42	1.73	1.74	1.74	6	5.00
	11:52		Middle	2.5	28.90	28.90		7.83	7.83		28.97	28.97		82.7	82.9		5.43	5.45		1.75	1.75		4	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P1 - HKCEC Phase I
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	4:35	Fine	Middle	3.0	28.40	28.40	28.50	8.08	8.08	8.09	28.65	28.65	28.65	86.6	88.0	86.9	5.45	5.51	5.47	1.29	1.15	1.17	3	2.50
	4:36		Middle	3.0	28.60	28.60		8.09	8.09		28.65	28.65		86.8	86.2		5.47	5.43		1.12	1.13		2	
30/9/2017	11:30	Cloudy	Middle	2.5	28.40	28.40	28.35	7.68	7.68	7.71	29.04	29.04	29.05	83.8	84.2	84.0	5.55	5.58	5.57	1.92	1.92	1.92	5	4.00
	11:32		Middle	2.5	28.30	28.30		7.74	7.74		29.05	29.05		84.1	84.0		5.57	5.56		1.92	1.93		3	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P3 - APA
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	4:41	Fine	Middle	3.0	27.90	27.90	27.90	8.09	8.09	8.09	28.59	28.59	28.59	81.4	81.2	81.7	5.18	5.17	5.20	1.35	1.37	1.34	<2	<2
	4:42		Middle	3.0	27.90	27.90		8.09	8.09		28.59	28.59		82.8	81.3		5.27	5.18		1.32	1.32		<2	
30/9/2017	11:35	Cloudy	Middle	2.5	28.30	28.30	28.40	7.75	7.75	7.77	28.99	28.99	29.02	85.4	85.6	85.0	5.63	5.64	5.64	1.99	1.92	1.97	6	5.00
	11:37		Middle	2.5	28.50	28.50		7.78	7.78		29.04	29.04		83.2	85.9		5.62	5.66		2.00	1.98		4	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P4 - SOC
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	4:48	Fine	Middle	3.0	27.90	27.90	27.90	8.06	8.06	8.08	28.63	28.63	28.63	86.3	86.6	86.8	5.50	5.51	5.53	2.25	2.26	2.31	3	3.00
	4:49		Middle	3.0	27.90	27.90		8.09	8.09		28.63	28.63		87.6	86.5		5.58	5.51		2.32	2.39		<2	
30/9/2017	11:40	Cloudy	Middle	2.5	28.40	28.40	28.55	7.78	7.78	7.79	28.19	28.19	28.20	85.6	85.6	85.4	5.63	5.63	5.62	2.08	2.08	2.08	5	4.00
	11:42		Middle	2.5	28.70	28.70		7.80	7.80		28.20	28.20		85.2	85.2		5.61	5.61		2.08	2.09		3	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P5 - WCT / RT / IT
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	4:53	Fine	Middle	3.0	28.40	28.40	28.40	8.09	8.09	8.09	28.64	28.64	28.64	85.2	86.5	85.6	5.39	5.46	5.41	1.04	1.06	1.09	2	2.00
	4:54		Middle	3.0	28.40	28.40		8.09	8.09		28.64	28.64		85.6	85.2		5.41	5.39		1.09	1.16		<2	
30/9/2017	11:45	Cloudy	Middle	2.5	28.60	28.60	28.65	7.80	7.80	7.81	29.03	29.03	29.05	84.8	84.6	84.5	5.57	5.56	5.56	1.73	1.73	1.74	5	4.00
	11:47		Middle	2.5	28.70	28.70		7.82	7.82		29.06	29.06		84.2	84.4		5.54	5.55		1.74	1.74		3	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at RW21-P789 - GEC/CRB/SHK
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	4:18	Fine	Middle	4.0	28.60	28.60	28.60	7.99	7.99	7.99	28.78	28.78	28.78	83.5	83.9	83.9	5.26	5.28	5.29	1.70	1.67	1.62	2	2.00
	4:19		Middle	4.0	28.60	28.60		7.99	7.99		28.78	28.78		84.3	84.0		5.31	5.29		1.64	1.48		2	
30/9/2017	7:30	Cloudy	Middle	3.5	28.40	28.40	28.35	6.96	6.96	6.98	29.24	29.24	29.24	94.0	95.1	94.4	6.22	6.29	6.24	2.73	2.73	2.81	<2	<2
	7:32		Middle	3.5	28.30	28.30		6.99	6.99		29.25	29.24		94.1	94.2		6.22	6.23		2.88	2.89		<2	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at WSD19 - Sheung Wan
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
28/9/2017	5:15	Fine	Middle	4.0	29.00	29.00	29.00	7.98	7.98	7.99	28.24	28.24	28.24	85.6	84.7	84.5	5.37	5.35	5.31	3.07	3.00	3.02	2	2.00
	5:16		Middle	4.0	29.00	29.00		7.99	7.99		28.24	28.24		83.5	84.1		5.24	5.28		3.01	2.98		<2	
30/9/2017	10:30	Cloudy	Middle	3.5	28.00	28.00	28.00	7.34	7.34	7.59	28.98	28.98	28.99	96.0	95.7	95.3	6.34	6.36	6.33	4.16	4.09	4.10	6	6.00
	10:32		Middle	3.5	28.00	28.00		7.84	7.84		28.99	28.99		95.4	94.2		6.35	6.27		4.08	4.07		6	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C7 - Windsor House
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	15:25	Fine	Middle	-	31.30	31.30	31.45	7.85	7.85	7.86	29.56	29.56	29.56	92.4	92.6	92.3	5.80	5.81	5.79	4.22	4.21	4.21	6	5.00
	15:27		Middle	-	31.60	31.60		7.87	7.87		29.56	29.56		92.5	91.7		5.80	5.75		4.19	4.21		4	
5/10/2017	16:25	Cloudy	Middle	-	30.10	30.10	30.10	8.21	8.21	8.21	30.61	30.61	30.61	82.0	82.8	81.9	5.23	5.28	5.23	2.22	2.30	2.30	2	2.00
	16:26		Middle	-	30.10	30.10		8.21	8.21		30.61	30.61		81.2	81.6		5.18	5.21		2.32	2.34		2	
7/10/2017	17:00	Fine	Middle	-	29.40	29.40	29.35	8.21	8.21	8.21	30.83	30.84	30.84	85.3	85.9	85.2	5.44	5.47	5.47	40.65	40.83	40.75	43	43.00
	17:01		Middle	-	29.30	29.30		8.21	8.21		30.84	30.84		84.7	84.9		5.46	5.49		40.92	40.61		43	
9/10/2017	9:35	Fine	Middle	-	29.70	29.70	29.65	8.17	8.17	8.17	30.57	30.57	30.58	84.7	85.1	84.7	5.44	5.47	5.44	9.80	9.80	9.79	9	9.50
	9:37		Middle	-	29.60	29.60		8.17	8.17		30.58	30.58		85.2	83.7		5.48	5.38		9.79	9.78		10	
11/10/2017	8:45	Fine	Middle	-	30.00	30.00	30.10	8.17	8.17	8.18	31.08	31.08	31.08	83.6	85.9	85.4	5.32	5.46	5.43	5.08	5.07	5.05	9	9.00
	8:47		Middle	-	30.20	30.20		8.18	8.18		31.08	31.08		86.2	85.8		5.48	5.45		5.03	5.00		9	
14/10/2017	12:30	Cloudy	Middle	-	28.60	28.60	28.50	8.22	8.22	8.22	31.09	31.09	31.10	81.4	81.8	81.9	5.31	5.34	5.35	4.50	4.50	4.51	4	4.00
	12:32		Middle	-	28.40	28.40		8.22	8.22		31.10	31.10		81.9	82.6		5.35	5.40		4.50	4.55		4	
16/10/2017	18:09	Cloudy	Middle	-	28.10	28.10	28.05	8.07	8.07	8.07	32.05	32.05	32.06	76.2	74.5	74.2	4.98	4.88	4.85	5.07	5.46	5.45	5	5.50
	18:11		Middle	-	28.00	28.00		8.06	8.06		32.06	32.06		73.2	72.7		4.79	4.76		5.63	5.63		6	
18/10/2017	16:55	Fine	Middle	-	28.80	28.80	28.75	8.26	8.26	8.26	31.38	31.38	31.38	86.0	86.3	86.2	5.60	5.61	5.61	3.74	3.79	3.79	7	6.00
	16:57		Middle	-	28.70	28.70		8.25	8.25		31.37	31.37		86.3	86.3		5.61	5.61		3.81	3.83		5	
20/10/2017	17:30	Cloudy	Middle	-	26.70	26.70	26.65	8.23	8.23	8.23	32.13	32.13	32.13	85.5	85.8	85.1	5.73	5.75	5.70	5.72	5.69	5.82	4	4.50
	17:31		Middle	-	26.60	26.60		8.23	8.23		32.13	32.13		84.2	84.7		5.65	5.67		5.93	5.95		5	
23/10/2017	8:05	Fine	Middle	-	26.80	26.80	26.70	8.24	8.24	8.24	31.95	31.95	31.96	82.1	82.6	82.7	5.50	5.53	5.54	4.64	4.63	4.61	11	10.50
	8:07		Middle	-	26.60	26.60		8.24	8.24		31.96	31.96		83.0	83.1		5.56	5.57		4.53	4.63		10	
25/10/2017	11:05	Fine	Middle	-	27.40	27.40	27.40	8.23	8.23	8.23	31.89	31.89	31.89	87.8	88.2	88.0	5.81	5.87	5.85	17.92	17.56	17.76	9	8.50
	11:07		Middle	-	27.40	27.40		8.23	8.23		31.89	31.89		88.0	88.1		5.86	5.86		17.77	17.77		8	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C1 - HKCEC Extension
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	17:50	Fine	Middle	2.5	29.50	29.50	29.55	7.94	7.94	7.94	30.02	30.02	30.02	74.0	74.1	73.9	4.78	4.79	4.77	13.68	13.70	13.68	14	14.00
	17:52		Middle	2.5	29.60	29.60		7.94	7.94		30.01	30.01		73.8	73.8		4.76	4.76		13.67	13.67		14	
5/10/2017	18:00	Cloudy	Middle	2.5	30.40	30.40	30.40	8.23	8.23	8.23	30.68	30.68	30.68	87.8	87.9	87.1	5.75	5.76	5.71	11.70	11.68	11.63	11	11.00
	18:01		Middle	2.5	30.40	30.40		8.23	8.23		30.68	30.68		86.1	86.6		5.64	5.67		11.62	11.51		11	
7/10/2017	18:21	Fine	Middle	3.0	29.10	29.10	29.10	8.22	8.22	8.22	30.91	30.91	30.91	83.1	85.6	83.5	5.38	5.54	5.40	14.40	14.04	13.99	9	9.00
	18:22		Middle	3.0	29.10	29.10		8.22	8.22		30.91	30.91		82.3	82.8		5.32	5.36		13.71	13.81		9	
9/10/2017	11:35	Fine	Middle	2.5	29.10	29.10	29.20	8.26	8.26	8.27	31.11	31.11	31.15	72.1	70.1	69.6	4.65	4.52	4.49	9.67	9.99	9.95	7	6.00
	11:37		Middle	2.5	29.30	29.30		8.27	8.27		31.18	31.18		67.6	68.4		4.36	4.41		10.06	10.07		5	
11/10/2017	12:05	Fine	Middle	2.5	29.40	29.40	29.40	8.23	8.23	8.23	31.17	31.17	31.17	86.9	87.3	86.8	5.59	5.62	5.59	13.40	13.40	13.40	14	14.00
	12:07		Middle	2.5	29.40	29.40		8.23	8.23		31.17	31.17		86.3	86.6		5.56	5.57		13.39	13.41		14	
14/10/2017	15:40	Cloudy	Middle	3.0	28.10	28.10	28.05	8.31	8.31	8.31	31.84	31.84	31.85	86.7	87.2	87.0	5.68	5.72	5.63	10.92	10.86	10.86	11	11.00
	15:42		Middle	3.0	28.00	28.00		8.31	8.31		31.85	31.85		86.4	87.5		5.66	5.47		10.84	10.82		11	
16/10/2017	18:06	Cloudy	Middle	3.5	27.70	27.70	27.70	8.08	8.08	8.08	32.36	32.36	32.36	98.0	97.4	96.9	6.44	6.40	6.37	11.65	11.49	11.49	11	10.50
	18:08		Middle	3.5	27.70	27.70		8.08	8.08		32.36	32.36		96.4	95.7		6.34	6.29		11.48	11.35		10	
18/10/2017	16:05	Fine	Middle	2.5	28.10	28.10	28.05	8.26	8.26	8.26	31.65	31.65	31.66	86.7	87.6	87.2	5.69	5.76	5.72	6.90	6.90	6.89	4	5.00
	16:07		Middle	2.5	28.00	28.00		8.26	8.26		31.66	31.66		87.1	87.3		5.71	5.72		6.86	6.88		6	
20/10/2017	18:46	Cloudy	Middle	3.0	26.80	26.80	26.75	8.26	8.26	8.26	32.49	32.49	32.49	90.7	89.1	90.0	6.48	6.37	6.43	8.65	8.63	8.62	14	13.00
	18:47		Middle	3.0	26.70	26.70		8.26	8.26		32.49	32.49		89.5	90.5		6.40	6.47		8.60	8.61		12	
23/10/2017	10:05	Fine	Middle	3.0	26.40	26.40	26.35	8.27	8.27	8.28	32.11	32.11	32.11	83.5	83.5	83.3	5.62	5.62	5.61	10.49	10.32	10.36	9	8.00
	10:07		Middle	3.0	26.30	26.30		8.28	8.28		32.10	32.10		83.2	83.0		5.60	5.59		10.31	10.31		7	
25/10/2017	10:10	Fine	Middle	3.0	26.10	26.10	26.00	8.24	8.24	8.24	32.15	32.15	32.15	81.8	82.7	82.7	5.54	5.60	5.60	9.97	9.96	10.01	8	8.00
	10:12		Middle	3.0	25.90	25.90		8.24	8.24		32.15	32.15		83.2	83.0		5.64	5.62		9.93	10.16		8	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P1 - HKCEC Phase I
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	17:30	Fine	Middle	2.5	30.10	30.10	30.20	7.82	7.82	7.85	29.82	29.82	29.83	81.6	81.6	81.2	5.22	5.22	5.19	6.35	6.37	6.37	4	5.00
	17:32		Middle	2.5	30.30	30.30		7.87	7.87		29.83	29.83		80.6	80.8		5.15	5.16		6.38	6.38		6	
5/10/2017	17:30	Cloudy	Middle	2.5	30.30	30.30	30.30	8.23	8.23	8.23	30.54	30.54	30.54	87.2	87.6	87.8	5.73	5.75	5.76	4.65	4.69	4.72	4	4.50
	17:31		Middle	2.5	30.30	30.30		8.23	8.23		30.54	30.54		87.8	88.4		5.77	5.80		4.70	4.83		5	
7/10/2017	17:55	Fine	Middle	3.0	29.20	29.20	29.20	8.21	8.21	8.21	30.85	30.85	30.85	83.8	83.5	83.2	5.42	5.39	5.38	8.01	8.03	7.97	9	10.50
	17:56		Middle	3.0	29.20	29.20		8.21	8.21		30.85	30.85		81.3	84.2		5.25	5.44		7.98	7.87		12	
9/10/2017	11:19	Fine	Middle	2.5	29.30	29.30	29.30	8.22	8.22	8.22	30.91	30.91	30.92	60.9	60.5	60.7	3.93	3.90	3.92	15.48	15.52	<u>15.58</u>	9	8.00
	11:21		Middle	2.5	29.30	29.30		8.22	8.20		30.92	30.92		60.6	60.9		3.91	3.93		15.65	15.67		7	
11/10/2017	11:45	Fine	Middle	2.5	30.40	30.40	30.25	8.18	8.18	8.19	30.96	30.96	30.96	83.8	84.2	84.1	5.31	5.37	5.35	8.24	8.19	8.17	9	9.50
	11:47		Middle	2.5	30.10	30.10		8.20	8.20		30.95	30.95		84.0	84.5		5.35	5.38		8.16	8.08		10	
14/10/2017	15:20	Cloudy	Middle	3.0	28.00	28.00	27.95	8.28	8.28	8.28	31.66	31.66	31.67	87.1	87.5	87.5	5.72	5.77	5.76	6.68	6.67	6.68	9	9.50
	15:22		Middle	3.0	27.90	27.90		8.28	8.28		31.67	31.67		87.8	87.7		5.77	5.77		6.68	6.69		10	
16/10/2017	17:50	Cloudy	Middle	3.5	27.90	27.90	27.90	8.02	8.02	8.04	32.36	32.36	32.37	101.1	102.0	101.5	6.62	6.67	6.64	9.74	9.72	<u>9.72</u>	5	5.50
	17:52		Middle	3.5	27.90	27.90		8.05	8.05		32.37	32.37		101.4	101.5		6.64	6.62		9.71	9.72		6	
18/10/2017	15:45	Fine	Middle	2.5	28.60	28.60	28.65	8.26	8.26	8.26	31.90	31.90	31.90	87.0	89.0	88.3	5.64	5.77	5.72	6.20	6.17	6.17	7	8.00
	15:47		Middle	2.5	28.70	28.70		8.26	8.26		31.90	31.90		88.7	88.4		5.75	5.73		6.16	6.15		9	
20/10/2017	18:21	Cloudy	Middle	3.0	26.90	26.90	26.90	8.30	8.30	8.30	32.47	32.47	32.48	87.9	89.2	88.6	6.27	6.36	6.32	5.00	4.90	4.90	4	6.00
	18:22		Middle	3.0	26.90	26.90		8.30	8.30		32.48	32.48		89.2	88.0		6.37	6.28		4.86	4.82		8	
23/10/2017	9:45	Fine	Middle	3.0	26.00	26.00	26.00	8.27	8.27	8.27	32.11	32.11	32.11	86.4	86.4	85.7	5.84	5.84	5.79	7.29	7.28	7.28	8	7.50
	9:47		Middle	3.0	26.00	26.00		8.27	8.27		32.11	32.11		84.9	84.9		5.74	5.74		7.27	7.27		7	
25/10/2017	9:50	Fine	Middle	3.0	26.50	26.50	26.50	8.20	8.20	8.21	32.28	32.28	32.29	84.9	85.7	85.1	5.69	5.72	5.70	11.38	11.48	<u>11.39</u>	8	8.00
	9:52		Middle	3.0	26.50	26.50		8.22	8.22		32.29	32.29		84.7	85.0		5.68	5.70		11.34	11.34		8	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P3 - APA
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	17:35	Fine	Middle	2.5	29.70	29.70	29.70	7.88	7.88	7.89	29.78	29.78	29.80	76.3	76.4	75.9	4.92	4.93	4.89	9.08	9.00	9.01	9	8.00
	17:37		Middle	2.5	29.70	29.70		7.90	7.90		29.81	29.81		75.7	75.1		4.88	4.84		8.98	8.99		7	
5/10/2017	17:37	Cloudy	Middle	2.5	30.50	30.50	30.50	8.23	8.23	8.23	30.58	30.58	30.58	86.0	87.5	86.5	5.63	5.73	5.66	6.95	6.99	6.87	6	5.50
	17:38		Middle	2.5	30.50	30.50		8.23	8.23		30.58	30.58		85.8	86.6		5.62	5.67		6.81	6.74		5	
7/10/2017	18:03	Fine	Middle	3.0	28.90	28.90	28.90	8.22	8.22	8.22	30.85	30.85	30.85	86.2	82.4	83.8	5.60	5.35	5.44	7.96	7.94	7.93	11	8.50
	18:04		Middle	3.0	28.90	28.90		8.22	8.22		30.85	30.85		83.3	83.1		5.41	5.40		7.92	7.90		6	
9/10/2017	11:23	Fine	Middle	2.5	29.10	29.10	29.10	8.23	8.23	8.23	30.83	30.83	30.86	67.9	67.0	68.1	4.40	4.34	4.41	11.36	11.41	11.38	9	8.50
	11:25		Middle	2.5	29.10	29.10		8.23	8.23		30.88	30.88		68.4	69.2		4.43	4.48		11.40	11.35		8	
11/10/2017	11:50	Fine	Middle	2.5	29.20	29.20	29.25	8.21	8.21	8.21	31.02	31.02	31.03	78.3	77.9	78.1	5.05	5.02	5.03	11.43	11.54	11.49	12	12.00
	11:52		Middle	2.5	29.30	29.30		8.21	8.21		31.03	31.03		78.0	78.0		5.03	5.03		11.50	11.49		12	
14/10/2017	15:25	Cloudy	Middle	3.0	28.20	28.20	28.15	8.29	8.29	8.29	31.75	31.75	31.75	83.9	84.3	83.6	5.50	5.53	5.48	9.87	9.83	9.79	7	7.50
	15:27		Middle	3.0	28.10	28.10		8.29	8.29		31.73	31.75		84.0	82.2		5.50	5.38		9.73	9.72		8	
16/10/2017	17:54	Cloudy	Middle	3.5	27.90	27.90	27.90	8.05	8.05	8.06	32.17	32.17	32.18	101.1	100.7	100.3	6.63	6.60	6.60	9.58	9.70	9.69	10	9.50
	17:56		Middle	3.5	27.90	27.90		8.06	8.06		32.18	32.18		99.8	99.5		6.55	6.61		9.70	9.79		9	
18/10/2017	15:50	Fine	Middle	2.5	28.30	28.30	28.30	8.26	8.26	8.26	31.82	31.82	31.82	86.5	87.9	87.2	5.64	5.73	5.69	6.02	6.06	6.04	4	3.50
	15:52		Middle	2.5	28.30	28.30		8.25	8.25		31.82	31.82		87.6	86.9		5.71	5.66		6.04	6.03		3	
20/10/2017	18:27	Cloudy	Middle	3.0	26.50	26.50	26.50	8.30	8.30	8.30	32.46	32.46	32.46	87.9	89.8	89.2	6.31	6.44	6.40	8.71	8.69	8.65	6	6.00
	18:28		Middle	3.0	26.50	26.50		8.30	8.30		32.46	32.46		89.6	89.5		6.43	6.42		8.60	8.58		6	
23/10/2017	9:50	Fine	Middle	3.0	26.10	26.10	26.10	8.26	8.26	8.26	32.12	32.12	33.38	81.3	81.7	81.9	5.50	5.53	5.53	8.75	8.28	8.37	8	7.00
	9:52		Middle	3.0	26.10	26.10		8.26	8.26		37.12	32.16		82.3	82.3		5.50	5.57		8.22	8.22		6	
25/10/2017	9:55	Fine	Middle	3.0	25.80	25.80	25.80	8.23	8.23	8.23	32.16	32.16	32.16	83.2	83.6	83.2	5.65	5.67	5.63	10.51	10.58	10.65	8	7.50
	9:57		Middle	3.0	25.80	25.80		8.23	8.23		32.16	32.16		82.6	83.4		5.54	5.66		10.73	10.79		7	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P4 - SOC
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	17:40	Fine	Middle	2.5	29.50	29.50	29.55	7.90	7.90	7.91	29.98	29.98	29.99	75.1	75.2	74.8	4.85	4.86	4.83	13.47	13.66	13.62	15	16.00
	17:42		Middle	2.5	29.60	29.60		7.92	7.92		29.99	29.99		74.7	74.2		4.82	4.79		13.66	13.67		17	
5/10/2017	17:43	Cloudy	Middle	2.5	30.50	30.50	30.50	8.21	8.21	8.21	30.68	30.68	30.68	86.5	87.7	87.5	5.66	5.74	5.73	10.62	10.60	10.54	8	8.00
	17:44		Middle	2.5	30.50	30.50		8.21	8.21		30.68	30.68		88.7	87.2		5.81	5.71		10.53	10.41		8	
7/10/2017	18:09	Fine	Middle	3.0	29.00	29.00	29.00	8.22	8.22	8.22	30.83	30.83	30.83	83.6	85.0	83.7	5.42	5.51	5.42	8.90	8.93	8.89	8	8.50
	18:10		Middle	3.0	29.00	29.00		8.22	8.22		30.83	30.83		83.8	82.3		5.43	5.33		8.88	8.86		9	
9/10/2017	11:27	Fine	Middle	2.5	29.00	29.00	29.05	8.24	8.24	8.24	31.91	31.91	31.42	76.4	76.4	75.5	4.95	4.94	4.88	9.47	9.69	9.65	6	6.50
	11:29		Middle	2.5	29.10	29.10		8.24	8.24		30.93	30.93		75.0	74.0		4.85	4.79		9.72	9.72		7	
11/10/2017	11:55	Fine	Middle	2.5	29.10	29.10	29.10	8.23	8.23	8.23	31.21	31.21	31.21	83.3	83.4	82.9	5.38	5.39	5.37	15.12	15.34	15.17	18	18.00
	11:57		Middle	2.5	29.10	29.10		8.23	8.23		31.20	31.20		82.7	82.3		5.34	5.36		15.11	15.10		18	
14/10/2017	15:30	Cloudy	Middle	3.0	28.00	28.00	28.00	8.30	8.30	8.31	31.83	31.83	31.84	84.8	84.2	84.9	5.56	5.53	5.58	11.49	11.42	11.38	10	10.50
	15:32		Middle	3.0	28.00	28.00		8.31	8.31		31.84	31.84		85.2	85.3		5.59	5.62		11.32	11.30		11	
16/10/2017	17:58	Cloudy	Middle	3.5	27.70	27.70	27.70	8.06	8.06	8.07	32.37	32.37	32.37	101.2	100.4	100.0	6.64	6.59	6.57	13.15	13.12	13.11	11	12.00
	18:00		Middle	3.5	27.70	27.70		8.07	8.07		32.37	32.37		99.3	99.2		6.52	6.51		13.12	13.05		13	
18/10/2017	15:55	Fine	Middle	2.5	28.00	28.00	28.00	8.26	8.26	8.27	31.80	31.80	31.80	88.1	88.4	88.5	5.77	5.79	5.80	6.14	6.19	6.19	4	4.50
	15:57		Middle	2.5	28.00	28.00		8.27	8.27		31.80	31.80		88.3	89.0		5.79	5.83		6.20	6.24		5	
20/10/2017	18:33	Cloudy	Middle	3.0	26.80	26.80	26.80	8.28	8.28	8.28	32.45	32.45	32.45	90.1	90.3	89.5	6.46	6.48	6.42	9.06	9.02	9.01	11	12.00
	18:34		Middle	3.0	26.80	26.80		8.28	8.28		32.45	32.45		88.2	89.5		6.33	6.42		8.98	8.96		13	
23/10/2017	9:55	Fine	Middle	3.0	26.10	26.10	26.10	8.27	8.27	8.28	32.11	32.11	32.12	85.7	85.8	85.6	5.78	5.80	5.78	9.90	9.90	9.90	12	11.00
	9:57		Middle	3.0	26.10	26.10		8.28	8.28		32.12	32.12		85.5	85.4		5.77	5.77		9.90	9.91		10	
25/10/2017	10:00	Fine	Middle	3.0	25.90	25.90	25.85	8.23	8.23	8.23	32.13	32.13	32.14	84.4	84.9	84.5	5.73	5.77	5.74	15.02	15.43	15.42	14	13.50
	10:02		Middle	3.0	25.80	25.80		8.23	8.23		32.14	32.14		83.7	84.9		5.69	5.77		15.55	15.69		13	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P5 - WCT / RT / IT
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth (m)		Water Temperature (°C)			pH (-)			Salinity (ppt)			DO Saturation (%)			DO (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	17:45	Fine	Middle	2.5	29.50	29.50	29.55	7.92	7.92	7.93	29.96	29.96	29.97	74.6	74.3	74.5	4.82	4.80	4.81	12.27	12.20	12.18	11	12.00
	17:47		Middle	2.5	29.60	29.60		7.93	7.93		29.97	29.97		74.4	74.5		4.81	4.81		12.14	12.10		13	
5/10/2017	17:52	Cloudy	Middle	2.5	30.30	30.30	30.30	8.23	8.23	8.23	30.66	30.66	30.66	87.7	88.1	87.5	5.76	5.79	5.74	7.90	7.94	7.88	8	8.00
	17:53		Middle	2.5	30.30	30.30		8.23	8.23		30.66	30.66		87.0	87.3		5.66	5.74		7.85	7.82		8	
7/10/2017	18:15	Fine	Middle	3.0	29.00	29.00	29.00	8.22	8.22	8.22	30.90	30.90	30.90	89.1	89.3	88.8	5.78	5.80	5.76	9.48	9.40	9.47	6	6.00
	18:16		Middle	3.0	29.00	29.00		8.22	8.22		30.90	30.90		88.3	88.4		5.72	5.73		9.51	9.50		6	
9/10/2017	11:31	Fine	Middle	2.5	29.10	29.10	29.10	8.25	8.25	8.26	31.00	31.00	31.06	73.8	71.9	72.0	4.77	4.64	4.65	10.17	10.16	10.12	5	6.00
	11:33		Middle	2.5	29.10	29.10		8.26	8.26		31.12	31.12		71.4	70.7		4.61	4.57		10.13	10.01		7	
11/10/2017	12:00	Fine	Middle	2.5	29.30	29.30	29.30	8.23	8.23	8.23	31.23	31.23	31.23	80.2	80.7	80.7	5.16	5.19	5.19	13.75	13.76	13.74	14	14.00
	12:02		Middle	2.5	29.30	29.30		8.23	8.23		31.23	31.23		80.9	80.9		5.21	5.21		13.69	13.75		14	
14/10/2017	15:35	Cloudy	Middle	3.0	28.10	28.10	28.05	8.31	8.31	8.31	31.82	31.82	31.84	83.7	83.1	84.6	5.48	5.44	5.54	13.12	13.23	13.31	12	12.50
	15:37		Middle	3.0	28.00	28.00		8.31	8.31		31.86	31.86		85.6	86.0		5.61	5.64		13.44	13.43		13	
16/10/2017	18:02	Cloudy	Middle	3.5	27.80	27.80	27.80	8..07	8.07	8.08	32.32	32.32	32.34	99.0	98.9	98.3	6.49	6.49	6.45	11.35	11.60	11.48	9	10.00
	18:04		Middle	3.5	27.80	27.80		8.08	8.08		32.36	32.36		98.3	96.9		6.45	6.36		11.48	11.47		11	
18/10/2017	16:00	Fine	Middle	2.5	27.90	27.90	27.90	8.26	8.26	8.27	31.78	31.78	31.78	86.7	87.3	86.8	5.66	5.73	5.69	7.20	7.19	7.24	7	6.50
	16:02		Middle	2.5	27.90	27.90		8.27	8.27		31.78	31.78		86.6	86.6		5.69	5.69		7.26	7.29		6	
20/10/2017	18:40	Cloudy	Middle	3.0	26.90	26.90	26.85	8.30	8.30	8.30	32.49	32.49	32.49	89.6	89.4	89.4	6.39	6.38	6.38	9.00	8.99	8.97	13	12.00
	18:41		Middle	3.0	26.80	26.80		8.30	8.30		32.49	32.49		89.6	89.0		6.40	6.35		9.01	8.88		11	
23/10/2017	10:00	Fine	Middle	3.0	26.20	26.20	26.15	8.28	8.28	8.28	32.11	32.11	32.11	83.8	83.8	83.8	5.66	5.66	5.66	9.70	9.74	9.72	8	8.50
	10:02		Middle	3.0	26.10	26.10		8.28	8.28		32.11	32.11		83.2	84.4		5.62	5.70		9.71	9.71		9	
25/10/2017	10:05	Fine	Middle	3.0	25.90	25.90	25.80	8.24	8.24	8.24	32.15	32.15	32.15	80.1	81.0	80.8	5.45	5.51	5.50	10.79	10.73	10.82	9	9.00
	10:07		Middle	3.0	25.70	25.70		8.24	8.24		32.15	32.15		81.5	80.6		5.54	5.49		10.76	10.98		9	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at RW21-P789 - GEC / CRB / SHK
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	17:00	Fine	Middle	3.5	30.50	30.50	30.50	7.89	7.89	7.89	29.75	29.75	29.75	75.5	76.7	75.6	4.80	4.88	4.80	5.84	5.77	5.76	6	7.00
	17:02		Middle	3.5	30.50	30.50		7.89	7.89		29.75	29.75		73.6	76.5		4.67	4.86		5.71	5.72		8	
5/10/2017	15:56	Cloudy	Middle	3.5	30.10	30.10	30.10	8.17	8.17	8.18	30.65	30.65	30.65	82.8	85.5	83.8	5.28	5.45	5.35	4.80	4.82	4.80	4	4.00
	15:57		Middle	3.5	30.10	30.10		8.18	8.18		30.65	30.65		83.3	83.7		5.31	5.37		4.86	4.72		4	
7/10/2017	17:40	Fine	Middle	3.5	29.00	29.00	29.00	8.18	8.18	8.19	30.90	30.90	30.91	87.4	88.7	88.2	5.66	5.75	5.71	8.02	7.99	7.97	7	7.50
	17:41		Middle	3.5	29.00	29.00		8.19	8.19		30.91	30.91		88.4	88.3		5.72	5.72		8.00	7.88		8	
9/10/2017	11:47	Fine	Middle	3.5	29.40	29.40	29.40	8.26	8.26	8.26	31.20	31.20	31.20	69.7	70.4	70.0	4.48	4.53	4.50	12.90	12.89	12.85	6	7.00
	11:49		Middle	3.5	29.40	29.40		8.26	8.26		31.20	31.20		70.1	69.6		4.51	4.47		12.82	12.80		8	
11/10/2017	11:25	Fine	Middle	3.5	30.10	30.10	30.25	8.19	8.19	8.20	31.03	31.03	31.04	83.6	83.1	82.9	5.32	5.27	5.26	11.13	11.12	11.12	15	14.50
	11:27		Middle	3.5	30.40	30.40		8.20	8.20		31.04	31.04		81.6	83.2		5.18	5.27		11.12	11.12		14	
14/10/2017	12:05	Cloudy	Middle	3.5	28.40	28.40	28.35	8.27	8.27	8.28	31.67	31.67	31.67	81.8	82.9	82.2	5.34	5.40	5.36	6.63	6.68	6.66	7	8.00
	12:07		Middle	3.5	28.30	28.30		8.28	8.28		31.67	31.67		82.8	81.4		5.40	5.31		6.65	6.68		9	
16/10/2017	17:01	Cloudy	Middle	3.5	27.90	27.90	27.90	7.99	7.99	8.00	32.36	32.36	32.36	100.7	100.6	100.2	6.60	6.59	6.57	8.85	8.89	8.93	9	8.50
	17:03		Middle	3.5	27.90	27.90		8.01	8.01		32.36	32.36		100.3	99.3		6.57	6.51		8.99	8.99		8	
18/10/2017	16:30	Fine	Middle	3.5	28.20	28.20	28.20	8.26	8.26	8.26	31.60	31.60	31.60	84.8	86.9	86.1	5.55	5.69	5.64	7.04	7.04	7.04	5	4.50
	16:32		Middle	3.5	28.20	28.20		8.26	8.26		31.60	31.60		86.9	85.9		5.69	5.62		7.03	7.03		4	
20/10/2017	18:00	Cloudy	Middle	4.0	26.50	26.50	26.50	8.18	8.18	8.18	32.62	32.62	32.62	86.1	88.5	87.9	5.77	5.93	5.89	7.78	7.76	7.75	9	9.00
	18:01		Middle	4.0	26.50	26.50		8.18	8.18		32.62	32.62		88.0	89.0		5.90	5.97		7.72	7.74		9	
23/10/2017	7:35	Fine	Middle	3.5	25.90	25.90	25.85	8.25	8.25	8.27	32.24	32.24	32.26	81.3	81.1	82.0	5.51	5.50	5.56	11.59	11.53	11.40	10	10.50
	7:37		Middle	3.5	25.80	25.80		8.29	8.29		32.28	32.28		82.2	83.2		5.57	5.64		11.24	11.22		11	
25/10/2017	10:40	Fine	Middle	3.5	26.60	26.60	26.60	8.24	8.24	8.24	32.17	32.17	32.17	82.5	83.1	82.9	5.52	5.59	5.56	10.91	10.91	10.91	7	7.50
	10:42		Middle	3.5	26.60	26.60		8.25	8.24		32.16	32.16		83.8	82.2		5.61	5.50		10.91	10.92		8	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at WSD19 - Sheung Wan
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	16:00	Fine	Middle	3.5	30.50	30.50	30.55	7.83	7.83	7.85	29.65	29.65	29.65	90.0	90.3	90.2	5.73	5.75	5.74	8.89	8.99	9.00	11	11.00
	16:02		Middle	3.5	30.60	30.60		7.86	7.86		29.65	29.65		90.2	90.2		5.74	5.74		9.05	9.05		11	
5/10/2017	18:15	Cloudy	Middle	3.5	30.50	30.50	30.50	8.19	8.19	8.19	30.68	30.68	30.68	83.6	85.0	84.7	5.47	5.57	5.55	6.53	6.49	6.49	7	7.00
	18:16		Middle	3.5	30.50	30.50		8.19	8.19		30.68	30.68		84.2	86.1		5.51	5.63		6.47	6.45		7	
7/10/2017	18:40	Fine	Middle	3.5	29.10	29.10	29.10	8.14	8.14	8.15	30.84	30.84	30.84	88.7	87.8	87.9	5.74	5.69	5.69	13.53	13.32	13.30	15	14.50
	18:41		Middle	3.5	29.10	29.10		8.15	8.15		30.84	30.84		87.1	87.8		5.64	5.68		13.19	13.15		14	
9/10/2017	8:10	Fine	Middle	3.5	29.40	29.40	29.40	8.19	8.19	8.19	30.79	30.79	30.79	52.2	51.7	51.2	3.36	3.33	3.30	15.11	15.12	15.12	18	17.00
	8:12		Middle	3.5	29.40	29.40		8.19	8.19		30.78	30.78		50.8	50.2		3.29	3.23		15.12	15.13		16	
11/10/2017	10:25	Fine	Middle	3.5	30.00	30.00	30.10	8.20	8.20	8.20	30.98	30.98	30.99	85.0	84.0	84.3	5.41	5.34	5.36	12.21	12.23	12.23	14	14.50
	10:27		Middle	3.5	30.20	30.20		8.20	8.20		30.99	30.99		84.5	83.8		5.37	5.33		12.23	12.24		15	
14/10/2017	14:05	Cloudy	Middle	3.5	28.20	28.20	28.15	8.26	8.26	8.26	31.66	31.66	31.67	81.2	81.1	80.9	5.32	5.31	5.30	11.00	11.02	11.01	12	11.50
	14:07		Middle	3.5	28.10	28.10		8.26	8.26		31.67	31.67		80.3	80.9		5.26	5.30		11.00	11.00		11	
16/10/2017	16:07	Cloudy	Middle	3.5	28.00	28.00	27.90	8.07	8.01	8.04	33.39	32.39	32.65	118.3	113.3	113.5	7.74	7.41	7.43	10.51	10.51	10.58	10	9.50
	16:09		Middle	3.5	27.80	27.80		8.04	8.04		32.41	32.41		112.1	110.3		7.33	7.22		10.60	10.71		9	
18/10/2017	18:05	Fine	Middle	4.0	28.20	28.20	28.20	8.26	8.26	8.27	31.83	31.83	31.83	84.8	85.4	85.3	5.54	5.65	5.62	8.00	8.01	8.01	6	7.00
	18:07		Middle	4.0	28.20	28.20		8.28	8.28		31.83	31.83		85.1	85.9		5.62	5.68		8.01	8.02		8	
20/10/2017	20:00	Cloudy	Middle	4.0	26.20	26.20	26.20	8.19	8.19	8.19	32.48	32.48	32.48	90.7	89.2	89.2	6.45	6.34	6.34	7.94	7.98	7.98	9	9.00
	20:01		Middle	4.0	26.20	26.20		8.19	8.19		32.48	32.48		88.1	88.7		6.26	6.31		8.01	7.97		9	
23/10/2017	8:45	Fine	Middle	4.0	26.20	26.20	26.15	8.27	8.27	8.27	31.59	31.59	31.60	84.4	84.8	83.9	5.72	5.74	5.69	7.65	7.66	7.65	9	8.00
	8:47		Middle	4.0	26.10	26.10		8.27	8.27		31.61	31.61		82.5	83.9		5.62	5.68		7.65	7.65		7	
25/10/2017	11:30	Fine	Middle	4.0	26.90	26.90	26.90	8.23	8.23	8.23	32.15	32.15	32.16	90.0	90.6	90.3	5.99	6.03	6.01	9.55	9.39	9.52	8	7.00
	11:32		Middle	4.0	26.90	26.90		8.23	8.23		32.16	32.16		90.5	89.9		6.03	5.98		9.58	9.57		6	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C7 - Windsor House
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth (m)		Water Temperature (°C)			pH (-)			Salinity (ppt)			DO Saturation (%)			DO (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	10:30	Fine	Middle	-	30.40	30.40	30.50	7.64	7.64	7.69	29.95	29.95	29.95	94.3	94.9	95.0	5.99	6.03	6.04	3.72	3.74	3.74	4	4.50
	10:32		Middle	-	30.60	30.60		7.73	7.73		29.95	29.95		95.0	95.7		6.04	6.08		3.73	3.77		5	
5/10/2017	11:30	Cloudy	Middle	-	31.10	31.10	31.05	8.17	8.17	8.17	30.74	30.75	30.75	86.8	88.0	86.3	5.46	5.53	5.43	3.60	3.46	3.41	4	4.00
	11:31		Middle	-	31.00	31.00		8.17	8.17		30.75	30.75		85.6	84.7		5.38	5.33		3.32	3.25		4	
7/10/2017	12:05	Fine	Middle	-	30.40	30.40	30.35	7.98	7.98	7.98	30.70	30.70	30.70	98.3	99.3	98.8	6.24	6.31	6.28	10.05	10.05	10.05	7	8.00
	12:07		Middle	-	30.30	30.30		7.98	7.98		30.70	30.70		99.0	98.7		6.29	6.27		10.05	10.05		9	
9/10/2017	13:57	Fine	Middle	-	30.00	30.00	30.05	8.20	8.20	8.20	30.80	30.80	30.80	69.8	69.3	69.4	4.45	4.42	4.40	12.90	12.99	12.86	9	9.50
	13:59		Middle	-	30.10	30.10		8.20	8.20		30.79	30.79		69.1	69.5		4.34	4.40		12.81	12.75		10	
11/10/2017	20:45	Cloudy	Middle	-	29.70	29.70	29.70	8.13	8.13	8.13	31.52	31.52	31.52	85.8	85.4	84.9	5.48	5.45	5.42	8.63	8.64	8.65	6	6.00
	20:46		Middle	-	29.70	29.70		8.13	8.13		31.52	31.52		84.7	83.7		5.40	5.35		8.59	8.73		6	
14/10/2017	7:45	Cloudy	Middle	-	28.90	28.90	28.75	8.24	8.24	8.24	31.58	31.58	31.58	83.7	84.5	84.0	5.42	5.47	5.44	7.59	7.56	7.56	4	4.50
	7:47		Middle	-	28.60	28.60		8.24	8.24		31.58	31.58		84.4	83.3		5.47	5.40		7.55	7.54		5	
16/10/2017	11:25	Cloudy	Middle	-	28.20	28.20	28.20	8.04	8.04	8.04	32.16	32.16	32.16	95.7	95.7	95.4	6.24	6.24	6.32	4.64	4.57	4.56	2	3.00
	11:27		Middle	-	28.20	28.20		8.04	8.04		32.16	32.16		95.8	94.3		6.54	6.25		4.51	4.51		4	
18/10/2017	10:50	Fine	Middle	-	27.80	27.80	28.10	8.30	8.30	8.31	31.69	31.69	31.70	87.7	87.7	87.7	5.71	5.71	5.71	3.73	3.79	3.75	3	3.50
	10:52		Middle	-	28.40	28.40		8.33	8.30		31.70	31.70		87.9	87.4		5.73	5.70		3.74	3.73		4	
20/10/2017	11:35	Fine	Middle	-	28.30	28.30	28.35	8.22	8.22	8.22	31.78	31.78	31.79	84.6	85.0	84.8	5.52	5.54	5.53	6.48	6.46	6.45	5	4.00
	11:37		Middle	-	28.40	28.40		8.22	8.22		31.79	31.79		84.5	85.1		5.51	5.55		6.43	6.42		3	
23/10/2017	15:55	Fine	Middle	-	28.00	28.00	28.05	8.20	8.21	8.21	31.84	31.84	31.84	85.1	85.6	85.3	5.57	5.60	5.59	6.09	6.02	5.99	6	6.00
	15:57		Middle	-	28.10	28.10		8.22	8.22		31.84	31.84		85.4	85.2		5.59	5.58		5.93	5.90		6	
25/10/2017	1:45	Fine	Middle	-	24.80	24.80	24.75	8.20	8.20	8.20	32.62	32.62	32.63	81.2	83.2	82.9	5.63	5.74	5.73	6.19	6.21	6.28	5	5.50
	1:46		Middle	-	24.70	24.70		8.20	8.20		32.63	32.63		83.9	83.4		5.79	5.75		6.27	6.45		6	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C1 - HKCEC
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth (m)		Water Temperature (°C)			pH (-)			Salinity (ppt)			DO Saturation (%)			DO (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	12:05	Fine	Middle	2.5	29.90	29.90	29.90	7.92	7.92	7.92	29.98	29.98	29.95	88.1	88.5	88.2	5.65	5.68	5.66	6.75	6.74	6.76	4	4.00
	12:07		Middle	2.5	29.90	29.90		7.92	7.92		29.92	29.92		88.3	87.7		5.67	5.62		6.77	6.76		4	
5/10/2017	13:53	Cloudy	Middle	2.5	30.60	30.60	30.60	8.22	8.22	8.22	30.57	30.57	30.58	84.6	85.1	84.3	5.36	5.39	5.34	6.27	6.20	6.25	5	5.00
	13:54		Middle	2.5	30.60	30.60		8.22	8.22		30.58	30.58		84.0	83.6		5.32	5.29		6.23	6.30		5	
7/10/2017	11:15	Fine	Middle	3.0	29.20	29.20	29.15	7.99	7.99	7.99	31.02	31.02	31.03	95.2	94.6	94.4	6.15	6.11	6.10	7.65	7.71	7.68	9	8.50
	11:17		Middle	3.0	29.10	29.10		7.99	7.99		31.03	31.03		94.3	93.5		6.09	6.04		7.74	7.61		8	
9/10/2017	15:45	Fine	Middle	2.5	29.30	29.40	29.38	8.24	8.24	8.24	30.95	30.95	30.95	59.2	61.3	61.1	3.81	3.95	3.81	9.32	9.34	<u>9.35</u>	8	8.00
	15:47		Middle	2.5	29.40	29.40		8.24	8.24		30.95	30.95		62.3	61.7		4.01	3.47		9.36	9.38		8	
11/10/2017	21:58	Cloudy	Middle	3.0	29.00	29.00	29.00	8.22	8.22	8.22	31.75	31.75	31.75	84.8	87.7	87.0	5.65	5.85	5.80	6.25	6.41	6.32	8	11.50
	21:59		Middle	3.0	29.00	29.00		8.22	8.22		31.75	31.75		87.6	87.7		5.84	5.84		6.34	6.27		15	
14/10/2017	10:50	Cloudy	Middle	3.0	28.20	28.20	28.40	8.27	8.27	8.27	31.47	31.47	31.53	79.7	80.7	80.3	5.21	5.28	5.25	6.42	6.40	6.32	8	8.00
	10:52		Middle	3.0	28.60	28.60		8.27	8.27		31.59	31.59		80.5	80.4		5.25	5.24		6.76	5.71		8	
16/10/2017	10:24	Cloudy	Middle	3.0	28.50	28.50	28.50	8.06	8.06	8.06	32.34	32.34	32.34	103.2	103.6	102.7	6.69	6.72	6.66	8.62	8.72	8.47	6	7.00
	10:26		Middle	3.0	28.50	28.50		8.06	8.06		32.34	32.34		103.1	100.7		6.68	6.53		8.21	8.31		8	
18/10/2017	13:50	Fine	Middle	2.5	28.10	28.10	28.10	8.25	8.25	8.26	31.83	31.83	31.83	88.9	88.6	88.9	5.82	5.80	5.82	9.06	9.06	9.02	10	9.00
	13:52		Middle	2.5	28.10	28.10		8.26	8.26		31.83	31.83		88.8	89.2		5.82	5.84		9.04	8.92		8	
20/10/2017	14:35	Fine	Middle	3.0	27.20	27.20	27.15	8.27	8.27	8.27	31.95	31.95	31.95	84.7	85.1	85.1	5.63	5.66	5.66	8.25	8.20	8.19	5	5.00
	14:37		Middle	3.0	27.10	27.10		8.27	8.27		31.95	31.95		85.5	85.0		5.69	5.65		8.12	8.17		5	
23/10/2017	14:35	Fine	Middle	3.0	27.30	27.30	27.30	8.24	8.24	8.24	32.14	32.14	32.14	85.0	85.7	85.6	5.63	5.67	5.66	7.64	7.65	7.65	8	7.00
	14:37		Middle	3.0	27.30	27.30		8.24	8.24		32.14	32.14		85.5	86.0		5.66	5.69		7.65	7.65		6	
25/10/2017	4:40	Fine	Middle	2.5	24.70	24.70	24.65	8.22	8.22	8.22	32.72	32.72	32.72	81.3	82.2	81.8	5.61	5.68	5.65	7.02	7.04	7.08	9	8.50
	4:41		Middle	2.5	24.60	24.60		8.22	8.22		32.72	32.72		81.6	82.0		5.63	5.66		7.10	7.14		8	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P1 - HKCEC Phase I
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth (m)		Water Temperature (°C)			pH (-)			Salinity (ppt)			DO Saturation (%)			DO (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	11:45	Fine	Middle	2.5	30.20	30.20	30.30	7.80	7.80	7.83	30.10	30.10	30.10	93.6	94.4	93.8	5.96	6.02	5.98	5.44	5.43	5.44	5	5.00
	11:47		Middle	2.5	30.40	30.40		7.85	7.85		30.10	30.10		93.4	93.8		5.95	5.98		5.45	5.43		5	
5/10/2017	13:30	Cloudy	Middle	2.5	30.40	30.40	30.40	8.20	8.20	8.20	30.73	30.73	30.73	85.0	87.2	86.9	5.39	5.53	5.51	6.81	6.94	6.89	6	6.00
	13:31		Middle	2.5	30.40	30.40		8.20	8.20		30.73	30.73		86.8	88.6		5.51	5.62		6.92	6.90		6	
7/10/2017	10:55	Fine	Middle	3.0	29.40	29.40	29.40	7.86	7.86	7.89	31.07	31.07	31.07	103.4	103.1	103.4	6.65	6.61	6.64	8.59	8.60	8.63	8	8.50
	10:57		Middle	3.0	29.40	29.40		7.92	7.92		31.07	31.07		103.8	103.1		6.68	6.61		8.65	8.69		9	
9/10/2017	15:27	Fine	Middle	2.5	29.70	29.70	29.70	8.23	8.23	8.23	30.99	30.99	30.97	61.9	61.0	61.9	3.96	3.91	3.96	8.94	8.92	8.92	6	6.00
	15:31		Middle	2.5	29.70	29.70		8.23	8.23		30.95	30.95		60.9	63.7		3.90	4.08		8.91	8.90		6	
11/10/2017	21:37	Cloudy	Middle	3.0	29.90	30.00	29.98	8.20	8.20	8.20	31.70	31.70	31.70	84.3	86.8	85.8	5.27	5.43	5.37	5.21	5.19	5.20	7	6.50
	21:38		Middle	3.0	30.00	30.00		8.20	8.20		31.70	31.70		85.7	86.2		5.36	5.40		5.23	5.17		6	
14/10/2017	10:30	Cloudy	Middle	3.0	27.80	27.80	27.75	8.27	8.27	8.27	31.61	31.61	31.62	80.7	80.5	80.7	5.32	5.31	5.32	6.26	6.21	6.21	7	7.50
	10:32		Middle	3.0	27.70	27.70		8.27	8.27		31.62	31.62		80.9	80.7		5.33	5.32		6.18	6.18		8	
16/10/2017	10:36	Cloudy	Middle	3.0	28.30	28.30	28.30	8.02	8.03	8.03	32.44	32.44	32.44	107.1	107.1	106.2	6.96	6.96	6.90	7.07	7.08	7.06	5	5.50
	10:38		Middle	3.0	28.30	28.30		8.03	8.03		32.43	32.43		105.7	104.8		6.87	6.81		7.05	7.04		6	
18/10/2017	13:30	Fine	Middle	2.5	29.60	29.60	29.65	8.24	8.24	8.24	31.94	31.94	31.94	91.6	91.9	91.4	5.85	5.87	5.84	8.65	8.66	8.66	8	7.50
	13:32		Middle	2.5	29.70	29.70		8.24	8.24		31.94	31.94		91.6	90.6		5.85	5.78		8.67	8.67		7	
20/10/2017	14:15	Fine	Middle	3.0	27.50	27.50	27.50	8.26	8.26	8.27	31.99	31.99	32.00	88.4	88.9	88.6	5.84	5.87	5.85	8.29	8.25	8.32	5	6.00
	14:17		Middle	3.0	27.50	27.50		8.27	8.27		32.00	32.00		88.5	88.5		5.84	5.85		8.35	8.40		7	
23/10/2017	14:15	Fine	Middle	3.0	27.40	27.40	27.45	8.14	8.14	8.14	32.17	32.17	32.17	85.3	84.4	84.6	5.63	5.57	5.58	6.89	6.88	6.88	5	5.50
	14:17		Middle	3.0	27.50	27.50		8.14	8.14		32.17	32.17		82.5	86.0		5.44	5.68		6.88	6.88		6	
25/10/2017	4:10	Fine	Middle	2.5	24.60	24.60	24.60	8.26	8.26	8.26	32.77	32.77	32.77	85.1	86.7	86.4	5.86	5.97	5.96	7.32	7.39	7.31	7	7.50
	4:11		Middle	2.5	24.60	24.60		8.26	8.26		32.77	32.77		87.4	86.3		6.04	5.96		7.28	7.26		8	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P3 - APA
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth (m)		Water Temperature (°C)			pH (-)			Salinity (ppt)			DO Saturation (%)			DO (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	11:50	Fine	Middle	2.5	30.10	30.10	30.00	7.86	7.86	7.88	29.82	29.82	29.84	92.2	93.8	92.8	5.89	6.02	5.95	5.64	5.67	5.60	11	10.00
	11:52		Middle	2.5	29.90	29.90		7.89	7.89		29.85	29.85		92.8	92.3		5.95	5.92		5.56	5.54		9	
5/10/2017	13:37	Cloudy	Middle	2.5	30.20	30.20	30.20	8.22	8.22	8.22	30.69	30.69	30.69	85.1	88.4	86.9	5.42	5.63	5.54	6.99	6.89	6.94	5	5.00
	13:38		Middle	2.5	30.20	30.20		8.22	8.22		30.69	30.69		87.8	86.1		5.59	5.50		6.96	6.93		5	
7/10/2017	11:00	Fine	Middle	3.0	29.10	29.10	29.15	7.93	7.90	7.94	31.05	31.05	31.05	96.6	96.0	96.5	6.24	6.20	6.23	8.34	8.30	8.28	8	9.00
	11:02		Middle	3.0	29.20	29.20		7.96	7.96		31.04	31.04		97.0	96.3		6.27	6.22		8.26	8.21		10	
9/10/2017	15:33	Fine	Middle	2.5	29.40	29.40	29.30	8.24	8.24	8.24	30.92	30.92	30.93	72.0	68.7	68.6	4.65	4.44	4.43	9.13	9.10	9.00	6	6.50
	15:35		Middle	2.5	29.20	29.20		8.24	8.24		30.94	30.94		67.1	66.5		4.34	4.30		8.89	8.89		7	
11/10/2017	21:42	Cloudy	Middle	3.0	29.20	29.20	29.20	8.15	8.15	8.13	31.68	31.68	31.68	87.1	87.3	87.9	5.79	5.82	5.85	8.53	8.50	8.52	6	5.50
	21:43		Middle	3.0	29.20	29.20		8.10	8.10		31.68	31.68		88.5	88.6		5.88	5.89		8.48	8.55		5	
14/10/2017	10:35	Cloudy	Middle	3.0	28.10	28.10	28.05	8.27	8.27	8.27	31.60	31.60	31.60	79.3	80.4	79.7	5.20	5.28	5.23	5.24	5.53	5.38	9	8.00
	10:37		Middle	3.0	28.00	28.00		8.27	8.27		31.60	31.60		79.9	79.2		5.24	5.20		5.40	5.36		7	
16/10/2017	10:32	Cloudy	Middle	3.0	28.20	28.20	28.20	8.04	8.04	8.04	32.45	32.45	32.45	103.2	102.1	102.6	6.72	6.68	6.68	7.54	7.54	7.56	6	5.50
	10:34		Middle	3.0	28.20	28.20		8.04	8.04		32.45	32.45		102.7	102.3		6.68	6.65		7.56	7.58		5	
18/10/2017	13:35	Fine	Middle	2.5	28.30	28.30	23.35	8.25	8.25	8.25	31.84	31.84	31.84	88.6	89.3	89.0	5.78	5.82	5.80	8.20	8.21	8.25	8	8.00
	13:37		Middle	2.5	28.40	8.40		8.25	8.25		31.83	31.83		88.9	89.0		5.79	5.80		8.28	8.29		8	
20/10/2017	14:20	Fine	Middle	3.0	27.10	27.10	27.10	8.27	8.27	8.27	31.98	31.98	31.98	86.7	86.7	86.9	5.76	5.77	5.78	7.15	7.13	7.16	5	5.00
	14:22		Middle	3.0	27.10	27.10		8.27	8.27		31.98	31.98		87.1	86.9		5.79	5.78		7.16	7.18		5	
23/10/2017	14:20	Fine	Middle	3.0	27.20	27.20	27.25	8.25	8.25	8.25	32.99	32.99	32.99	87.8	88.5	88.3	5.82	5.87	5.85	7.04	7.02	6.97	6	6.00
	14:22		Middle	3.0	27.30	27.30		8.25	8.25		32.99	32.99		88.1	88.6		5.84	5.87		6.93	6.90		6	
25/10/2017	4:16	Fine	Middle	2.5	24.60	24.60	24.60	8.26	8.26	8.26	32.79	32.79	32.79	84.0	82.9	83.9	5.81	5.73	5.80	6.31	6.40	6.35	7	6.50
	4:17		Middle	2.5	24.60	24.60		8.26	8.26		32.79	32.79		83.6	85.1		5.78	5.88		6.35	6.32		6	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P4 - SOC
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity			Suspended Solids	
			m		°C			-			ppt			%			mg/L			NTU			mg/L	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	11:55	Fine	Middle	2.5	29.80	29.80	29.80	7.89	7.89	7.90	30.06	30.06	30.06	95.1	94.9	94.7	6.11	6.10	6.09	5.76	5.77	5.75	6	7.00
	11:57		Middle	2.5	29.80	29.80		7.90	7.90		30.06	30.06		94.9	94.0		6.10	6.03		5.74	5.72		8	
5/10/2017	13:43	Cloudy	Middle	2.5	30.20	30.20	30.20	8.23	8.23	8.23	30.51	30.51	30.51	87.0	88.9	87.6	5.54	5.67	5.58	5.71	5.69	5.64	4	4.00
	13:44		Middle	2.5	30.20	30.20		8.23	8.23		30.51	30.51		86.7	87.6		5.53	5.59		5.61	5.55		4	
7/10/2017	11:05	Fine	Middle	3.0	29.20	29.20	29.20	7.96	7.96	7.97	31.03	31.03	31.03	96.7	97.5	97.1	6.25	6.30	6.27	7.66	7.62	7.65	13	14.00
	11:07		Middle	3.0	29.20	29.20		7.97	7.97		31.03	31.03		97.1	96.9		6.28	6.26		7.63	7.68		15	
9/10/2017	15:37	Fine	Middle	2.5	29.20	29.20	29.25	8.24	8.24	8.24	30.69	30.69	30.81	70.2	70.3	69.3	4.53	4.54	4.47	9.34	9.09	9.19	5	6.00
	15:39		Middle	2.5	29.30	29.30		8.24	8.24		30.93	30.93		68.6	68.2		4.42	4.40		9.08	9.25		7	
11/10/2017	21:49	Cloudy	Middle	3.0	29.00	29.00	29.00	8.24	8.24	8.24	31.70	31.70	31.70	85.9	87.6	86.5	5.74	5.85	5.77	7.92	7.94	7.91	14	11.50
	21:50		Middle	3.0	29.00	29.00		8.24	8.24		31.70	31.70		87.4	84.9		5.83	5.67		7.90	7.88		9	
14/10/2017	10:40	Cloudy	Middle	3.0	28.30	28.30	28.25	8.27	8.27	8.27	31.59	31.69	31.62	80.8	80.2	80.5	5.28	5.25	5.26	5.83	5.89	5.92	6	6.50
	10:42		Middle	3.0	28.20	28.20		8.27	8.27		31.60	31.60		80.3	80.5		5.25	5.26		5.98	5.99		7	
16/10/2017	10:28	Cloudy	Middle	3.0	28.30	28.30	28.30	8.05	8.05	8.05	32.44	32.44	32.44	102.5	102.4	101.8	6.66	6.66	6.61	7.54	7.54	7.55	6	5.50
	10:30		Middle	3.0	28.30	28.30		8.05	8.05		32.44	32.44		101.6	100.7		6.57	6.55		7.54	7.56		5	
18/10/2017	13:40	Fine	Middle	2.5	27.90	27.90	27.95	8.25	8.25	8.26	31.83	31.83	31.83	88.7	89.1	88.8	5.82	5.84	5.83	8.41	8.42	8.43	7	7.00
	13:42		Middle	2.5	28.00	28.00		8.26	8.26		31.83	31.83		88.7	88.8		5.82	5.83		8.43	8.46		7	
20/10/2017	14:25	Fine	Middle	3.0	27.30	27.30	27.25	8.27	8.27	8.27	31.95	31.95	31.96	86.1	86.6	86.1	5.71	5.74	5.71	7.18	7.18	7.18	6	6.00
	14:27		Middle	3.0	27.20	27.20		8.27	8.27		31.96	31.96		86.0	85.6		5.70	5.68		7.16	7.18		6	
23/10/2017	14:25	Fine	Middle	3.0	27.00	27.00	27.00	8.25	8.25	8.25	32.10	32.10	32.10	85.5	85.9	85.3	5.69	5.72	5.67	8.39	8.22	8.25	6	6.00
	14:27		Middle	3.0	27.00	27.00		8.25	8.25		32.10	32.10		84.1	85.5		5.59	5.69		8.20	8.19		6	
25/10/2017	4:21	Fine	Middle	2.5	24.80	24.80	24.80	8.24	8.24	8.24	32.77	32.77	32.77	87.9	89.8	88.7	6.05	6.16	6.10	11.05	11.02	11.08	8	7.50
	4:22		Middle	2.5	24.80	24.80		8.24	8.24		32.77	32.77		89.6	87.4		6.17	6.02		11.14	11.12		7	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at P5 - WCT / RT / IT
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth (m)		Water Temperature (°C)			pH (-)			Salinity (ppt)			DO Saturation (%)			DO (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	12:00	Fine	Middle	2.5	29.80	29.80	29.80	7.91	7.91	7.92	30.04	30.40	30.14	90.4	90.7	90.5	5.81	5.83	5.83	5.80	5.89	5.87	6	6.00
	12:07		Middle	2.5	29.80	29.80		7.92	7.92		30.05	30.05		90.1	90.8		5.82	5.84		5.89	5.89		6	
5/10/2017	13:49	Cloudy	Middle	2.5	30.50	30.50	30.50	8.22	8.22	8.22	30.63	30.63	30.63	85.4	85.1	86.3	5.41	5.45	5.48	6.98	6.94	6.97	5	5.00
	13:50		Middle	2.5	30.50	30.50		8.22	8.22		30.63	30.63		88.3	86.3		5.60	5.47		6.98	6.99		5	
7/10/2017	11:10	Fine	Middle	3.0	29.20	29.20	29.20	7.98	7.98	7.99	31.02	31.02	31.02	96.5	96.8	96.5	6.23	6.25	6.23	9.08	9.08	9.05	8	8.00
	11:12		Middle	3.0	29.20	29.20		7.99	7.99		31.02	31.02		96.2	96.5		6.21	6.23		9.07	8.97		8	
9/10/2017	15:41	Fine	Middle	2.5	29.30	29.40	29.38	8.24	8.24	8.24	30.94	30.94	30.96	72.9	72.1	72.6	4.69	4.64	4.67	11.66	11.65	11.47	7	7.00
	15:43		Middle	2.5	29.40	29.40		8.24	8.24		30.98	30.98		72.9	72.6		4.66	4.68		11.26	11.32		7	
11/10/2017	21:53	Cloudy	Middle	3.0	29.10	29.10	29.10	8.19	8.19	8.19	31.76	31.76	31.76	81.3	83.6	82.6	5.42	5.56	5.50	5.50	5.74	5.75	9	9.00
	21:54		Middle	3.0	29.10	29.10		8.19	8.19		31.76	31.76		82.9	82.6		5.52	5.50		5.96	5.80		9	
14/10/2017	10:45	Cloudy	Middle	3.0	28.20	28.20	28.15	8.27	8.27	8.27	31.59	31.59	31.59	82.3	84.7	84.0	5.39	5.55	5.50	6.41	6.59	6.50	4	5.00
	10:47		Middle	3.0	28.10	28.10		8.27	8.27		31.59	31.59		84.3	84.5		5.52	5.53		6.53	6.48		6	
16/10/2017	10:40	Cloudy	Middle	3.0	28.20	28.20	28.20	7.93	7.93	7.96	32.38	32.38	32.39	111.8	111.5	111.7	7.67	7.47	7.45	9.28	9.29	9.29	7	6.00
	10:42		Middle	3.0	28.20	28.20		7.98	7.98		32.39	32.39		112.9	110.5		7.35	7.29		9.29	9.29		5	
18/10/2017	13:45	Fine	Middle	2.5	27.90	27.90	27.90	8.25	8.25	8.25	31.82	31.82	31.82	88.8	89.0	89.1	5.83	5.85	5.85	7.74	7.77	7.81	7	8.00
	13:47		Middle	2.5	27.90	27.90		8.25	8.25		31.82	31.82		89.3	89.1		5.86	5.85		7.86	7.88		9	
20/10/2017	14:30	Fine	Middle	3.5	27.00	27.00	26.95	8.27	8.27	8.27	31.96	31.96	31.97	88.0	88.3	88.1	5.87	5.90	5.88	8.06	8.04	8.05	4	4.50
	14:32		Middle	3.5	26.90	26.90		8.27	8.27		31.98	31.98		87.3	88.8		5.82	5.92		8.05	8.05		5	
23/10/2017	14:30	Fine	Middle	3.0	27.00	27.00	27.00	8.25	8.25	8.25	32.15	32.15	32.15	87.2	87.5	87.3	5.81	5.83	5.81	7.67	7.65	7.65	7	6.50
	14:32		Middle	3.0	27.00	27.00		8.25	8.25		32.15	32.15		87.3	87.0		5.81	5.79		7.66	7.61		6	
25/10/2017	4:25	Fine	Middle	2.5	24.50	24.50	24.58	8.25	8.25	8.25	32.77	32.77	32.77	76.3	79.7	78.7	5.28	5.52	5.44	7.39	7.46	7.37	5	6.00
	4:26		Middle	2.5	24.50	24.80		8.25	8.25		32.77	32.77		79.1	79.6		5.46	5.51		7.34	7.28		7	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at RW21-P789 - GEC / CRB / SHK
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth (m)		Water Temperature (°C)			pH (-)			Salinity (ppt)			DO Saturation (%)			DO (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	10:00	Fine	Middle	3.5	30.40	30.40	30.50	7.48	7.48	7.55	30.64	30.64	30.64	88.1	87.7	88.6	5.58	5.55	5.61	4.81	4.81	4.81	7	7.00
	10:02		Middle	3.5	30.60	30.60		7.62	7.62		30.64	30.64		89.4	89.0		5.66	5.63		4.82	4.79		7	
5/10/2017	17:55	Cloudy	Middle	3.5	30.60	30.60	30.60	8.15	8.15	8.15	30.93	30.93	30.94	86.6	87.6	85.8	5.48	5.54	5.43	6.86	6.82	6.72	6	6.50
	17:57		Middle	3.5	30.60	30.60		8.15	8.15		30.94	30.94		84.9	83.9		5.37	5.31		6.62	6.57		7	
7/10/2017	11:30	Fine	Middle	3.5	29.70	29.70	29.70	7.97	7.97	7.99	31.17	31.17	31.17	98.6	98.6	98.2	6.30	6.30	6.28	7.41	7.41	7.41	6	6.00
	11:32		Middle	3.5	29.70	29.70		8.00	8.00		31.17	31.17		97.6	98.0		6.24	6.27		7.40	7.42		6	
9/10/2017	15:57	Fine	Middle	3.5	29.80	29.80	29.80	8.25	8.25	8.25	31.22	31.22	31.17	56.6	56.4	56.7	3.62	3.61	3.63	9.35	9.37	9.31	8	8.50
	15:59		Middle	3.5	29.80	29.80		8.25	8.25		31.12	31.12		56.9	56.9		3.64	3.64		9.27	9.26		9	
11/10/2017	21:20	Cloudy	Middle	4.0	29.60	29.60	29.65	8.03	8.03	8.04	31.83	31.83	31.83	84.9	86.9	86.1	5.42	5.54	5.49	6.22	6.42	6.28	7	8.00
	21:21		Middle	4.0	29.70	29.70		8.05	8.05		31.83	31.83		86.7	85.9		5.53	5.48		6.29	6.18		9	
14/10/2017	7:30	Cloudy	Middle	3.5	28.50	28.50	28.45	8.30	8.30	8.30	31.96	31.96	31.98	81.8	81.8	81.8	5.32	5.32	5.32	12.15	12.19	12.22	6	6.00
	7:32		Middle	3.5	28.40	28.40		8.29	8.29		31.99	31.99		81.9	81.7		5.33	5.32		12.24	12.28		6	
16/10/2017	11:26	Cloudy	Middle	3.0	28.30	28.30	28.30	8.00	8.00	8.02	32.28	32.28	32.28	108.3	110.1	108.2	7.14	7.16	7.07	6.65	6.48	6.54	6	6.00
	11:28		Middle	3.0	28.30	28.30		8.04	8.04		32.28	32.28		108.1	106.3		7.07	6.91		6.29	6.73		6	
18/10/2017	10:30	Fine	Middle	4.0	27.90	27.90	27.75	8.23	8.23	8.24	31.93	31.93	31.96	87.5	87.3	87.3	5.75	5.74	5.74	8.66	8.62	8.65	7	8.00
	10:32		Middle	4.0	27.60	27.60		8.24	8.24		31.99	31.99		87.0	87.4		5.73	5.75		8.65	8.66		9	
20/10/2017	11:00	Fine	Middle	4.0	28.00	28.00	28.10	8.27	8.27	8.27	32.13	32.13	32.12	82.7	82.7	82.5	5.40	5.40	5.39	10.20	10.21	10.21	10	9.00
	11:02		Middle	4.0	28.20	28.20		8.26	8.26		32.11	32.11		82.1	82.6		5.36	5.39		10.22	10.22		8	
23/10/2017	15:05	Fine	Middle	4.0	27.60	27.60	27.60	8.25	8.25	8.25	32.15	32.15	32.15	85.2	85.0	84.7	5.61	5.60	5.57	5.74	5.75	5.71	4	4.50
	15:07		Middle	4.0	27.60	27.60		8.25	8.25		32.15	32.15		84.6	84.1		5.57	5.51		5.69	5.67		5	
25/10/2017	3:50	Fine	Middle	3.5	24.60	24.60	24.55	8.16	8.16	8.16	31.66	31.66	31.66	90.1	92.1	91.0	6.27	6.42	6.33	3.23	3.09	3.09	6	5.00
	3:51		Middle	3.5	24.50	24.50		8.16	8.16		31.66	31.66		91.1	90.7		6.32	6.32		3.02	3.00		4	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at WSD19 - Sheung Wan
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth (m)		Water Temperature (°C)			pH (-)			Salinity (ppt)			DO Saturation (%)			DO (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)	
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value	Average
3/10/2017	11:10	Fine	Middle	3.5	30.30	30.30	30.35	7.76	7.76	7.78	79.37	29.37	41.87	98.5	99.2	98.6	6.29	6.34	6.30	4.02	4.00	3.97	5	5.00
	11:12		Middle	3.5	30.40	30.40		7.80	7.80		29.37	29.37		98.3	98.3		6.28	6.28		3.93	3.92		5	
5/10/2017	14:10	Cloudy	Middle	3.5	29.30	29.90	29.75	8.09	8.09	8.09	30.53	30.53	30.53	84.1	83.6	84.3	5.38	5.35	5.39	7.92	7.90	7.94	6	5.50
	14:11		Middle	3.5	29.90	29.90		8.09	8.09		30.53	30.53		85.5	83.9		5.47	5.37		7.98	7.95		5	
7/10/2017	13:30	Fine	Middle	4.0	29.60	29.60	29.60	7.46	7.46	7.46	30.89	30.89	30.90	103.5	104.1	103.6	6.65	6.68	6.66	12.05	12.09	12.12	13	13.50
	13:32		Middle	4.0	29.60	29.60		7.46	7.46		30.90	30.90		103.3	103.4		6.64	6.65		12.15	12.17		14	
9/10/2017	14:38	Fine	Middle	3.5	29.70	29.70	29.80	8.18	8.18	8.19	30.73	30.73	30.72	71.2	70.2	70.3	4.56	4.59	4.52	13.71	13.89	13.90	9	8.50
	14:40		Middle	3.5	29.90	29.90		8.19	8.19		30.71	30.71		70.9	68.7		4.53	4.39		13.98	14.02		8	
11/10/2017	22:15	Cloudy	Middle	4.0	29.90	29.90	29.90	8.05	8.05	8.05	31.81	31.81	31.81	89.8	88.5	88.9	5.61	5.54	5.56	7.82	7.77	7.62	7	7.50
	22:16		Middle	4.0	29.90	29.90		8.05	8.05		31.81	31.81		88.2	89.2		5.51	5.58		7.57	7.33		8	
14/10/2017	9:30	Cloudy	Middle	4.0	28.20	28.20	28.15	8.28	8.28	8.29	31.83	31.83	31.83	89.6	90.3	89.8	5.86	5.91	5.88	8.93	8.99	9.02	13	13.50
	9:32		Middle	4.0	28.10	28.10		8.29	8.29		31.82	31.82		90.2	89.2		5.90	5.84		9.08	9.09		14	
16/10/2017	9:02	Cloudy	Middle	3.0	27.40	27.40	27.30	8.15	8.15	8.15	32.41	32.41	32.43	100.8	101.2	99.8	6.67	6.70	6.64	10.82	10.82	10.81	11	11.00
	9:04		Middle	3.0	27.20	27.20		8.14	8.14		32.44	32.44		98.4	98.9		6.58	6.62		10.82	10.79		11	
18/10/2017	11:25	Fine	Middle	4.0	28.20	28.20	28.20	8.29	8.29	8.30	31.83	31.83	31.83	84.1	84.0	84.3	5.50	5.49	5.51	10.90	10.85	10.86	16	15.50
	11:27		Middle	4.0	28.20	28.20		8.30	8.30		31.82	31.82		84.4	84.5		5.52	5.53		10.84	10.83		15	
20/10/2017	12:45	Fine	Middle	3.5	28.10	28.10	28.10	8.21	8.21	8.22	31.80	31.80	31.80	87.8	87.8	87.5	5.75	5.75	5.73	8.35	8.35	8.33	6	6.00
	12:47		Middle	3.5	28.10	28.10		8.23	8.23		31.80	31.80		87.2	87.2		5.71	5.71		8.32	8.31		6	
23/10/2017	13:30	Fine	Middle	4.0	27.80	27.80	27.85	8.24	8.24	8.23	32.24	32.24	32.24	85.6	85.7	85.6	5.61	5.62	5.61	8.67	8.72	8.73	8	8.00
	13:32		Middle	4.0	27.90	27.90		8.22	8.22		32.23	32.23		85.4	85.6		5.60	5.61		8.76	8.77		8	
25/10/2017	4:52	Fine	Middle	3.5	24.90	24.90	24.90	8.16	8.16	8.16	32.71	32.71	32.71	86.7	87.8	87.2	5.97	6.04	6.00	7.70	7.75	7.74	7	6.00
	4:53		Middle	3.5	24.90	24.90		8.16	8.16		32.71	32.71		87.5	86.9		6.02	5.98		7.71	7.80		5	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C7 - Windsor House
Additional Monitoring

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO			Turbidity		
			m		°C			-			ppt			%			mg/L			NTU		
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average	Value		Average
8/10/2017	10:30	Fine	Middle	-	30.60	30.60	30.65	7.68	7.68	7.69	31.11	31.11	31.11	109.4	108.1	108.2	6.90	6.81	6.82	10.44	10.42	<u>10.42</u>
	10:32		Middle	-	30.70	30.70		7.69	7.69		31.11	31.11		107.0	108.4		6.75	6.83		10.41	10.41	
10/10/2017	14:35	Fine	Middle	-	31.40	31.40	31.50	8.14	8.14	8.14	30.91	30.91	30.91	86.5	84.9	86.2	5.38	5.28	5.36	5.50	5.51	5.52
	14:37		Middle	-	31.60	31.60		8.14	8.14		30.91	30.91		85.6	87.7		5.32	5.45		5.52	5.53	
26/10/2017	12:15	Fine	Middle	-	27.90	27.90	28.00	8.17	8.17	8.18	31.98	31.98	31.98	84.6	86.0	85.5	5.54	5.63	5.59	4.56	4.75	4.74
	12:17		Middle	-	28.10	28.10		8.18	8.18		31.98	31.98		85.8	85.5		5.61	5.59		4.83	4.82	

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Graphic Presentation of Water Quality Result of WSD19 - Sheung Wan







Graphic Presentation of Water Quality Result of C1 - HKCEC







Graphic Presentation of Water Quality Result of P1 - HKCEC Phase I







Graphic Presentation of Water Quality Result of P3 - APA







Graphic Presentation of Water Quality Result of P5 - WCT / RT / IT







Graphic Presentation of Water Quality Result of P4 - SOC







Graphic Presentation of Water Quality Result of RW21-P789 - GEC/CRC/SHK







Graphic Presentation of Water Quality Result of C7 - Windsor House







Water Monitoring Result at C6 - Excelsior Hotel
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO		
			m		°C			-			ppt			%			mg/L		
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average
28/9/2017	-	Fine	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	15:20		Middle	1.5	30.80	30.80	30.8	7.99	7.99	8.0	28.11	28.11	28.1	60.4	60.1	60.3	3.88	3.85	3.87
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
30/9/2017	-	Cloudy	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	15:00		Middle	1.5	29.90	29.90	29.9	7.67	7.67	7.7	28.19	28.19	28.2	80.2	79.7	80.0	5.20	5.13	5.17
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C6 - Excelsior Hotel
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO		
			m		℃			-			ppt			%			mg/L		
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average
28/9/2017	-	Fine	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	3:51		Middle	2	28.60	28.60	28.6	7.91	7.91	7.9	28.23	28.23	28.2	80.2	80.5	80.4	5.05	5.07	5.06
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
30/9/2017	-	Cloudy	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	9:45		Middle	2	28.90	28.90	28.9	7.27	7.27	7.3	28.24	28.24	28.2	63.7	63.8	63.8	4.20	4.21	4.21
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C6 - Excelsior Hotel
Mid-Flood Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO		
			m		°C			-			ppt			%			mg/L		
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average
3/10/2017	-	Fine	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	15:15		Middle	1.5	31.20	31.20	31.2	7.83	7.83	7.8	29.49	29.49	29.5	103.7	104.6	104.2	6.49	6.54	6.52
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5/10/2017	-	Cloudy	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	16:37		Middle	1.0	29.80	29.80	29.8	8.22	8.22	8.2	30.31	30.31	30.3	87.0	87.2	87.1	5.58	5.60	5.59
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
7/10/2017	-	Fine	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	17:17		Middle	1.0	29.00	29.00	29.0	8.09	8.09	8.1	30.35	30.35	30.4	85.6	85.7	85.7	5.55	5.56	5.56
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
9/10/2017	9:25	Fine	Surface	1.0	29.60	29.60	29.6	8.16	8.16	8.2	30.31	30.31	30.3	66.0	66.9	66.5	4.25	4.31	4.28
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	9:27		Bottom	3.0	29.20	29.20	29.2	8.17	8.17	8.2	30.14	30.14	30.1	74.0	74.5	74.3	4.79	4.83	4.81
11/10/2017	-	Fine	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	8:50		Middle	1.5	29.40	29.40	29.4	8.17	8.17	8.2	30.60	30.60	30.6	77.1	77.0	77.1	4.98	4.97	4.98
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
14/10/2017	-	Cloudy	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	12:35		Middle	1.5	28.30	28.30	28.3	8.19	8.19	8.2	30.63	30.63	30.6	68.7	68.5	68.6	4.51	4.50	4.51
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
16/10/2017	-	Cloudy	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	18:20		Middle	1.5	28.00	28.00	28.0	8.06	8.06	8.1	31.89	31.89	31.9	73.5	73.1	73.3	4.81	4.79	4.80
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
18/10/2017	16:45	Fine	Surface	1.0	28.40	28.40	28.4	8.21	8.21	8.2	30.43	30.43	30.4	77.3	77.2	77.3	5.03	5.02	5.03
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	16:47		Bottom	3.0	28.10	28.10	28.1	8.22	8.22	8.2	30.56	30.56	30.6	82.4	82.8	82.6	5.43	5.46	5.45
20/10/2017	16:45	Cloudy	Surface	1.0	27.50	27.50	27.5	8.23	8.23	8.2	31.12	31.12	31.1	77.6	77.6	77.6	5.15	5.15	5.15
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	16:47		Bottom	3.0	27.30	27.30	27.3	8.24	8.24	8.2	30.34	30.34	30.3	83.1	83.7	83.4	5.54	5.57	5.56
23/10/2017	7:50	Fine	Surface	1.0	26.40	26.40	26.4	8.25	8.25	8.3	31.73	31.73	31.7	76.3	76.8	76.6	5.15	5.19	5.17
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	7:52		Bottom	3.0	26.20	26.20	26.2	8.26	8.26	8.3	31.75	31.75	31.8	87.9	88.0	88.0	5.95	5.95	5.95
25/10/2017	10:55	Fine	Surface	1.0	26.60	26.60	26.6	8.23	8.23	8.2	31.86	31.86	31.9	85.4	85.3	85.4	5.73	5.73	5.73
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	10:57		Bottom	3.0	26.60	26.60	26.6	8.23	8.23	8.2	31.81	31.81	31.8	80.2	91.1	85.7	6.06	6.11	6.09

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Water Monitoring Result at C6 - Excelsior Hotel
Mid-Ebb Tide

Date	Time	Weater Condition	Sampling Depth		Water Temperature			pH			Salinity			DO Saturation			DO		
			m		°C			-			ppt			%			mg/L		
					Value		Average	Value		Average	Value		Average	Value		Average	Value		Average
3/10/2017	-	Fine	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	10:45		Middle	1.5	29.90	29.90	29.9	7.75	7.75	7.8	29.71	29.71	29.7	92.3	92.6	92.5	5.93	5.95	5.94
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5/10/2017	-	Cloudy	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	11:42		Middle	1.5	30.90	30.90	30.9	8.17	8.17	8.2	30.05	30.05	30.1	86.7	87.4	87.1	5.48	5.52	5.50
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
7/10/2017	11:55	Fine	Surface	1.0	29.70	29.70	29.7	7.95	7.95	8.0	30.95	30.95	31.0	101.8	101.6	101.7	6.53	6.52	6.53
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	11:57		Bottom	3.0	29.60	29.60	29.6	7.96	7.96	8.0	30.43	30.43	30.4	100.8	100.2	100.5	6.47	6.44	6.46
9/10/2017	13:50	Fine	Surface	1.0	30.10	30.10	30.1	8.21	8.21	8.2	30.84	30.84	30.8	82.9	82.4	82.7	5.26	5.23	5.25
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	13:52		Bottom	3.0	29.60	29.60	29.6	8.21	8.21	8.2	30.80	30.80	30.8	80.6	82.1	81.4	5.17	5.27	5.22
11/10/2017	-	Cloudy	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	20:59		Middle	1.5	30.30	30.30	30.3	8.17	8.17	8.2	31.43	31.43	31.4	82.9	82.3	82.6	5.17	5.13	5.15
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
14/10/2017	8:52	Cloudy	Surface	1.0	28.50	28.50	28.5	8.23	8.23	8.2	26.97	26.97	27.0	71.9	72.2	72.1	4.75	4.76	4.76
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	8:54		Bottom	3.0	28.00	28.00	28.0	8.22	8.22	8.2	30.11	30.11	30.1	85.0	84.5	84.8	5.59	5.56	5.58
16/10/2017	-	Cloudy	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	11:00		Middle	1.5	28.50	28.50	28.5	7.99	7.99	8.0	31.64	31.64	31.6	107.3	104.9	106.1	6.99	6.83	6.91
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
18/10/2017	10:45	Fine	Surface	1.0	28.20	28.20	28.2	8.28	8.28	8.3	31.02	31.02	31.0	76.6	76.1	76.4	5.03	5.00	5.02
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	10:47		Bottom	3.0	28.30	28.30	28.3	8.28	8.28	8.3	31.22	31.22	31.2	84.8	84.7	84.8	5.55	5.55	5.55
20/10/2017	11:40	Fine	Surface	1.0	27.70	27.70	27.7	8.23	8.23	8.2	31.43	31.43	31.4	76.5	77.4	77.0	5.05	5.10	5.08
	-		Middle	2.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	11:42		Bottom	3.0	27.50	27.50	27.5	8.23	8.23	8.2	31.59	31.59	31.6	85.8	86.0	85.9	5.68	5.69	5.69
23/10/2017	-	Fine	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	15:55		Middle	1.5	27.00	27.00	27.0	8.22	8.22	8.2	31.59	31.59	31.6	77.9	78.7	78.3	5.19	5.28	5.24
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
25/10/2017	-	Fine	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	2:05		Middle	1.5	24.70	24.70	24.7	8.21	8.21	8.2	31.89	31.89	31.9	81.1	82.6	81.9	5.62	5.73	5.68
	-		Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Remarks:
Single underline denotes exceedance over Action Level.
Double underline denotes exceedance over Limit Level.

Graphic Presentation of Enhanced Water Monitoring Results (DO) at C6 - Excelsior Hotel





Appendix 6.1

Event Action Plans

Event/Action Plan for Construction Noise

EVENT	ACTION			
	ET	**IEC**	**ER**	**CONTRACTOR**
Action Level being exceeded	1. Notify ER, IEC and Contractor; 2. Carry out investigation; 3. Report the results of investigation to the IEC, ER and Contractor; 4. Discuss with the IEC and Contractor on remedial measures required; 5. Increase monitoring frequency to check mitigation effectiveness. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Review the investigation results submitted by the ET; 2. Review the proposed remedial measures by the Contractor and advise the ER accordingly; 3. Advise the ER on the effectiveness of the proposed remedial measures. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. In consolidation with the IEC, agree with the Contractor on the remedial measures to be implemented; 4. Supervise the implementation of remedial measures. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Submit noise mitigation proposals to IEC and ER; 2. Implement noise mitigation proposals. (The above actions should be taken within 2 working days after the exceedance is identified)

EVENT	ACTION			
	ET	**IEC**	**ER**	**CONTRACTOR**
Limit Level being exceeded	1. Inform IEC, ER, Contractor and EPD; 2. Repeat measurements to confirm findings; 3. Increase monitoring frequency; 4. 4. Identify source and investigate the cause of exceedance; 5. 5. Carry out analysis of Contractor's working procedures; 6. 6. Discuss with the IEC, Contractor and ER on remedial measures required; 7. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results; 8. If exceedance stops, cease additional monitoring. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Discuss amongst ER, ET, and Contractor on the potential remedial actions; 2. Review Contractor's remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. In consolidation with the IEC, agree with the Contractor on the remedial measures to be implemented; 4. Supervise the implementation of remedial measures; 5. If exceedance continues, consider stopping the Contractor to continue working on that portion of work which causes the exceedance until the exceedance is abated. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IEC and ER within 3 working days of notification; 3. Implement the agreed proposals; 4. Submit further proposal if problem still not under control; 5. Stop the relevant portion of works as instructed by the ER until the exceedance is abated. (The above actions should be taken within 2 working days after the exceedance is identified)

Event / Action Plan for Construction Air Quality

EVENT	ACTION			
	ET	IEC	ER	CONTRACTOR
ACTION LEVEL				
1. Exceedance for one sample	1. Identify source, investigate the causes of exceedance and propose remedial measures; 2. Inform IEC and ER; 3. Repeat measurement to confirm finding; 4. Increase monitoring frequency to daily. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Check monitoring data submitted by ET; 2. Check Contractor's working method. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Notify Contractor. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Rectify any unacceptable practice; 2. Amend working methods if appropriate. (The above actions should be taken within 2 working days after the exceedance is identified)
2. Exceedance for two or more consecutive samples	1. Identify source; 2. Inform IEC and ER; 3. Advise the ER on the effectiveness of the proposed remedial measures; 4. Repeat measurements to confirm findings; 5. Increase monitoring frequency to daily; 6. Discuss with IEC and Contractor on remedial actions required; 7. If exceedance continues, arrange meeting with IEC and ER; 8. If exceedance stops, cease additional monitoring. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Check monitoring data submitted by ET; 2. Check Contractor's working method; 3. Discuss with ET and Contractor on possible remedial measures; 4. Advise the ET on the effectiveness of the proposed remedial measures; 5. Supervise Implementation of remedial measures. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Ensure remedial measures properly implemented. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Submit proposals for remedial to ER within 3 working days of notification; 2. Implement the agreed proposals; 3. Amend proposal if appropriate. (The above actions should be taken within 2 working days after the exceedance is identified)
LIMIT LEVEL				
1. Exceedance for one sample	1. Identify source, investigate the causes of exceedance and propose remedial measures; 2. Inform ER, Contractor and EPD; 3. Repeat measurement to confirm finding; 4. Increase monitoring frequency to daily; 5. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Check monitoring data submitted by ET; 2. Check Contractor's working method; 3. Discuss with ET and Contractor on possible remedial measures; 4. Advise the ER on the effectiveness of the proposed remedial measures; 5. Supervise implementation of remedial measures. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Ensure remedial measures properly implemented. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IEC within 3 working days of notification; 3. Implement the agreed proposals; 4. Amend proposal if appropriate. (The above actions should be taken within 2 working days after the exceedance is identified)
2. Exceedance for two or more consecutive samples	1. Notify IEC, ER, Contractor and EPD; 2. Identify source; 3. Repeat measurement to confirm findings; 4. Increase monitoring frequency to daily; 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented; 6. Arrange meeting with IEC and ER to discuss the remedial actions to be taken; 7. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results; 8. If exceedance stops, cease additional monitoring. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Discuss amongst ER, ET, and Contractor on the potential remedial actions; 2. Review Contractor's remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly; 3. Supervise the implementation of remedial measures.	1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. In consolidation with the IEC, agree with the Contractor on the remedial measures to be implemented; 4. Ensure remedial measures properly implemented; 5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated. (The above actions should be taken within 2 working days after the exceedance is identified)	1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IEC within 3 working days of notification; 3. Implement the agreed proposals; 4. Resubmit proposals if problem still not under control; 5. Stop the relevant portion of works as determined by the ER until the exceedance is abated. (The above actions should be taken within 2 working days after the exceedance is identified)

Event and Action Plan for Marine Water Quality

EVENT	ACTION			
	ET	IEC	ER	CONTRACTOR
Action level being exceeded by one sampling day	Repeat in-situ measurement to confirm findings; Identify source(s) of impact; Inform IEC and Contractor; Check monitoring data, all plant, equipment and Contractor's working methods; Discuss mitigation measures with IEC and Contractor; (The above actions should be taken within 1 working day after the exceedance is identified) Repeat measurement on next day of exceedance.	Discuss with ET and Contractor on the mitigation measures; Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; Assess the effectiveness of the implemented mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)	Discuss with IEC on the proposed mitigation measures; Make agreement on the mitigation measures to be implemented. (The above actions should be taken within 1 working day after the exceedance is identified)	Inform the ER and confirm notification of the non-compliance in writing; Rectify unacceptable practice; Check all plant and equipment; Consider changes of working methods; Discuss with ET and IEC and propose mitigation measures to IEC and ER; Implement the agreed mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)
Action level being exceeded by more than one consecutive sampling days	Identify source(s) of impact; Inform IEC and Contractor; Check monitoring data, all plant, equipment and Contractor's working methods; Discuss mitigation measures with IEC and Contractor; Ensure mitigation measures are implemented; Prepare to increase the monitoring frequency to daily; (The above actions should be taken within 1 working day after the exceedance is identified) Repeat measurement on next working day of exceedance.	Discuss with ET and Contractor on the mitigation measures; Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; Assess the effectiveness of the implemented mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)	Discuss with IEC on the proposed mitigation measures; Make agreement on the mitigation measures to be implemented; Assess the effectiveness of the implemented mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)	Inform the Engineer and confirm notification of the non-compliance in writing; Rectify unacceptable practice; Check all plant and equipment; Consider changes of working methods; Discuss with ET and IEC and propose mitigation measures to IEC and ER within 3 working days; Implement the agreed mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)

EVENT	ACTION			
	ET	**IEC**	**ER**	**CONTRACTOR**
Limit level being exceeded by one sampling day	Repeat in-situ measurement to confirm findings; Identify source(s) of impact; Inform IEC, contractor and EPD; Check monitoring data, all plant, equipment and Contractor's working methods; Discuss mitigation measures with IEC, ER and Contractor; Ensure mitigation measures are implemented; Increase the monitoring frequency to daily until no exceedance of Limit level. (The above actions should be taken within 1 working day after the exceedance is identified)	Discuss with ET and Contractor on the mitigation measures; Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; Assess the effectiveness of the implemented mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)	Discuss with IEC, ET and Contractor on the proposed mitigation measures; Request Contractor to critically review the working methods; Make agreement on the mitigation measures to be implemented; Assess the effectiveness of the implemented mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)	Inform the Engineer and confirm notification of the non-compliance in writing; Rectify unacceptable practice; Check all plant and equipment; Consider changes of working methods; Discuss with ET , IEC and ER and propose mitigation measures to IEC and ER within 3 working days; Implement the agreed mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)
Limit level being exceeded by more than one consecutive sampling days	Identify source(s) of impact; Inform IEC, contractor and EPD; Check monitoring data, all plant, equipment and Contractor's working methods; Discuss mitigation measures with IEC, ER and Contractor; Ensure mitigation measures are implemented; Increase the monitoring frequency to daily until no exceedance of Limit level for two consecutive days. (The above actions should be taken within 1 working day after the exceedance is identified)	Discuss with ET and Contractor on the mitigation measures; Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; Assess the effectiveness of the implemented mitigation measures. (The above actions should be taken within 1 working day after the exceedance is identified)	Discuss with IEC, ET and Contractor on the proposed mitigation measures; Request Contractor to critically review the working methods; Make agreement on the mitigation measures to be implemented; Assess the effectiveness of the implemented mitigation measures; Consider and instruct, if necessary, the Contractor to slow down or to stop all or part of the marine work until no exceedance of Limit level. (The above actions should be taken within 1 working day after the exceedance is identified)	Inform the ER and confirm notification of the non-compliance in writing; Rectify unacceptable practice; Check all plant and equipment; Consider changes of working methods; Discuss with ET, IEC and ER and propose mitigation measures to IEC and ER within 3working days; Implement the agreed mitigation measures; As directed by the Engineer, to slow down or to stop all or part of the marine work or construction activities. (The above actions should be taken within 1 working day after the exceedance is identified)

Event and Action Plan for Odour Patrol

Event	ACTION	
	Person-in-charge of Odour Monitoring	**Implementation Agent Identified by CEDD**
Action Level		
Exceedance of Action Level	1. Identify source/reason of exceedance; 2. Repeat odour patrol to confirm finding.	1. Carry out investigation to identify the source/reason of exceedance; 2. Rectify any unacceptable practice 3. Implement more mitigation measures if necessary; 4. Inform EPD or MD if exceedance is considered to be caused by expedient connections or floating debris.
Limit Level		
Exceedance of Limit Level	1. Identify source / reason of exceedance; 2. Repeat odour patrol to confirm findings; 3. Increase odour patrol frequency; 4. If exceedance stops, cease additional odour patrol.	1. Carry out investigation to identify the source/reason of exceedance. Investigation shall be completed within 2 weeks; 2. Rectify any unacceptable practice; 3. Formulate remedial actions; 4. Ensure remedial actions properly implemented; 5. If exceedance continues, consider what more/enhanced mitigation measures shall be implemented; 6. Inform EPD or MD if exceedance is considered to be caused by expedient connections or floating debris.

Appendix 6.2

Summary for Notification of Exceedance

Ref. No.	Date	Time	Location	Measured TSP Level	Unit	Action Level	Limit Level	Follow-up action	
X_16A057	26-Oct-17	13:00	CMA1b - Harbour Grand Hotel Boundary Wall	**821.6**	1hr TSP (ug/m^3)	320.1	500	**Possible reason:**	Elevated TSP level potentially in relate to non-construction activities vehicle exhaust around the monitoring station.
								Action taken / to be taken:	Reviewed the trend of air quality measurement across monitoring stations. Analysis of contractor's working procedures.
								Remarks / Other Obs:	Despite excavation, breaking works and pile head trimming works were undertaken around the monitoring location on the monitoring date at the under Contractor of HY/2009/19, dust mitigation measure including water spraying for breaking works and haul road were generally implemented by the Contractor. Meanwhile, it was observed that vehicle exhaust from non-construction works was observed as the major factor affecting the monitoring station during monitoring period. In view of the above, the exceedance was considered as non-Project related.
X_16A059	26-Oct-17	17:00	CMA5b- Pedestrian Plaza	**485.5**	1hr TSP (ug/m^3)	332.0	500	**Possible reason:**	TSP level potentially in relate to the ambient condition around the monitoring station.
								Action taken / to be taken:	Reviewed the trend of air quality measurement across monitoring stations. Analysis of contractor's working procedures.
								Remarks / Other Obs:	No construction works was undertaken around the monitoring location on the monitoring date under Contractor of HK/2009/01 and no particular observation regarding air quality impact was observed during sampling. Nevertheless, non WDII-CWB Project construction activities was observed opposite to the monitoring station on the monitoring date. Meanwhile, it was noted that the EPD AQHI for Causeway Bay District was recorded as level 7 during the monitoring period, indicating a high level of air pollution in the area affecting the ambient air quality condition. In view of the above, the exceedance was considered to be non-project related and generally contributed by ambient air quality condition. Nevertheless, the Contractor of HK/2009/01 was reminded to provide dust suppression measures for any potential dusty surface and dust generating operation if required around the concerned location to avoid any potential cumulative air quality impact.
X_16A060	26-Oct-17	17:00	CMA5b- Pedestrian Plaza	**485.5**	1hr TSP (ug/m^3)	332.0	500	**Possible reason:**	TSP level potentially in relate to the ambient condition around the monitoring station.
								Action taken / to be taken:	Reviewed the trend of air quality measurement across monitoring stations. Analysis of contractor's working procedures.
								Remarks / Other Obs:	Road and drains works was undertaken under Contract HK/2012/08 around the monitoring location on the monitoring date and no particular observation regarding air quality impact was observed during sampling. Nevertheless, non WDII-CWB Project construction activities was observed opposite to the monitoring station on the monitoring date and dust mitigation including water spraying for haul raod was generally implemented. Meanwhile, it was noted that the EPD AQHI for Causeway Bay District was recorded as Level 7 during the monitoring period, indicating a high level of air pollution in the area affecting the ambient condition. In view of the above, the exceedance was considered to be non-project related and potentially contributed by ambient air quality condition. Nevertheless, the Contractor of HK/212/08 was reminded to provided regularly dust suppression measures if any potential dust generating operation around the concerned location would be required to avoid any potential cumulative air quality impact.

Lam Geotechnics Limited

Ref no.	Date	Tidal	Location	Parameters	Measured	Action Level	Limit	Follow-up action	
X_16W094	3-Oct-17	Mid-flood	WSD19	DO(mg/l)	5.74	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	**9.00**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	11.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 5 October 2017 ebb tide.
X_16W095	7-Oct-17	Mid-ebb	WSD19	DO(mg/l)	6.66	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**12.12**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	**13.50**	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station WSD19 during the monitoring period. In view of the above, it is considered that the turbidity and suspended solid exceedances were not related to Project works.
X_16W096	7-Oct-17	Mid-flood	WSD19	DO(mg/l)	5.69	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**13.30**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	**14.50**	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of the above, it is considered that the turbidity and suspended solid exceedances were not related to Project works.
X_16W097	9-Oct-17	Mid-flood	WSD19	DO(mg/l)	**3.30**	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**15.12**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	**17.00**	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of the above, it is considered that the DO, turbidity and suspended solid exceedances were not related to Project works.

Lam Geotechnics Limited

Ref no.	Date	Tidal	Location	Parameters	Measured	Action Level	Limit	Follow-up action	
X_16W098	9-Oct-17	Mid-flood	RW21-P789	DO(mg/l)	4.50	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**12.85**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	7.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above, it is considered that the exceedance was not related to Project works.
X_16W099	9-Oct-17	Mid-ebb	WSD19	DO(mg/l)	4.52	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**13.90**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.50	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station WSD19 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works.
X_16W100	9-Oct-17	Mid-ebb	RW21-P789	DO(mg/l)	**3.63**	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	**9.31**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.50	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above and considering transition period from wet season to dry season, it is considered that the DO and turbidity exceedances were not related to Project works.
X_16W101	11-Oct-17	Mid-flood	WSD19	DO(mg/l)	5.36	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**12.23**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	**14.50**	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the turbidity and suspended solid exceedances were not related to Project works. No exceedance was recorded in the subsequent monitoring on 11 October 2017 ebb tide.

Lam Geotechnics Limited

Ref no.	Date	Tidal	Location	Parameters	Measured	Action Level	Limit	Follow-up action	
X_16W101	11-Oct-17	Mid-flood	RW21-P789	DO(mg/l)	5.26	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**11.12**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	**14.50**	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above, it is considered that the turbidity and suspended solid exceedances were not related to Project works.
X_16W102	14-Oct-17	Mid-ebb	WSD19	DO(mg/l)	5.88	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	**9.02**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	**13.50**	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station WSD19 during the monitoring period. In view of no construction activities conducted and considering transition from wet season to dry season, it is considered that the turbidity and suspended solid exceedances were not related to Project works.
X_16W103	14-Oct-17	Mid-ebb	RW21-P789	DO(mg/l)	5.32	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**12.22**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	6.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above, it is considered that the exceedance was not related to Project works.
X_16W104	14-Oct-17	Mid-flood	WSD19	DO(mg/l)	5.30	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**11.01**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	11.50	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to Project works.

Ref no.	Date	Tidal	Location	Parameters	Measured	Action Level	Limit	Follow-up action	
X_16W105	16-Oct-17	Mid-ebb	WSD19	DO(mg/l)	6.64	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**10.81**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	11.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station WSD19 during the monitoring period. In view of no construction activities conducted, it is considered that the exceedance was not related to Project works.
X_16W106	16-Oct-17	Mid-flood	WSD19	DO(mg/l)	7.43	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**10.58**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	9.50	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to Project works.
X_16W107	16-Oct-17	Mid-flood	RW21-789	DO(mg/l)	6.57	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	**8.93**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.50	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above and considering transition period from wet season to dry season, it is considered that the exceedance was not related to Project works.
X_16W108	18-Oct-17	Mid-ebb	WSD19	DO(mg/l)	5.51	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**10.86**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	**15.50**	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station WSD19 during the monitoring period. In view of no construction activities conducted, it is considered that the turbidity and suspended solid exceedances were not related to Project works. No exceedance was recorded in the subsequent monitoring on 18 October 2017 flood tide.

Lam Geotechnics Limited

Ref no.	Date	Tidal	Location	Parameters	Measured	Action Level	Limit	Follow-up action	
X_16W109	18-Oct-17	Mid-ebb	RW21-P789	DO(mg/l)	5.74	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	**8.65**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above and considering transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 18 October 2017 flood tide.
X_16W110	20-Oct-17	Mid-ebb	WSD19	DO(mg/l)	5.73	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	**8.33**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	6.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station WSD19 during the monitoring period. In view of no construction activity and considering transition period from wet season to dry season, it is considered the exceedance was not related to Project work. No exceedance was recorded in the subsequent monitoring on 20 October 2017 flood tide.
X_16W111	20-Oct-17	Mid-ebb	RW21-P789	DO(mg/l)	5.39	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**10.21**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	9.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 20 October 2017 flood tide.
X_16W112	23-Oct-17	Mid-flood	RW21-P789	DO(mg/l)	5.56	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**11.40**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	10.50	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 23 October 2017 ebb tide.

Lam Geotechnics Limited

Ref no.	Date	Tidal	Location	Parameters	Measured	Action Level	Limit	Follow-up action	
X_16W113	23-Oct-17	Mid-ebb	WSD19	DO(mg/l)	5.61	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	**8.73**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station WSD19 during the monitoring period. In view of no construction activity and considering transition period from wet season to dry season, it is considered the exceedance was not related to Project work. No exceedance was recorded in the subsequent monitoring on 25 October 2017 ebb tide.
X_16W114	25-Oct-17	Mid-flood	WSD19	DO(mg/l)	6.01	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	**9.52**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	7.00	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of no construction activity and considering transition period from wet season to dry season, it is considered the exceedance was not related to Project work. No exceedance was recorded in the subsequent monitoring on 27 October 2017 ebb tide.
X_16W115	25-Oct-17	Mid-flood	RW21-P789	DO(mg/l)	5.56	3.66	3.28	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	**10.91**	8.04	9.49	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	7.50	13.00	14.43	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date, and the installed silt screen was observed generally in order. In view of the above, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 27 October 2017 ebb tide.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C096	7-Oct-17	Mid-ebb	C7	DO(mg/L)	6.28	3.36	2.73	Possible reason:	Muddy dispersion originated from underwater diaphragm wall cleaning works adjacent to monitoring location was identified during monitoring and incomplete installed Silt Screen for Windsor House Water Intake were considered as the major factors to the affected water quality.
				Turbidity (NTU)	10.05	9.10	10.25		
				SS (mg/L)	8.00	15.00	22.13		
	7-Oct-17	Mid-flood	C7	DO(mg/L)	5.47	3.36	2.73	Action taken/ to be taken:	Immediate repeat in-situ measurement to confirm the exceedances. The Contractor of HY/2010/08 was immediately advised to take remedial action to rectify the defects identified
				Turbidity (NTU)	40.75	9.10	10.25		
				SS (mg/L)	43.00	15.00	22.13		Water quality monitoring was conducted on **07 October 2017 during ebb tide at 1205hrs** and **action level exceedance of Turbidity (10.05 NTU)** was recorded. Subsequent monitoring was conducted on **07 October 2017 during flood tide at 1700hrs** and **limit level exceedances of Turbidity (40.75NTU)** and **Suspended Solid (43.00mg/L)** were subsequently recorded.
	9-Oct-17	Mid-flood	C7	DO(mg/L)	5.44	3.36	2.73		
				Turbidity (NTU)	9.79	9.10	10.25		Additional monitoring in accordance with the Event and Action Plan was conducted on **08 October 2017** and l**imit level exceedance of Turbidity (10.42 NTU)** was recorded.
				SS (mg/L)	9.50	15.00	22.13		
	9-Oct-17	Mid-ebb	C7	DO(mg/L)	4.40	3.36	2.73		Water quality monitoring was conducted on subsequent sampling date on **09 October 2017 during flood tide at 0935hrs** and **action level exceedance of Turbidity (9.79NTU)** was recorded. Meanwhile**, no further Suspended Solid exceedance** was recorded on 09 October 2017 during flood tide at 0935hrs.
				Turbidity (NTU)	12.86	9.10	10.25		
				SS (mg/L)	9.50	15.00	22.13		Water quality monitoring was subsequently conducted on **09 October 2017 during ebb tide at 1357hrs** and **limit level exceedance of Turbidity (12.86NTU)** was recorded.
									Additional monitoring in accordance with the Event and Action Plan was conducted on **10 October 2017** and **no further Turbidity exceedance** was recorded.
									Upon **identification of defects on 07 October 2017**, rectification measures including **reinstatement of the silt screen** installed for Windsor House Water Intake ; **cleaning of water holding tank**, and **provide mitigation measures including impermeable barrier around underwater cleaning works area**, as appropriate under the Contractor HY/2010/08 were **implemented by 11 October 2017**.
								Remarks/ Other Obs:	Water Quality Monitoring was conducted on 07 October 2017 during ebb tide and flood tide, and **action level exceedance of Turbidity was recorded on 07 October 2017 ebb tide** and **limit level exceedance of Turbidity and Suspended Solid was recorded on 07 October 2017 flood tide**. Underwater diaphragm wall cleaning works was conducted adjacent to the monitoring location on the monitoring date and the works was considered as the major contribute to the affected water quality. Meanwhile, the installed Silt Screen for Windsor House Water Intake was found incomplete according to the submitted Silt Screen Deployment Plan. Hence, the exceedances recorded were considered as **Project related**.
									Additional monitoring in accordance with the Event and Action Plan was conducted on **08 October 2017**, **limit level exceedance of Turbidity** was recorded. No underwater works was observed at the concerned location while the silt screen was remain defective.
									Subsequently, water quality monitoring was conducted on the next sampling date on **09 October 2017 during flood tide** and **action level exceedance of Turbidity** was recorded while **no further Suspended Solid exceedance** was recorded during the same monitoring tide. However, underwater diaphragm wall cleaning works with muddy dispersion adjacent to monitoring location was observed on-going with defective silt screen conducted on 09 October 2017 during flood tide and the exceedances was therefore considered as **Project related**.
									At subsequent water quality monitoring on **09 October 2017 during ebb tide**, **limit level exceedance of Turbidity** was recorded. Underwater diaphragm wall cleaning works with muddy dispersion adjacent to monitoring location was observed while the silt screen was remain defective conducted on 09 October 2017 during ebb tide and the exceedances was therefore considered as **Project related**. The Contractor of HY/2010/08 was advised to **implement proper rectification prior to conducting further underwater cleaning works** to avoid further water quality impact.
									Additional monitoring in accordance with the Event and Action Plan was conducted on **10 October 2017 and no further Turbidity exceedance was recorded**. No further underwater cleaning works was observed during monitoring sampling on 10 October 2017 while the silt screen was observed remained to be
									On **11 October 2017,** rectification measures including **reinstatement of the silt screen** installed for Windsor House Water Intake; **cleaning of water holding tank**, and provide **mitigation measures including impermeable barrier around underwater cleaning works area**, as appropriate, were implemented under the Contractor HY/2010/08. The Contractor was reminded to maintain regular checking and maintenance for silt screen installed and the water holding tank to avoid potential water quality impact.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C097	3-Oct-17	Mid-flood	C1	DO(mg/l)	4.77	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	13.68	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	14.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/02 project works. No exceedance was recorded in the subsequent monitoring on 5 October 2017 ebb tide.
X_16C098	3-Oct-17	Mid-flood	P4	DO(mg/l)	4.83	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	13.62	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	16.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P4 during the monitoring period. In view of the above, it is considered that the turbidity and suspended solid exceedances were not related to Project works. No exceedance was recorded in the subsequent monitoring on 5 October 2017 ebb tide.
X_16C099	3-Oct-17	Mid-flood	P5	DO(mg/l)	4.81	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	12.18	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	12.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P5 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 5 October 2017 ebb tide.
X_16C100	5-Oct-17	Mid-flood	C1	DO(mg/l)	5.71	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	11.63	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	11.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/02 project works. No exceedance was recorded in the subsequent monitoring on 7 October 2017 ebb tide.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C101	5-Oct-17	Mid-flood	P4	DO(mg/l)	5.73	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	10.54	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P4 during the monitoring period. In view of the above and considering transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 7 October 2017 ebb tide.
X_16C102	7-Oct-17	Mid-flood	C1	DO(mg/l)	5.40	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	13.99	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	9.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/02 project works.
X_16C103	7-Oct-17	Mid-flood	P5	DO(mg/l)	5.76	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.47	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	6.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P5 during the monitoring period. In view of the above and considering transition period from wet season to dry season, it is considered that the exceedance was not related to Project works.
X_16C104	9-Oct-17	Mid-flood	C1	DO(mg/l)	4.49	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.95	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	6.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/02 project works.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C105	9-Oct-17	Mid-flood	P1	DO(mg/l)	3.92	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	15.58	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P1 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works.
X_16C106	9-Oct-17	Mid-flood	P3	DO(mg/l)	4.41	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	11.38	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P3 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works.
X_16C107	9-Oct-17	Mid-flood	P4	DO(mg/l)	4.88	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.65	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	6.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P4 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works.
X_16C108	9-Oct-17	Mid-flood	P5	DO(mg/l)	4.65	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	10.12	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	6.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P5 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C109	9-Oct-17	Mid-ebb	C1	DO(mg/l)	3.81	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.35	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/02 project works.
X_16C110	9-Oct-17	Mid-ebb	P4	DO(mg/l)	4.47	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.19	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	6.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of no construction activity conducted and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works.
X_16C111	9-Oct-17	Mid-ebb	P5	DO(mg/l)	4.67	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	11.47	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	7.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of no construction activity conducted, it is considered that the exceedance was not related to Project works.
X_16C112	11-Oct-17	Mid-flood	C1	DO(mg/l)	5.59	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	13.40	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	14.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/02 project works. No exceedance was recorded in the subsequent monitoring on 11 October 2017 ebb tide.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C113	11-Oct-17	Mid-flood	P3	DO(mg/l)	5.03	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	11.49	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	12.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P3 during monitoring period. In view of no construction activity conducted, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 11 October 2017 ebb tide.
X_16C114	11-Oct-17	Mid-flood	P4	DO(mg/l)	5.37	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	15.17	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	18.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P4 during monitoring period. In view of no construction activity conducted, it is considered that the turbidity and suspended solid exceedances were not related to Project works. No exceedance was recorded in the subsequent monitoring on 11 October 2017 ebb tide.
X_16C115	11-Oct-17	Mid-flood	P5	DO(mg/l)	5.19	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	13.74	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	14.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P5 during monitoring period. In view of no construction activity conducted, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 11 October 2017 ebb tide.
X_16C116	14-Oct-17	Mid-flood	C1	DO(mg/l)	5.63	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	10.86	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	11.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/02 project works.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C117	14-Oct-17	Mid-flood	P3	DO(mg/l)	5.48	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.79	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	7.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P3 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 16 October 2017 ebb tide.
X_16C118	14-Oct-17	Mid-flood	P4	DO(mg/l)	5.58	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	11.38	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	10.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P4 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 16 October 2017 ebb tide.
X_16C119	14-Oct-17	Mid-flood	P5	DO(mg/l)	5.54	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	13.31	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	12.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P5 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works.
X_16C120	16-Oct-17	Mid-ebb	P5	DO(mg/l)	7.45	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.29	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	6.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of the above and considering transition period from wet season to dry season, it is considered that the exceedance was not related to Project works.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C121	16-Oct-17	Mid-flood	C1	DO(mg/l)	6.37	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	11.49	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	10.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted, it is considered that the exceedance was not related to HK/2009/02 project works.
X_16C122	16-Oct-17	Mid-flood	P1	DO(mg/l)	6.64	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.72	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	5.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P1 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 18 October 2017 ebb tide.
X_16C123	16-Oct-17	Mid-flood	P3	DO(mg/l)	6.60	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.69	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	9.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P3 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 18 October 2017 ebb tide.
X_16C124	16-Oct-17	Mid-flood	P4	DO(mg/l)	6.57	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	13.11	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	12.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P4 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 18 October 2017 ebb tide.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C125	16-Oct-17	Mid-flood	P5	DO(mg/l)	6.45	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	11.48	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	10.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P5 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 18 October 2017 ebb tide.
X_16C126	23-Oct-17	Mid-flood	C1	DO(mg/l)	5.61	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	10.36	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/02 project works. No exceedance was recorded in the subsequent monitoring on 23 October 2017 ebb tide.
X_16C127	23-Oct-17	Mid-flood	P4	DO(mg/l)	5.78	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.90	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	11.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P4 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 23 October 2017 ebb tide.
X_16C128	23-Oct-17	Mid-flood	P5	DO(mg/l)	5.66	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	9.72	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P5 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 23 October 2017 ebb tide.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C129	25-Oct-17	Mid-ebb	P4	DO(mg/l)	6.10	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	11.08	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	7.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. In view of no construction activities conducted and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works.
X_16C130	25-Oct-17	Mid-flood	C1	DO(mg/l)	5.60	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	10.01	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2009/01 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/01 project works. No marine construction activity under Contract HK/2009/02 was conducted on the monitoring date. In view of no construction activities conducted and considering transition period from wet season to dry season, it is considered that the exceedance was not related to HK/2009/02 project works. No exceedance was recorded in the subsequent monitoring on 27 October 2017 ebb tide.
X_16C131	25-Oct-17	Mid-flood	P1	DO(mg/l)	5.70	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	11.39	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	8.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P1 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 27 October 2017 ebb tide.
X_16C132	25-Oct-17	Mid-flood	P3	DO(mg/l)	5.63	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	10.65	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	7.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P3 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 27 October 2017 ebb tide.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C133	25-Oct-17	Mid-flood	P4	DO(mg/l)	5.74	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station.
				Turbidity	15.42	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	13.50	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P4 during the monitoring period. In view of the above, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 27 October 2017 ebb tide.
X_16C134	25-Oct-17	Mid-flood	P5	DO(mg/l)	5.50	3.36	2.73	Possible reason:	Natural variation or changes of water quality in the vicinity of water quality monitoring station. Transition of action and limit level from wet season.
				Turbidity	10.82	9.10	10.25	Action taken/ to be taken:	Immediate repeated in-situ measurement to confirm the exceedances. Checked with Contractor works and reviewed previous monitoring data.
				SS	9.00	15.00	22.13	Remarks/ Other Obs:	No marine construction activity under Contract HK/2012/08 was conducted on the monitoring date. Location of construction site area was at downstream of monitoring station P5 during the monitoring period. In view of the above and considering the transition period from wet season to dry season, it is considered that the exceedance was not related to Project works. No exceedance was recorded in the subsequent monitoring on 27 October 2017 ebb tide.

Ref no.	Date	Tidal	Location	Parameters (Unit)	Measured	Action Level	Limit Level	Follow-up action	
X_16C135	25-Oct-17	Mid-flood	C7	DO(mg/l)	5.85	3.36	2.73	Possible reason:	Underwater diaphragm wall cleaning work adjacent to monitoring location was observed during monitoring while impermeable barrier deployed was not fully enclosing the works area and considered as the major factor affecting the water quality at the time of sampling.
				Turbidity	17.76	9.10	10.25	Action taken/ to be taken:	Immediate repeat in-situ measurement to confirm the exceedance. The water turbidity level of repeated measurement at the same monitoring location on the same date and tide was: 25 October 2017 flood tide 17.39 NTU. The Contractor of HY/2010/08 was immediately advised to take remedial action to rectify the defects observed. Additional monitoring in accordance with the Event and Action Plan was conducted on 26 October 2017, no further turbidity exceedance was recorded: 26 October 2017 4.74NTU.
				SS	8.50	15.00	22.13		Rectification measures including i) maintained deployed impermeable barriers without openings, and ii) flushing at the affected water holding tank were implemented under the Contractor of HY/2010/08 by 26 October 2017.
								Remarks/ Other Obs:	Underwater diaphragm wall cleaning work was conducted adjacent to the monitoring location under Contract HY/2010/08 during the monitoring period on 25 October 2017 while impermeable barrier deployed was not fully enclosing the works area and affecting the water quality at the concerned Windsor House cooling water intake during monitoring sampling. As such, it was considered that the turbidity exceedance was related to HY/2010/08 Project works. Additional monitoring in accordance with the Event and Action Plan was conducted on 26 October 2017, no further turbidity exceedance was recorded: 26 October 2017 4.74NTU. Rectification measures including i) maintained deployed impermeable barriers without openings, and ii) flushing at the affected water holding tank were implemented under the Contractor of HY/2010/08 by 26 October 2017. Nevertheless, the Contractor is reminded to conduct regular checking of impermeable barrier or silt curtain deployed to ensure the mitigation measures are maintained without opening and fully extended to seabed level to safeguard the water quality and nearby water intakes.

Appendix 9.1

Complaint Log

Environmental Complaints Log

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
100321a	21/3/2010	ICC Case no. 1-224618029, Ms. Tsang	Location near Tin Hau	Complaint regarding the loud noise and dark smoke in the course of dredging works on 21 March 2010 (Sunday).	1) A valid Construction Noise Permit no. GW-RS0119-10 was granted from EPD since 18th Feb. 2010 for the dredging works which carry out at area for North Point Reclamation. 2) Officer from Marine Department, Police and EPD's officer attended the scene for inspection and investigation. 3) The Contractor (CHEC-CRBC JV) strictly comply all the conditions in CNP and take all mitigation measures in order to minimize the potential impacts to surrounding sensitive receivers. A formal letter was issued out by CHEC-CRBC JV and to explain the status of the recent construction activities. 4) No limit level exceedance was recorded on the noise measurement during day time and evening time noise measurement on 23 March 2010. Additional restrict hours noise monitoring at Causeway Bay Community and City Garden was conducted on 5 April 2010 (Public Holiday). No limit level exceedance was recorded in the monitoring. 5) No further complaints were received from Mr. Tsang in the reporting month. The complaint is considered closed.	Closed
100321b	21/3/2010	Unknown	Near the eastern breakwater of the Causeway Bay Typhoon Shelter	A public complaint and enquiry regarding loud noises emanated from dredging activities on 21/3/2010 (Sunday) until 2220 hours and between 1920-1946 hours in the evening of 22 March 2010(Monday).	1) A valid Construction Noise Permit no. GW-RS0119-10 was granted from EPD since 18th Feb. 2010 for the dredging works at area for North Point Reclamation during general holidays including Sunday between 0700-2300 hours and any day not being a general holiday between 1900-2300hours. It is complied with the condition of CNP. 2) Officer from Marine Department, Police and EPD's officer attended the scene for inspection and investigation. 3) No limit level exceedance was recorded on the noise measurement during day time and evening time noise measurement on 23 March 2010. Additional restrict hours noise monitoring at Causeway Bay Community and City Garden was conducted on 5 April 2010 (Public Holiday). No limit level exceedance was recorded in the monitoring. 4) No further complaints were received in the reporting month. The complaint is considered closed.	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
100504	4/5/2010	Public complainant received by ICC (ICC case: 1-233384048)	Watson Road	Complaint on the noise nuisance due to the large scale of dredging machine (face to Island East Corridor) in particular the hours 1900 to 0800 and request to reduce the noise level.	1) Contractor for HY/2009/11 was granted valid Construction Noise Permit no. GW-RS0119-10 for their dredging works. Contractor has implemented mitigation measures to reduce the working hour not later than 2230. 2) According to RSS 's record, no more daytime and night time dredging since the departure of the split hopper barge from the workplace on 29 April 2010 at 1900 hrs to 5 May 2010. 3) No further complaints were received in the reporting month. The complaint is considered closed.	Closed
100731	31/7/2010	Mr. Lee received by ICC (CC Case: 1-250702681)	Oil Street to Watson Road	Complaint on the noise nuisance due to the dredging works. Three construction plants were operated concurrently.	1) Contractor for HY/2009/11 was granted valid Construction Noise Permit no. GW-RS0371-10 for their dredging works. 2) There was only 1 grab dredger operated by Contractor within NPR project site area for dredging works. 3) No noise exceedance was recorded at noise monitoring station at Victoria Centre on 27 July and 3 August 2010 during daytime and evening time period. 4) It is considered as invalid from the EP and CNP point of view.	Closed
100812	12/8/2010	Mr. Wong, Harbour Heights (Management) Ltd.	Harbour Heights	Management office received their resident complained on the noise nuisance from the dredging works at the marine works area adjacent to the Harbour Height during the period from 0700 to 2200.	1) Contractor for HY/2009/11 was granted valid Construction Noise Permit no. GW-RS0371-10 for their dredging works. Contractor has implemented mitigation measures to reduce the working hour not later than 2230. 2) No noise exceedance was recorded at noise monitoring station at Victoria Centre on 10 and 17 August 2010 during daytime and evening time period. 3) It is considered as invalid complaint. No further complaints were received in the reporting month. The complaint is considered closed.	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
101108	8/11/2010	Mr. Nip received by ICC (CC Case)	Sai Wan Ho	Visual concern around the seaside silt screen outside the WSD freshwater intake pump at Sai Wan Ho (Monitoring station ref no.. WSD15)	1) Contractor for HY/2009/11has been regular checked of condition and removal of trapped rubbish before the dismantling of the floating silt screen to be replaced by wall mount silt screen. 2) Follow-up action had been immediately carried out to check and clear the floating refuse around the seaside silt screen after receipt of the complaint. 3) Removal of seaside silt screen outside the WSD freshwater intake (WSD15) by contractor HY/2009/11 was checked and confirmed dated 9 November 2010. Silt screen has been deployed into the existing steel frame at WSD15 for the protection of WSD salt water intake.	Closed
101110	10/11/2010	Mr. Wong, Harbour Heights (Management) Ltd.	Harbour Heights	Management office received their resident complained on the noise nuisance from the power mechanical equipment during the 0700 to 2200hrs	1) Contractor for HY/2009/11 was granted valid Construction Noise Permit no. GW-RS0870-10 for their dredging works during evening time. Contractor has implemented mitigation measures to reduce the working hour not later than 2230. 2) No noise exceedance was recorded at noise monitoring station at Victoria Centre on 4 and 10 November 2010 during daytime and evening time period. 3) It is considered as invalid complaint. No further complaints were received in the reporting month. The complaint is considered closed.	Closed
101203	3/12/2010, 01:45a.m.	The resident of Block 11, City Garden by ICC referral from Marine Department	North Point	Bad odour was generated from the dredging plant off North Point	1) The first investigation was carried out by Marine Department patrol in the morning on 3 Dec 2010 at around 10:00 and revealed that a few working barges were anchoring in the vicinity without carrying out dredging work. 2) A further specific investigation inspection on contractor's backhoe barge in the vicinity of City Garden was jointly conducted with Engineer Representatives (AECOM/RSS), and ET on 8 Dec 2010 at 11:30. No bad odour was noted during the investigation. 3) Routine dredging operation of the backhoe barge was performed during the jointed investigation inspection and it was revealed that no bad odour was attributed by the dredged materials inspected.	Closed
101206	6/12/2010	Ms Lui, the resident of 27/F, Block 10, City	City Garden, North Point	Two barges were generating noise at 22:00 on 6 December 2010 in which the noise from	1) ET confirmed the following information with resident site staff on the complaint: • It was referred to the filling operation at North Point	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
		Garden by ICC (ICC case: 1-266039336)		filling operation was louder than the traffic noise & visual impact was generated due to the spot-light pointing directly to the complainant flat, suspected the filling operation was part of Wanchai Development Phase II; Complainant also raised the same complaint to District Councillor, Mr. Hui on 7 Dec 2010 regarding the night-time noise and suspected earlier start of work at 06:30. Complaint also requested for limiting the plant operating hours from 09:00-21:00.	Reclamation of Central Wan Chai Bypass site area instead of part of Wanchai Development Phase II; • Two derrick barges were in operation at the time of complaint for placing 400 rockfill onto the excavation trench and for levelling the formation level to receive the pre-cast caisson seawall; • Flood light on the control mast of derrick barge have no lighting shields for the prevention of glare of flood lights; • No starting work on 7 Dec 2010 at 0630hours. 2) PME used in restricted hours were checked and confirmed compliant with valid CNP no. GW-RS0870-10. The noise level recorded on 6 Dec 2010 was complied with the noise criteria during restricted hour; 3) It was found that the occasional noise nuisance might be caused by the hitting or scratching onto the rock surface during loading down the grab onto the Grade 400 rockfill; 4) The absence of the lighting shields at flood light results in visual glare to the complainant at night-time. 5) Contractor was advised to minimize the finishing time of placing Grade 400 rockfill at 2100hrs and switch off all unnecessary flood lights apart from the light for the safety and security purpose; 6) No further complaint was received after implementation of proposed measures	
110415	15/04/2011	The resident, Mr Law at Victoria Centre by ICC (ICC#1-281451236)	North Point	A dust generation and a concern of mosquitoes breeding complaint in which suspected the filling operation was part of North Point Reclamation.	1) The concerned stockpile was a working stockpile under Contract HY/209/15 and was covered at night time after work. 2) Water spraying on the haul road and potential dust generating material at least 4 times a day was conducted by contractor that complies with the requirement. 3) It is considered invalid but preventive actions can be taken because the stockpile is relatively large and easily visible by complainant. 4) It was recommended that increasing the frequency of water spraying shall be conducted to all potential dust generating materials and activities. Besides, Contractor should consider to cover the idle part of the stockpile 5) The concern of mosquitoes breeding is out the scope of EM&A, the follow-up action is not reported in this monthly EM&A report.	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
110419	19/04/2011	Ms Chiu at Victoria Centre at Victoria Centre by ICC (ICC# 1-272874759)	North Point	The episode of night noise on 19/4/11 and 20/4/11 at 2:50 am and the noise lasted for 30 minutes per night.	1) According to the RSS's record, there was no construction works undertaken under the EP-356/2009 during the concern time period. 2) There was no abnormal real-time noise monitoring data recorded in RTN1 - FEHD Hong Kong Transport Section Whitefield Depot which is next to the Victoria Centre. 3) It is considered as invalid complaint under this Project.	Closed
110617	9/06/2011	Mr. Law from Victoria Centre Management Office	North Point	An odour nuisance suspected generating from the discharge point – Channel T at Watson Road in part of the site area was related to CWB under Contract no. HY/2009/11	1) The complaint was received by ET on 13 Jun 2011. During the weekly site inspection on 7 and 17 June 2011, there was no any odour impact detected in the site area. 2) According to the site record, there was muddy water discharged from the unknown source at upstream of Channel T during heavy rainstorm. No any site surface runoff to the Channel T and out of site boundary was observed in the inspection. 3) In order to prevent muddy water washing out to the water body under heavy rainstorm, a silt curtain was installed at the outfall of the channel by Contractor. ET confirmed with the Resident Site Staff that a silt curtain was installed at the outfall of the channel to prevent muddy water washing out to the water body under heavy rainstorm. Besides, regular cleaning of refuse in the channel has been conducted by Contractor. 4) A further site investigation on 28 June 2011 revealed that no odour nuisance was detected at the upstream of the Channel T and no source of odour nuisance was identified at site. As such, it was concluded that the source of odour nuisance was not related to the Project works. 5) Although no source of odour nuisance was identified at site, the muddy water and dirt from the unknown source at upstream of Channel T may cause a potential smell during low tide and low water flow. Contractor was reminded to remove the silt curtain at the channel on non-rainy day so as to avoid the accumulation of the sediment and dirt in the water channel.	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
110709	09/07/2011	Mr. Au from City Garden Management Office	North Point	A complaint letter to Contractor HY/2009/11 was raised by Cayley Property Management Limit on 9 July 2011 regarding a series of pump breakdown events at seawater intake of City Garden on 4, 6, 7 and 8 July 2011. A lot of rubbish such as plastic bags, nylon bags, nylon-wire mesh was observed sucking from the seawater intake at the seawater front of Block 7 of City Garden affecting the operation of seawater pump plant.	1) Contractor conducted formation works for installation of caisson seawall at C27, C28, C29 and C30 on 4, 6, 7 and 8 July 2011 and no dredging work was conducted during this time period 2) Water mitigation measures of an 80m long silt curtain at the site boundary in front of City Garden Relocation of silt curtain and silt curtain at the outfall of the channel were provided and maintained to accommodate the site works. All vessels are equipped with rubbish collection facilities and disposed the rubbish regularly. Also, daily cleaning actions had been taken by contractor to minimize floating refuse within the site boundary. 3) Moreover, it has been reported several times that discharged from outfall pipeline outside the site boundary near the intake of the pump maybe considered as another source of rubbish generation. 4) Referring to the record provided by Cayley Property Management Limit, the trapped rubbish was unlikely generated from the construction works. It was considered that complaint is invalid and not related to project.	Closed
110710	09/07/2011	Complainant by ICC (ICC no. 1-301520309	North Point	It was received at 00:56 on 10 July 2011. There was complained a derrick barge unloading rockfill material off the shore facing the Harbour Grant HK Hotel causing noise nuisance.	1) ET confirmed with the Resident Site Staff that the complaint was referred to Contract HY/2009/15 for the loading and unloading of fill material at two barges operation in the sea at around 300m adjacent to Island Eastern Corridor (Oil Street Chainage) where is outside the Site of HY/2009/15 in the period of around 19:45 on 9 July to 1:00 on 10 July 2011. 2) The material loading and unloading operation processed in restricted hours was checked without a valid CNP. It was found that the operation was due to an unexpected water leakage of the hopper barge and considered an incident. 3) According to the incident report provided from RSS on 20 July 2011, around 7:30 pm the barge S22 was inclined slightly and slightly water leakage might occur. Due to marine safety concern, the hopper barge would open the hopper to release the contained materials in order to reduce the weight and stabilize the barge. In consider of slight water leakage, the operator decided to use the nearby Derrick Barge ST32 to help for unload the general fill materials first and the unloading operation was started at around 7:45pm, and end at around 1:00 am. Contractor was reminder to provide frequent check of vessel condition	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					so as to prevent recurrent by barge defect	
110723a	23/07/2011	Ms. Law at Victoria Centre by ICC no. 1-303887687	North Point	She concerned that Highways Department published a notice in their Management Office about construction works will be conducted from 0700 hours to 2300 hours during July to December 2011 including Saturday, Sunday and public holiday.	1) It was referred by AECOM to ET on 28 July 2011 2) RSS confirmed that the notice was prepared by Victoria Centre's Management office to their resident and the advice was only given on the extension construction works (for Contract HY/2009/15) to 7am-9pm from Monday to Saturday except Public Holidays and Sundays. 3) As a mitigation measure to minimize the noise nuisance in the vicinity of the residents, rock breaking activities will be started at 8am and is expected to be completed by mid-August 2011. 4) No noise exceedance was recorded at construction noise monitoring station at Victoria Centre on 19 and 25 July 2011 during daytime while breaking and excavation works were undertaken during monitoring. 5) In conclusion, it was related to the construction works under Contract HY/2009/15 and mitigation measure was provided. The complainant was satisfied with the arrangement and no further complaint was received after proposed measures.	Closed
110723b	23/07/2011	Ms. Yau at Block 2, Victoria Centre by ICC no. 1-304013959	North Point	Reclamation work was conducted at Causeway Bay Typhoon Shelter at 7am on 23 July 2011. She complained that the works shall be started later to minimize the noise nuisance to the vicinity of the residents in early morning	1) It was referred by AECOM to ET on 8 August 2011 2) With reference to the construction noise monitoring at Vitoria Centre, no exceedance was recorded on 19 and 25 July 2011 during daytime while breaking and excavation works were undertaken during monitoring 3) As a mitigation measure to minimize the noise nuisance in the vicinity of the residents, rock breaking activities will be started at 8am and is expected to be completed by mid-August 2011. 4) In conclusion, it was related to the construction works under Contract HY/2009/15 and mitigation measure was provided. The complainant was satisfied with the arrangement and no further complaint was received after proposed measures.	Closed
110727a	27/07/2011	Mr. Law from Victoria Centre Management Office by ICC no. 1-304616162	North Point	It was complained by Mr. Law from Victoria Centre Management Office on 27 July 2011 regarding construction noise generated by the construction operations of	1) It was referred by AECOM to ET on 28 July 2011 2) RSS confirmed to start the rock breaking activities for Contract HY/2009/15 at 8am as a mitigation measure to minimize the noise nuisance in the vicinity of the residents. 3) No noise exceedance was recorded at construction noise	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
				Central-Wanchai Bypass at noon rather than in morning at 7am.	monitoring station at Victoria Centre on 25 July and 4 August 2011 during daytime while breaking and excavation works were undertaken during monitoring. 4) In conclusion, it was related to the construction works under Contract HY/2009/15 and mitigation measure was provided. No further complaint from complainant was received after proposed the mitigation measure.	
110727b	27/07/2011	Ms. Chiu by ICC no.1-304615409	North Point	Noise nuisance from the excavation works for the Highways Department adjacent to the Victoria Centre was conducted from 7am	1) It was referred by AECOM to ET on 28 July 2011 2) With reference to the construction noise monitoring at Vitoria Centre, no exceedance was recorded on 25 July and 4 and 10 August 2011 during daytime while breaking and excavation works were undertaken during monitoring. 3) As a mitigation measure to minimize the noise nuisance in the vicinity of the residents, rock breaking activities will be started at 8am.	Closed
	08/08/2011				4) However, complainant did not satisfy with the response on the noise nuisance from the rock-breaking during morning in front of Victoria Centre and then further complaint via 1823 on 7 August 2011. 5) Highways contacted the complainant on 15 August 2011 that the noisy rock breaking operation had been completed. *Remarks: There will be counted as two complaints in this complaint log.*	
110810	10/08/2011	Mr. Yip by ICC no. 1 – 306740207	North Point	Muddy water was discharged from work site to the seafront near Oil Street during heavy rain. The environmental protection measures were not good enough and are needed to rectify.	1) It was referred by AECOM to ET on 17 August 2011. 2) Confirmed with RE, Muddy water was caused by a heap of earth being washed to the sea by heavy rain. The heap of earth was referred as a small stockpile placed close to the seafront in front of Oil Street within the site area under handover transition period from contract HY/2009/11 to contract HY/2009/19. The necessary mitigation measures to protect the small stockpile against rainfall were missing at the time of complaint. 3) Due to the missing of mitigation measures to protect the small stockpile during handover transition period, loose material was washed into the harbour when heavy rain came. Muddy water was formed and dispersed in the sea that caused the water quality and visual concern to the public. The complaint was considered as valid. 4) Contractors were advised to relocate the loose materials	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					away from the coastline as far as practicable. Any loose material placed which needed to be placed near the coastline shall be properly compacted or covered as appropriate. To avoid any further environmental deficiency, Contractors shall ensure all necessary environmental mitigation measures will not be missing during site area handover.	
110826	26/08/2011	Grand Hyatt and a complainant by ICC	Wan Chai	Construction noise and vibration nuisance generated from the works at Convention Avenue and inside the HKCEC1 reclamation area.	1) Confirmed with the Resident Site Staff that the construction works were referred to the Contractor HK/2009/01. 2) The Excavator mounted breaker at Convention Avenue and Drilling rig at HKCEC1 reclamation area were the dominant construction noise source during this period. 3) The drilling rig at HKCEC1 reclamation area and excavator mounted breaker at Convention Avenue were then temporary suspended after received the complaint. 4) Investigation revealed that the erected noise barrier (4m cantilevered movable noise barrier for the drilling rig and 1m movable noise barrier for the excavator mounted breaker) were not located close to the plants to provide adequate noise screening. 5) Contractor was advised to avoid concurrent operation of construction plants at site. Further enhancement of movable noise barriers at HKCEC1 and providing noise enclosure for the excavator mounted breaker at Convention Avenue are needed. 6) Further site investigation and checking on 31 August and 7 September 2011 revealed that the implemented noise mitigation measures were in proper and minimize the noise impact.	Closed
110826A	26/08/2011	A complaint letter from Mr. Au of Cayley Property of City Garden	North Point	Harbor front adjacent to their cooling water intake suction which caused 3 times of system breakdown of the sea water pump on 9, 22 and 25 August 2011.	1) It was referred by AECOM to ET on 29 August 2011. Confirmed with the Resident Site Staff that the • construction works were referred to the Contractors HY/2009/11 and HY/2009/19. • The pump is located on the site area of HY/2009/19 • A temporary garbage defender was installed on 23 July 2011 by HY/2009/11 and the shape of the defender was adjusted on 8 August 2011 in order to excluse the outfall. • An ad hoc inspection of the effectiveness of garbage defender was conducted with RSS (CWB project	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					team), contractor of HY/200911 and HY/2009/19 and IECon 29 August 2011. Inspection report of it was submitted to RSS on 19 September 2011. • Daily cleaning near the water intake was conducted twice a day by contractor HY/2009/19. • In response to City Garden request, the contractors have set up the temporary garbage defender in function and collect the floating refuses, but cannot eliminate all refuses, in particular the refuse coming from the seabed 2) According to the complaint letter from Cayley Property, the outcomes of the preventive measures were not complying wih their expectation. 3) During on-site inspection, floating refuses observed occasionally outside the garbage defender. No conclusion could be made for the source of these floating refuses. On the other hand, some of the refuses were observed floating behind the garbage defender during investigation. 4) All daily cleaning actions had been taken by contractor to minimize floating refuse inside the construction site. 5) It was noted that the cooling water intake was accessible to the public. As such, fish breeding and fishing activities were observed even though a notice has already hoisted. Also, tripping of rubbish by the passers-by could result in a lot of rubbish accumulated around the intake point. 6) Referring to the record provided by CPML, there were a lot of nylon/ plastic bags and nylon wire mesh that matched those rubbishes generated from the public activities. 7) Contractors have fulfilled the requirement of site cleanness and no exceedance was recorded during Water Quality Monitoring. It is consider the cause of this complaint is not related to project and environmental issue in this project as well. No more complaint received after ad-hoc inspection	
111014	14/10/2011	The complainant, Ms. Tam complained via hotline 1823	Wan Chai	The polluted fumes and exhaust from the excavation by sub-contractor of CEDD on pedestrian way outside no.25 Harbour Road (in front of the Harbour Centre)	1) RSS notified ET to carry out investigation on 17 October 2011. 2) ET confirmed with the Resident Site Staff that the location of the excavator was within site area of Contract no. HK/2009/02 undertaking the water cooling main reprovision works along the Harbour Road. The plants including the excavator have been checked before using	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					at the site. However, the polluted fumes and exhausted from the excavator was caused due to insufficient maintenance of the plant after using at site. 3) After receiving the complaint, the excavator was then removal off-site for checking and maintenance works on 17 October 2011. 4) Contractor was reminded to enhance regular checking and maintenance to all plants at site. 5) RSS has replied to the complainant on the arrangement of the measures taken on 17 October 2011. Complainant was satisfied with the response and follow-up action taken by the Contractor.	
111104	04/11/2011	Mr. Liu from LCSD complained via Contractor Complaint Hotline	Wan Chai	Complain about a tree near the site of pipe installation works outside Wan Chai Swimming Pool at Harbour Road, the status is not healthy and roof ball of two trees inside the site near Renaissance Hong Kong Harbour View Hotel at Convention Avenue were half cut.	1) ET confirmed with the Resident Site Staff that • A tree near the site of pipe installation works outside Wan Chai Swimming Pool at Harbour Road is the Tree no. TA1122 under Contract no. HK/2009/02. Leaves of a branch of this tree were shrivelled. • Two trees inside the site near Renaissance Hong Kong Harbour View Hotel at Convention Avenue are the tree nos. A160 and A161 under Contract no. HK/2009/01. Part of roof ball of these two trees was covered by the metal plate. 2) Independent Tree Specialists for these two inspected the trees. Contractor HK/2009/01 has taken the measure as recommend downgrading the soil level around the trunk base. Reinstating of the ground works will be conducted in mid-December 2011. For the tree no. TA1122 under Contract no. HK/2009/02, the brown leaves were removed and fenced the tree with orange net is provided to prevent damage of tree trunk by construction works. The distance between the tree and the edge of the trench is kept approximate 2m. Two Contractors were reminded to carry out regular watering to the trees within their site area.	Closed
111106	06/11/2011	Police officer	Wan Chai	Construction noise generated from the site at about 6:30 a.m on 6 November 2011 and require to stop the machine operation	1) According to the information reported by Contractor, one BC cutter and hoist were operated for Diaphragm Wall construction of Shatin-Central Link to inspect bentonite pipes and ensure no damages and all the joints are tightened in good position. Then, the subcontractor for Diaphragm wall, SAMBO Korean foreman stopped the engine of the BC cutter immediately. The police officer recorded the details and HKID number of the foreman and then left. Due to the different language communication between the police officer and the Korean foreman, no	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					CNP was checked by the police officer. 2) ET confirmed with the Resident Site Staff that same issue was also raised out by RSS at about 7:00a.m on the same day. Besides, it was confirmed that there is no valid Construction Noise Permit for the conducted construction works in the period between 2300 and 0700. 3) Due to insufficient communication between Contractor HK/2009/01 and their Korean Sub-contractor, Korean Sub-contractor had not notified to Contractor before carrying out the inspection of the BC cutter, hoists and bentonite pipes at about 6:00a.m to ensure no damages and all the pipe joints should be tightened and in good position. 4) Contractor was advised to enhance the communication between Contractor and sub-contractor and provide sufficient environmental training to all foreman and operators on restricted hour operation. Futhermore, Construction Noise Permit should be checked and in place for the construction works during restricted hour 5) This complaint was considered in relation to the conducted construction works during restricted hours without valid Construction Noise Permit. No more construction works were conducted during night time period. The construction works will be conducted in accordance with the time period stated in valid CNP. This complaint will be kept in view of any follow-up action from the relevant government activities.	
120405	05/04/2012	N/A	North Point	A complaint regarding excessive noise from construction sites of CBTS was observed daily before 7:30am except on public holidays, and the noise source was mainly from piling works. The complainant requested that construction works should start after 8:30am to avoid nuisance to nearby residents and a speedy follow-up and reply.	1) RSS notified ET on 5 April 2012. 2) ET confirmed with the Resident Site Staff that no piling works were performed during the concerned period. 3) After reviewing the results of noise monitoring (M2b and M3a), no exceedance was recorded during daytime period and the noise level was below 75dB(A). Site inspection for HY/2009/15 was conducted on 10 April 2012. The condition of noise mitigation measures around CBTS was found satisfactory. RSS confirmed that no pilings were performed during the concerned period. The major works included drilling, diaphragm wall construction and excavations. 4) HyD made a reply to the complainant on 16 April 2012 via 1823. HyD replied that the current works at CBTS were drilling, diaphragm wall construction and deep excavations. In order to minimize the noise generated	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					from the above works, the Contractor had erected temporary noise barriers and provided noise blankets on plants. RSS would continue to work with the Contractor on the effectiveness of the environmental mitigation measures implemented on site. No further complaint was received after the response.	
130308	06/03/2013	ICC Case#1-407181502	Tin Hau	A complaint regarding the dropping of fine rock material into surrounding waterbody was observed during rock breaking operation with two excavators in active operation at the Eastern Breakwater of Causeway Bay Typhoon Shelter near the North Point lighthouse.	1) RSS notified ET on 8 March 2013 2) ET confirmed with RSS that excavation works, installation of buoy, flashing light and silt curtain and dredging works were undertaken at Eastern Breakwater during the concerned period on 6 March 2013. One backhoe equipped with breaker and one derrick barge were confirmed in operation while another backhoe was at idle during the concerned period on 6 March 2013. 3) Reviewing the photo record provided by RSS, the condition of the silt curtain deployed around the Eastern Breakwater on 6 March 2013 was found to be in good condition. It is considered that the silt curtain was properly in place during the concerned period and the concerned act of dropping of fine rock material was confined within the silt curtain boundary without adverse impact to the nearby water quality. Further follow up was conducted on 12 March 2013 during weekly environmental audit inspection, the silt curtain deployed around the concerned area was found to be maintained in good condition and the water quality at the concerned work area was generally satisfactory. No violation of the Environmental Permit condition was found. The contracotr was advised and committed to implement preventive meaures to miminize the potential impact of work including conducting regular diver check to ensure the integrity and the extend of silt curtain deployment and to provide adequtae back up stock of silt curtain for emergency use.	Closed
140612	12/06/2014	EPD ref: EP/860/F2/24 Annex IV	Wan Chai	The complaint is regarding to the water quality of the waterfront outside the Hong Kong Academy for Performing Arts Theatre Block, where a large piece of muddy water was found.	1) WSII RSS team notified ET on 12 June 2014; Notification letter from EPD (ref: EP/860/F2/24 Annex IV) was received by ET on 13 June 2014. 2) ET confirmed with RSS that neither marine construction works nor barge operation was conducted at the concerned location during the time of complaint. With respect to the complaint case, muddy dispersion was observed at HKCEC2W works area on 12 June 2014, and	Closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					the dispersion was observed partly extended beyond the outermost layer silt curtain at 1000hrs. Immediate follow up action was requested. 3) It is considered that Contractor's mitigation measures would require further review on the effectiveness to avoid seepage of muddy dispersion such as regular diver inspection check and daily visual checking of silt curtains. Additional silt curtain at marine access zone was installed by Contractor on 12 June 2014 and the double layer silt curtain were generally in order. Follow-up inspection was further conducted on 16 June 2014. The Contractor's investigation report on the complaint case was submitted to EPA via email on 18 June 2014.	
140723	21/07/2014	ICC Case Ref: 2-341537112	Works area opposite to Ngan Tao Building	The complaint is regarding to construction noise impact to the complainant who could not sleep due to work and machine at the project site opposite to the Ngan Tao Building.	1) Construction noise impact referred by RSS was received by ET on 25 July 2014 2) ET confirmed with RSS that horizontal cutting and removal of D-wall at Eastern, Southern and Northern side of TS2 was undertaken by Contractor of HY/2009/15 within Causeway Bay Typhoon Shelter before 23:00hrs on 20 July 2014 that total 3 numbers of derrick lighter and 3 numbers of saw cut machine were in operation, and removal of D-wall at Panel S30A-1 of TS2 was undertaken by Contractor of HY/2009/15 within Causeway Bay Typhoon Shelter around 00:25hrs to 00:56hrs on 21 July 2014 that total 1 number of derrick lighter was in operation. 3) According to the relevant site records under Contract HY/2009/15, before 23:00hrs on 20 July 2014, horizontal cutting and removal of Diaphragm Wall at Eastern, Southern and Northern side of TS2 was conducted under HY/2009/15 within Causeway Bay Typhoon Shelter. Total 3 nos. of derrick lighter and 3 nos. of saw cut machine were in operation at the above period. From around 00:25hrs to 00:56hrs on 21 July 2014, removal of D-wall at Panel S30A-1 of TS2 was undertaken by Contractor of HY/2009/15 within Causeway Bay Typhoon Shelter. Total 1 no. of derrick lighter was found operating at the above period 4) It was considered the condition of CNP GW-RS0592-14 was not fulfilled by the Contractor of HY/2009/15. "From 00:25hrs to 00:57hrs on 21 July 2014, the PME(s) (1 no. of Derrick Lighter) on-site could not follow with any given PME grouping requirement(s) as stated in condition 3.a. and condition 3.d. in no. GW-RS0592-14."	Final report (Issue1) issued on 31 July 2014. Further to complainant follow-up, Final report (Issue2) Issued on 12 Aug 2014.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					Notwithstanding the above, according to the site recorded provided by the RSS, the derrick lighter was found malfunction at around 23:00hrs on 20 July 2014 while the diaphragm wall cutting procedure was incomplete. Under safety and navigation consideration, the completion of diaphragm wall removal was necessary and of imminent need. 5) The Contractor of HY/2009/15 was advised to review the construction sequence and emergency response procedure for construction activities during restricted hours and night time period to allow for sufficient buffer time for work completion such that the Construction Noise Permit would be followed. Furthermore, the Contractor of HY/2009/15 was suggested to conduct throughout checking of PME used on site prior to work commencement to minimize the potential malfunctioning of PME during the course of work which affect the duration of works.	
141016	14/10/2014	EPD Ref.: EP860/E2/24 Annex IV ICC complaint received by ET on 10 October 2014	Work site next to new Wan Chai Ferry Pier and opposite to Wan Chai Sports Ground.	Construction noise like piling works was heard on 14 October 2014 night until 23:45 hrs. It was suspected that the noise was emanated from the work site next to new Wan Chai Ferry Pier and opposite to Wan Chai Sports Ground.	A public complaint regarding construction noise impact referred by EPD was received by ET on 16 October 2014 (EPD Ref.: EP860/E2/24 Annex IV dated 16 October 2014). The complainant reported that construction noise like piling works was heard on 14 October 2014 night until 23:45 hrs. It was suspected that the noise was emanated from the work site next to new Wan Chai Ferry Pier and opposite to Wan Chai Sports Ground. ET confirmed with the Resident Site Staff that From 19:00hrs to 23:00hrs on 14 October 2014, dredging works was conducted under Contractor of HK/2009/02 at WCR3 Area. Total one grab dredger was in operation. Mitigation measures including provision of steel sheeting screening to the power generation part of the grab dredger was implemented by the Contractor of HK/2009/02. From 23:00 hrs to 05:00 hrs, dredging works was conducted under Contractor of HK/2009/02 at WCR3 Area. Total one grab dredger was in operation. Mitigation measures including provision of steel sheeting screening to the power generation part of the grab dredger was implemented by the Contractor of HK/2009/02.	Interim investigation report submitted to EPD on 23 October 2014. Updated interim investigation with supplementary information submitted to EPD on 17 November 2014 EPD

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					From 23:00 hrs to 06:00hrs, panel replacement works was conducted under Contractor of HK/2009/02 at the Temporary Covered Walkway. Total one scissor platform and two hand held drills (battery) were in operation. From 23:00 hrs to 06:00hrs, trial pit works was conducted under Contractor of HK/2009/02 at Hung Hing Road.Total one crane lorry was in operation. According to the relevant site records under Contract HK/2009/02, from 19:00hrs to 23:00hrs on 14 October 2014, dredging works was conducted under Contractor of HK/2009/02 at WCR3 Area. Total one grab dredger was in operation. Mitigation measures including provision of steel sheeting screening to the power generation part of the grab dredger was implemented by the Contractor of HK/2009/02. From 23:00 hrs to 05:00 hrs, dredging works was conducted under Contractor of HK/2009/02 at WCR3 Area.Total one grab dredger was in operation. Mitigation measures including provision of steel sheeting screening to the power generation part of the grab dredger was implemented by the Contractor of HK/2009/02. From 23:00 hrs to 06:00hrs, panel replacement works was conducted under Contractor of HK/2009/02 at the Temporary Covered Walkway. Total one scissor platform and two hand held drills (battery) were in operation. From 23:00 hrs to 06:00hrs, trial pit works was conducted under Contractor of HK/2009/02 at Hung Hing Road. Total one crane lorry was in operation. In view of the above findings, no direct information associated with the noise concern was considered available.	advised no further comment on the updated interim report and case closed on 27 Nov 2014.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
141110	07/11/2014	EPD Ref.: H05/RS/00027815-14 EPD complaint received by ET on 10 November 2014	Construction site at old Wan Chai Ferry Pier	Malodour of construction plant exhaust from the construction site at old Wan Chai Ferry Pier was scented that affecting the swimmers at Wan Chai Swimming Pool.	A public complaint regarding odour concern referred by EPD was received by ET on 07 November 2014 (EPD Ref.: H05/RS/00027815-14 dated 10 November 2014). The complainant reported that Malodour of construction plant exhaust from the construction site at old Wan Chai Ferry Pier was scented that affecting the swimmers at Wan Chai Swimming Pool. ET confirmed with the Resident Site Staff that ELS works was conducted on 7 November 2014 during daytime at Portion 2 (Area oppsite to WanChai Swimming Pool). Total 3 nos. of excavators, 2 nos. of crawler cranes, 2 nos. of generator, 1 no. of crane lorry and 2 no. of dump trucks were operated. Demolition works was conducted on 7 November 2014 during daytime at West of old Wan Chai Ferry Pier. Total 2 nos. of excavators, 1 no. of derrick barge and 1 no. of tug boat were operated. Dredging works was conducted on 7 November 2014 during daytime at WCR3 (East of old Wan Chai Ferry Pier) Total 1 no .of dredger, 1 no. of hopper and 1 no. of tug boat were operated. According to the relevant site records under Contract HK/2009/02, ELS works was conducted on 7 November 2014 during daytime at Portion 2 (Area oppsite to WanChai Swimming Pool). Total 3 nos. of excavators, 2 nos. of crawler cranes, 2 nos. of generator, 1 no. of crane lorry and 2 no. of dump trucks were operated. Demolition works was conducted on 7 November 2014 during daytime at West of old Wan Chai Ferry Pier. Total 2 nos. of excavators, 1 no. of derrick barge and 1 no. of tug boat were operated. Follow-up inspection was conducted during weekly environmental inspection on 13 November 2014, no dark smoke emission was observed from the PMEs operating on-site. The condition of chemical waste storage was considered satisfactory and no malodour was identified. Despite no information related to malodour was identified, the Contractor was reminded to conduct regular checking on the condition of PMEs to ensure only well maintained PMEs are used on site.	Interim investigation report submitted to EPD on 17 November 2014. EPD advised no comment on the interim report and case closed on 1 Dec 2014.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					Based on the relevant information provided by RSS, despite no information associated with the malodour concern was identified after investigation, the Contractor was reminded to conduct regular checking on the condition of PME used on site to ensure only well maintained PME are used on site The interim report would be submitted to EPD on 17 November 2014.	
141113	12/11/2014	EPD Ref.: H05/RS/00028253-14 EPD complaint received by ET on 13 November 2014	Construction site at old Wan Chai Ferry Pier	Malodour and dark smoke emission from an excavator located at the construction site at old Wan Chai Ferry Pier was observed that affecting the pedestrians.	A public complaint regarding odour concern referred by EPD was received by ET on 13 November 2014 (EPD Ref.: H05/RS/00028253-14 dated 13 November 2014). The complainant reported thatMalodour and dark smoke emission from an excavator located at the construction site at old Wan Chai Ferry Pier was observed that affecting the pedestrians. (Contract HK/2009/02) ET confirmed with the Resident Site Staff that demolition works was conducted under Contract HK/2009/02 on 12 November 2014 during daytime at old Wan Chai Ferry Pier. Total 2 nos. of excavators, 1 no. of derrick barge and 1 no. tug boat were operated. According to the relevant site records under Contract HK/2009/02, demolition works was conducted on 12 November 2014 during daytime at old Wan Chai Ferry Pier. Total 2 nos. of excavators, 1 no. of derrick barge and 1 no. tug boat were operated. In addition, investigation found that due to malfunctioning of one of the excavators deployed at old Wan Chai Ferry Pier, dark smoke was emitted from the defective excavator for a short period of approximately 30 seconds at around 15:00 hrs on 12 November 2014. The operation of excavator was immediately suspended and followed by repair works. The normal operation of the excavator was resumed after repair. Follow-up inspection was conducted during weekly environmental inspection on 13 November 2014, no dark smoke emission was observed from the PMEs operating on-site and the Contractor of HK/2009/02 was reminded to conduct regular checking on the condition of PMEs to ensure only well maintained PMEs are used on site.	Interim investigation report submitted to EPD on 19 November 2014. EPD advised no comment on the interim report and case closed on 8 Dec 2014.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
141121	Not Specified	EPD Ref: H08/RS/28263-14 EPD complaint information and findings was received by ET via email on 21 Nov 2014	Causeway Bay Typhoon Shelter	Resident in Hing Fat Street complaining about loud noise from dredging work in CBTS up to 10pm at night.	EPD received a construction noise complaint from dredging works at Causeway Bay Typhoon Shelter and a resident in Hing Fat Street complaining about loud noise from dredging work in CBTS up to 10pm at night. EPD investigation found that the operation of a derrick barge is covered by CNP no. GW-RS0701-14. EPD reminded the Contractor of HY/2011/08 to ensure the work strictly follow the permit conditions and endeavor to minimize the noise as so not to disturb the nearby residents.	Complaint case handled by EPD and relevant investigation findings was sent to ET on 21 November 2014
150127	21 Jan 2015	EPD complaint (EPD Ref.: H05/RS/00001725-15) received by ET on 27 January 2015 and further information from EPD regarding the updated location under complaint was received by ET on 30 January 2015	A portion of Hung Hing Road immediately to the east of Marsh Road near SPCA	Construction dust and grit was emitted from the construction site to the carriageway causing nuisance to the public.	A public complaint regarding air quality impact referred by EPD was received by ET on 27 January 2015 (EPD Case Ref.: H05/RS/00001725-15 dated 27 January 2015) and further information from EPD regarding the updated location under complaint was received by ET on 30 January 2015. The complainant reported that construction dust and grit was emitted from the construction site to the carriageway causing nuisance to the public. ET confirmed with the Resident Site Staff that the major construction activities around the concerned location conducted on 21 January 2015 include breaking of seawall blocks and D-wall at TPCWAW; concreting, grouting and drilling works at TPCWAW;reclamation/ backfilling works at TPCWAW Mitigation measures implemented by the Contractor for the above construction works include spraying haul road with water; covering bagged cement with tarpaulin; providing three sided and top covering for grouting stations; providing water spraying to dusty activities such as breaking works According to the relevant site records, breaking of seawall blocks and D-wall, concreting, grouting and drilling works and reclamation/ backfilling works were	Interim report submitted to EPD on 9 February 2015, EPD advised no comment on 27 February 2016 on the interim report submitted and case closed.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					conducted at TPCWAW. Dust mitigation measures including spraying haul road with water, covering bagged cement with tarpaulin, providing three sided and top covering for grouting stations and water spraying to dusty activities such as breaking works were implemented by the Contractor of HY/2009/15 near the concerned location on 21 January 2015. Follow-up investigation was conducted on 27 January 2015 during weekly environmental inspection, dust mitigation measures including water spraying for dusty haul road and major dust generation works; and provision of three sides and top covering for grouting station were confirmed in place. In addition, based on the review of the monitoring data of the monitoring station located at the concerned location raised by the complainant, namely monitoring station CMA3a , no action or limit level exceedance was recorded during air quality monitoring conducted on 20 and 21 January 2015. Nevertheless, the Air Quality Health Index (AQHI) recorded by EPD across Western District and Eastern District on the complaint date was ranged from 4 to 10+ indicating a severely high concentration of ambient air pollutants. As such, the site condition under Contract HY/2009/15 at the concerned location was considered to be generally satisfactory and no non-conformity related to cumulative air quality impact was observed. Nevertheless, in view of the public concern, the contractor was reminded to enhance the dust mitigation measures implemented to minimize potential nuisance to nearby public.	
150622	18 June 2015	EPD Ref.:H05/RS/ 00015054-15 dated 8 June	A mooring location near shore and at location outside Wan Chai Sports	Dark smoke and malodour emission was observed from a hopper barge moored near shore and	A public complaint regarding dark smoke and malodour concern referred by EPD was received by ET on 22 June 2015 (EPD Ref.: H05/RS/00015054-15 dated 22 June 2015). The complainant reported that dark smoke and malodour emission was observed from a hopper barge	Interim report submitted to EPD on 29 June 2015 and EPD

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
		2015	Ground	other construction plants under operation from the reclamation construction site	moored near shore and other construction plants under operation from the reclamation construction site with Contract no. HK/2009/02 at location outside Wan Chai Sports Ground caused air pollution. The complainant alleged that the said situation had been observed for a prolonged period. ET confirmed with the Resident Site Staff that reinforced bar fixing and concreting work (on 17 June 2015 only) were conducted at Portion 2 from 15 June 2015 to 19 June 2015. Total 3 nos. of mobile crane were in operation. On 17 June 2015, one no. of concrete pump truck and two nos. of concrete mixer were in operation.Excavation and Lateral Support was conducted at Portions 3 & 4 from 15 June 2015 to 19 June 2015. Total 4 nos. of excavator, 2 nos. of truck and 2 nos. of crawler crane were in operation. In addition, on 15 June 2015, 17 June 2015 and 19 June 2015, 1 no. of derrick barge was moored near Portions 3 & 4 for transportation of the excavated material away from site. According to the relevant site records under Contract HK/2009/02, from 15 June 2015 to 19 June 2015, reinforced bar fixing and concreting work (on 17 June 2015 only) were conducted at Portion 2 and total 3 nos. of mobile crane, one no. of concrete pump truck (on 17 June 2015 only) and two nos. of concrete mixer (on 17 June 2015 only) were in operation; excavation and lateral support was conducted at Portions 3 & 4 and total 4 nos. of excavator, 2 nos. of truck and 2 nos. of crawler crane were in operation. Based on relevant site record, no hopper barge was moored under Contract HK/2009/02 around the concerned location while 1 no. of derrick barge was moored under Contract HK/2009/02 near Portions 3 & 4 for transportation of the excavated material from Portions 3 & 4 away from site on 15 June 2015,17 June 2015 and 19 June 2015 respectively. Follow-up inspection was conducted during weekly	advised no comment on 20 July 2016 on the interim report submitted and case closed.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					environmental inspection on 25 June 2015, no dark smoke and malodour emission was observed from the PMEs operating on-site. A derrick barge was observed moored near Portions 3 & 4 and excavated material was transferred to the derrick barge by the excavators on land without barge operation and no particular dark smoke and malodour emission was observed. Nevertheless, the Contractor was reminded to conduct regular checking on the condition of the derrick barge and other PMEs deployed on site to ensure only well maintained PMEs are used to avoid potential dark smoke and maldour emission affecting nearby public.	
150723	20 July 2015	EPD Ref.:H05/RS/ 00018040-15 dated 23 July 2015	Ex-Wanchai Ferry Pier near 720 & & 722 Bus stop	Malodour from marine sediment	A public complaint regarding malodour referred by EPD was received by ET on 23 July 2015 (EPD Ref.: H05/RS/00018040-15 dated 23 July 2015). The complainant reported that malodour from marine sediment was scented at ex-Wanchai ferry pier near route 720 & 722 bus stop. (Contract HK/2009/02). ET confirmed with the Resident Site Staff that Rockfill placing works was conducted by one derrick barge at the concerned location (WCR3) under Contract HK/2009/02 on 20 July 2015. No marine sediment was stored or placed on site at the concerned location under Contract HK/2009/02 on 20 July 2015. According to the relevant site records under Contract HK/2009/02, rockfill placing works was conducted by one derrick barge at WCR3 area on 20 July 2015 and no marine sediment was stored or placed on site at the concerned location on the concerned date. Follow-up inspection was conducted during weekly environmental inspection on 29 July 2015. No marine sediment was observed stored or placed at the concerned location while it was noted that a culvert outfall with potential odour concern is located adjacent to the concerned location.	Interim report submitted to EPD on 30 July 2015. EPD advised no comment on 17 August 2015 on the interim report submitted and case closed.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					Nevertheless, the Contractor was reminded to review the handling procedures in case of any future marine sediment handling at the concerned location and to consider the implementation of mitigation measures as appropriate to minimize potential malodour impact to nearby public.	
150904	01 Sept 2015	EPD Ref.: H05/RS/00022241-15 dated 04 September 2015 received by ET on 4 September 2015	East of New WanChai Ferry Pier	Dropping of excavated material from land to sea during laoding of material	A public complaint regarding dropping of excavated material from land to sea referred by EPD was received by ET on 04 September 2015 (EPD Ref.: H05/RS/00022241-15 dated 04 September 2015). The complainant reported that dropping of excavated materials from land to sea during loading of materials by excavator at the construction site to work boat. (Contract HK/2009/02) ET confirmed with the Resident Site Staff that transferring of C&D materials from land to hopper barge by excavator at seaside along CWB Tunnel Portions 3 and 4 was undertaken by Contract HK/2009/02 on 01 September 2015. Mitigation measure including providing tarpaulin sheet to cover the gap between seawall and the hopper barge to prevent dropping of material to the sea was implemented by the Contractor. According to the relevant site records under Contract HK/2009/02, transferring of C&D materials from land to hopper barge by excavator at seaside along CWB Tunnel Portions 3 and 4 was carried out on 01 September 2015 and mitigation measures including provision of tarpaulin sheet between seawall and the hopper barge was implemented by the Contractor of HK/2009/02 on the concerned date. Follow-up inspection was conducted during weekly environmental inspection on 10 September 2015. Transferring of C&D materials from land to barge by excavator was observed at the concerned location and mitigation measures including provision of tarpaulin sheet between seawall and hopper	Interim report submitted to EPD on 14 September 2015. EPD advised no comment on 5 October 2015 on the interim report submitted and case closed

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					barge and the material transfer works was generally in order. Nevertheless, the Contractor of HK/2009/02 was reminded to maintain the handling procedure for C&D materials transfer from land to hopper barge and regularly inspect the condition of the tarpaulin sheet provided to ensure the nearby water quality are not affected by the loading and unloading of material from land side to hopper barge. The Contractor was reminded to maintain the handling procedure for C&D materials transfer from land to hopper barge and regularly inspect the condition of the tarpaulin sheet provided to ensure the nearby water quality are not affected by the loading and unloading of material from land side to hopper barge.	
150904	02 Sept 2015	EPD Ref.: H04/RS/00022385-15 dated 04 September 2015 received by ET on 04 September 2015	Location outside Fleet Arcade	Construction noise was generated from the construction site of HK/2012/08 at location outside Fleet Arcade during night time on weekdays and daytime during General Holidays. The complainant also concerned construction dust and exhaust emission from derrick barges during transporting C&D material at the site.	A public complaint regarding construction noise and dust and exhaust emission referred by EPD was received by ET on 04 September 2015 (EPD Ref.: H04/RS/00022385-15 dated 04 September 2015). The complainant reported that construction noise was generated from the construction site of HK/2012/08 at location outside Fleet Arcade during night time on weekdays and daytime during General Holidays. The complainant also concerned construction dust and exhaust emission from derrick barges during transporting C&D material at the site. (Contract HK/2012/08) ET confirmed with the Resident Site Staff that from 0800 hrs to 1800 hrs on 30 August 2015, removal of scaffold and timber and installation of bulkhead was undertaken by the Contractor of HK/2012/08 at the concerned location. Total one generator and one circular saw were in operation. From 1900hrs on 30 August 2015 to 0700 on 31 August 2015, no construction works was undertaken by the Contractor of HK/2012/08 at the concerned location.	Interim report submitted to EPD on 14 September 2015. 2nd interim report submitted to EPD on 17 Dec 2015 3rd interim report submitted to EPD on 31 Dec 2015

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					From 1900hrs on 31 August 2015 to 0700hrs on 01 September 2015, no construction works was undertaken by the Contractor of HK/2012/08 at the concerned location. From 1900hrs to 2115 hrs on 01 September 2015, unloading of soil was undertaken by the Contractor of HK/2012/08 at the concerned location. Total one derrick barge was in operation. From 2300hrs on 01 September 2015 to 0700hrs on 02 September 2015, no construction works was undertaken by the Contractor of HK/2012/08 at the concerned location. One derrick barge was deployed for unloading of soil on 02 September 2015 during daytime under Contract HK/2012/08 at the concerned location. Based on the relevant site records, from 0800 hrs to 1800 hrs on 30 August 2015, removal of scaffold and timber and installation of bulkhead was undertaken by the Contractor of HK/2012/08 at the concerned location. Total one generator and one circular saw were in operation and the relevant Construction Noise Permit GW-RS0296-15 for the concerned operation was confirmed in place. From 1900hrs on 30 August 2015 to 0700 on 31 August 2015, no construction works was undertaken by the Contractor of HK/2012/08 at the concerned location and from 1900hrs on 31 August 2015 to 0700hrs on 01 September 2015, no construction works was undertaken by the Contractor of HK/2012/08 at the concerned location. From 1900hrs to 2115 hrs on 01 September 2015, unloading of soil was undertaken by the Contractor of HK/2012/08 at the concerned location. Total one derrick barge was in operation and the Construction Noise Permit GW-RS0296-15 for the concerned operation was confirmed in place.	

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					From 2300hrs on 01 September 2015 to 0700hrs on 02 September 2015, no construction works was undertaken by the Contractor of HK/2012/08 at the concerned location. In view of the above, the construction activities conducted under Contract HK/2012/08 during the concerned period was in compliance with the statutory requirement. In addition, one derrick barge was deployed for unloading of soil on 02 September 2015 during daytime under Contract HK/2012/08 at the concerned location. Follow-up inspection was conducted during weekly environmental inspection on 08 September 2015 and no dark smoke emission was observed from the derrick barge moored outside the concerned location. Nevertheless, the Contractor of HK/2012/08 was reminded to conduct regular checking on the condition of the all derrick barges deployed on site to ensure only well maintained equipment are used to avoid potential dark smoke emission affecting nearby public and the Contractor of HK/2012/08 was reminded to upkeep the site control system for construction works carrying out at restricted hours and night time for Construction Noise Permit compliance. The Contractor was reminded to conduct regular checking on the condition of derrick barges deployed on site to ensure only well maintained equipments are used on site to avoid potential dark smoke emission affecting nearby public. The Contractor of HK/2012/08 was reminded to upkeep the site control system for construction works carrying out at restricted hours and night time for Construction Noise Permit compliance.	
150917	17 Sep 2015	A public complaint regarding water quality referred by EPD was	Central and Wan Chai Reclamation coastline (between LUNG WUI ROAD to LUNG WO ROAD,	Silt from Central and Wan Chai Reclamation was spotted along the coastline (between LUNG WUI ROAD to LUNG WO ROAD, Central & Wan	Based on the site records confirmed by RSS, removal of seawall blocks by derrick barge was undertaken by Contract HK/2012/08 at Central Reclamation Phase III works area while mitigation measures including provision of silt curtain implemented by the Contractor of HK/2012/08 during the	Interim investigation report submitted to EPD on 25

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
		received by ET on 17 September 2015	Central & Wan Chai, Hong Kong)	Chai, Hong Kong)	seawall block removal works. According to relevant record, muddy dispersion at HKCEC2W (area opposite to Lung King Street) was observed by the Environmental Team on 14 September 2015 afternoon. The muddy patch was observed dispersing outside the outer layer silt curtain deployed by the Contractor of HK/2012/08 towards the Central Reclamation Phase III area while the outer layer silt curtain was observed partially opened. In view of the above observations, the Contractor was advised to rectify any environmental deficiencies such that adequate protection such as silt curtain shall be provided for exposed soil slope to mitigate for potential runoff related water quality impact to the surrounding waters; outer layer silt curtain deployed shall be entirely closed during works to safeguard the surrounding water quality. Any opening for marine vessel shall be closed promptly after passage and localized silt curtain deployed on site shall be properly maintained to avoid any gap or opening to effectively safeguard the nearby waters.	September 2015. EPD advised no comment on 14 October 2015 and case closed.
151015	11 Oct 2015	A public complaint regarding direct discharge of muddy effluent referred by RSS was received by ET on 14 October 2015	Seafront opposite to Watson Road adjacent to Eastern Breakwater	Pink fluid was observed discharged into marine waters at seafront opposite to Watson Road adjacent to the Eastern Breakwater on 11 October 2015.	Based on the site records confirmed by RSS, no construction activity near the seaside between Eastern Breakwater and the Dumping Jetty was undertaken by Contract HY/2009/19 while at site area away from the seawall, construction of EVB substructure, EVB and APS structure was undertaken on 11 October 2015. In addition, no works involving the use of paint was carried out at the concerned site area (Site Portion between Eastern Breakwater and the Dumping Jetty) and along the alignment of the Culvert T1 under Contract HY/2009/19 and no temporary storage of paint was located at the concerned site area and along the alignment of the Culvert T1 under HY/2009/19 on 11 October 2015. Follow-up inspection was conducted during weekly environmental inspection on 14 October 2015. No construction works involving the use of paint was observed undertaken at the concerned location while a few number of small containers of paint was observed placed around the concerned location and the paint containers were sealed and no sign of leakage was observed. The few containers were further checked and was found not matching the pink fluid observed on the complaint date. On the other hand, a culvert discharge outfall was found located within the concerned area where the pink fluid was observed. Based on the above, no direct information indicating the pink	HyD will consolidate all input from relevant parties to form a reply to ICC.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					fluid was originated from the worksarea under HY/2009/19 was considered available. Nevertheless, the Contractor was reminded that paints stored on site shall be properly labelled and stored in sealed container at weather proof location to avoid potential spillage.	
151028	26 Oct 2015	A public complaint regarding construction noise impact referred by EPD was received by ET on 28 October 2015 (EPD Ref:H05/RS/00027330-15 Dated 28 October 2015)	Construction Site next to ex-Wan Chai Ferry Pier	Operation of grab dredger at construction site near the ex-Wan Chai Ferry Pier from around 0100 to 0400 hours on 26 October 2015 caused noise nuisance.	According to the relevant site records under Contract HK/2009/02, from 01:00hrs to 04:00hrs on 26 October 2015, rock filling was conducted under Contractor of HK/2009/02 at WCR3 Area. Total one grab dredger was in operation. Mitigation measures including provision of steel sheeting screening to the power generation part of the grab dredger was implemented by the Contractor of HK/2009/02 and the relevant Construction Noise Permit GW-RS1121-15 for the concerned construction works was in place. The construction activity conducted under Contract HK/2009/02 during the concerned period was in compliance with the statutory requirement. Nevertheless, the Contractor was reminded to upkeep the site control system for construction works carrying out at restricted hours and night time for Construction Noise Permit compliance in view of the nearby public concern.	The interim report would be submitted to EPD on 05 November 2015 and EPD advised no comment on 16 November 2016 and case closed.
151116	13 November 2015	A public complaint regarding water quality referred by EPD was received by ET on 16 November 2015 (EPD Ref: H05/RS/00029126-15)	Construction Site at HKCEC and seafront outside Lung Wo Road	Muddy water was discharged from the construction site at HKCEC and dispersed to seafront outside Lung Wo Road on 13 November 2015 afternoon. The complainant also alleged that the deployment of the silt curtain did not follow the design requirement under the environmental permit that the curtain should be hanged to seabed level	Based on the site records, rock mound trimming works was conducted under Contract HK/2012/08 at HKECE2 area on 13 November 2015 and mitigation measures including provision of localized silt curtain around the works area was implemented by the Contractor. Follow-up inspection was conducted during weekly environmental inspection on 17 November 2015, both outer layer silt curtain and localized layer of silt curtain around the active works area were observed deployed while the localized silt curtain deployed around the marine works area was observed partially opened for marine access. Despite no muddy dispersion was generated around the localized silt curtain enclosed area, the Contractor was advised to promptly improve the condition of the silt curtain to ensure the effectiveness of the mitigation measure deployed and to ensure the silt curtain is closed after marine vessel movement. Based on further review on the current construction stage at HKECE2, the dredging works and trench filling works were completed and filling works were conducted behind seawall or temporarily seawall in form of rockbund, the outer layer of silt curtain currently serves as the additional mitigation measure to	The interim investigation report would be submitted to EPD on 1 December 2015 and record of diving inspection conducted on 27 November 2016 was forwarded to EPD on 4 Dec 2016. EPD advised no further comment on 14 Dec 2015 and case closed.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					the required silt curtain deployment for safeguarding the water quality in the area. To clarify for the current silt curtain arrangement, the Contractor was advised to submit an updated silt curtain deployment plan with respect to the latest silt curtain arrangement for the current construction stage. In addition, contaminated discharge at Culvert L originating from upstream locations was intermittently observed based on previous site records. Nevertheless, in view of the public concern, the Contractor was reminded to conduct regular checking on the condition and maintenance for the silt curtain deployed on site to ensure the effectiveness of the mitigation measure. A joint meeting for the complaint was held amongst the EPD, WDII RSS team, the ET and the Contractor of HK/2012/08 on 24 November 2015 and a joint silt curtain diver inspection check amongst EPD, ET, IEC, WDII RSS and the Contractor was conducted on 27 November 2015 to confirm the silt curtain condition and the silt curtain deployed at the HKCEC2 water channel was found generally in order.	
160413 (HK201208)	13 April 2016	A public complaint referred by EPD was received by ET on 13 April 2016 (EPD Ref.: H05/RS/00008367-16 dated 13 April 2016)	Outside the Hong Kong Academy for Performing Arts	Muddy water discharge from construction site	A public complaint regarding muddy water discharge referred by EPD was received by ET on 13 April 2016 (EPD Ref.: H05/RS/00008367-16 dated 13 April 2016). The complainant reported that muddy water was discharged from the construction work of Contract HK/2012/08 to the sea outside the Hong Kong Academy for Performing Arts on 13 April 2016 morning. ET confirmed with the Resident Site Staff that internal transport of soil to the hopper barge for storage via landing barge was conducted by Contractor of HK/2012/08 during 0800 hours to 1000 hours on 13 April 2016 at the sea outside the concerned location and 3 nos. of dump trucks were deployed for the operation. Protection measure including provision of sandbag bunding along the side of the landing barge was implemented by the Contractor of HK/2012/08. According to the relevant site records provided by RSS, internal transport of soil to the hopper barge for storage via landing barge was conducted by Contractor of HK/2012/08 during 0800 hours to 1000 hours on 13	Interim investigation report was submitted to the EPD on 21 April 2016. EPD advised no further comment on 6 June 2016 on the interim report submitted and case closed.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					April 2016 at the sea outside the concerned location and 3 nos. of dump trucks were deployed for the operation. Protection measure including provision of sandbag bunding along the side of the landing barge was implemented by the Contractor of HK/2012/08. In addition, amber rainstorm warning signal was hoisted from 0630 hours to 1200 hours on 13 April 2016 and during the above time period, muddy water was observed from the upstream of culvert L outside the HK/2012/08 site. Follow up inspection was conducted on 19 April 2016, protection measures including provision of sandbag bunding along the side of the landing barge was implemented and no mud or soil deposition was observed along the seawall and no discharge point was located within the temporary water channel connecting the Culvert L outfall location to the Victoria Harbour. In addition, piling works was observed at the north side of Zone A1 on 19 April 2016 and construction effluent collection from piling work via sedimentation tank to wastewater treatment facility was implemented and steel barrier was installed around the piling works area to mitigate against potential surface runoff related impact. Nevertheless, in view of the public concern, the Contractor was reminded to maintain adequate perimeter embankment protection along the seawall boundary and maintain proper construction effluent collection system to avoid potential runoff related impact to nearby waters.	
160706	30 June 2016	A public complaint referred by EPD was received by ET on 06 July	Construction area near Royal Hong Kong Yacht Club	Derrick barge moored near Royal Hong Kong Yacht Club emitted dark smoke since mid of June 2016.	A public complaint referred by EPD was received by ET on 06 July 2016 (Case Ref.: H05/RS/0016226-16). The complainant reported that a derrick barge in green colour under Contract HY/2009/15 moored near Royal Hong Kong Yacht Club emitted dark smoke since mid of June 2016.	Interim report was submitted to EPD on 14 July 2016.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
		2016 (Case Ref:. H05/RS/00016 226-16),			ET confirmed with Resident Site Staff that the concerned green derrick barge was identified as Yue Fat 206 (YF 206) and the concerned green derrick barge was operated within the Ex-PCWA area for excavation works intermittently across the period from 15 June 2016 to 30 June 2016. The concerned green derrick barge YF206 within Ex-PCWA area was no longer deployed under Contract HY/2009/15 after 02 July 2016. Follow-up inspection was conducted on 11 July 2016, the concerned derrick barge YF206 was not deployed at the concerned location and no dark smoke was observed from other derrick barge operating on-site. Nevertheless, in view of the public concern, the Contractor of HY/2009/15 was reminded to conduct regular checking and maintenance of all derrick barges deployed on site to ensure only well maintained equipment is used to avoid potential dark smoke emission affect nearby surroundings.	EPD advised no further comment on 20 September 2016 on the interim report submitted and case closed.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
160825	25 August 2016	A public complaint referred by EPD was received by ET on 25 August 2016 (Case Ref.: H08/RS/00012592-16)	East of Temporary Reclamation Zone TS3, Causeway Bay Typhoon Shelter	Muddy water was observed at Causeway Bay Typhoon Shelter	A public complaint referred by EPD was received on 25 August 2016 (Case Ref.: H08/RS/00012592-16). The complainant reported that muddy water was observed at Causeway Bay Typhoon Shelter. ET confirmed with the Resident Site Staff that no marine construction activities were undertaken at the concerned location at East of Temporary Reclamation Zone TS3 within Causeway Bay Typhoon Shelther from 14:00hrs to 17:00hrs on 25 May 2016. Site control measures including the following were implemented by the Contractor of HY/2010/08 around the concerned location. Site control measures including i) Wastewater treatment facilities (AquaSed) were installed at TS3 for treatment of wastewater generated during construction activities. Sampling of effluent from AquaSed was conducted by the Contractor of HY/2010/08 and all results complied with the requirements in the Discharge Licence. Visual inspection and pH measurement of effluent were conducted daily by Environmental Supervisors and all results passed. ii) Brick/ earth/ sandbag bunds were installed alongside the site perimeter of TS3 to prevent muddy runoff into the sea. iii) Piping with idled ends were removed to prevent accidental discharge of untreated wastewater. iv) Diver inspection for silt curtains and/ or impermeable barriers was conducted on an ad-hoc basis. vii) Temporary cut slopes were shotcreted or properly covered with tarpaulin sheets. viii) Regular inspections were conducted by the RSS and Contractor's environmental representatives on regular basis on the conditions of mitigation measures implemented on site. Based on the complainant photo information, the exposed soil slope at Temporary Reclamation Zone TS3 were observed protected by covering and enclosed by double layer of impermeable barrier/ silt curtain and no contaminated discharge was identified. In addition, based on information from Hong Kong Observatory, the tidal condition on 25 May 2016 afternoon was found to	The Interim investigation report was submitted to EPD on 2 September 2016. EPD advised no further comment on 31 October 2016 on the interim report submitted and case closed.

Complaint Log No.	Date of Complaint	Received From and Received By	Location of Complainant	Nature of Complaint	Outcome	Status
					be ebb-tide while non construction works marine vessel movements around the identified muddy plume within Causeway Bay Typhoon Shelter was observed in the complainant photo information. Based on review on relevant records, no contaminated surface runoff and no contaminated discharge was identified at the concerned location during the environmental site inspection conducted on 25 May 2016. Follow up inspection was conducted on 31 August 2016 and seawall construction and filing works at the Temporary Reclamation Zone TS3 was observed completed. No contaminated discharge and no contaminated surface runoff was found. Nevertheless, the contractor of HY/2010/08 was reminded to maintain appropriate bunding at seawall boundary for protection against potential surface runoff related impact. Also, the Contractor of HY/2010/08 was reminded to maintain proper site drainage for effluent collection and treatment system to ensure the compliance with relevant discharge license.	

Appendix 10.1

Construction Programme of Individual Contracts

Activity ID	Activity Name	Original Duration	Start	Finish
Total		306d	15-May-17 A	16-Mar-18
3 Months Rolling Programme - 2017-09 (DWP-08, 1st submission)		306d	15-May-17 A	16-Mar-18
Removal of TS3 South side		306d	15-May-17 A	16-Mar-18
South West (Zone A)		78d	17-May-17 A	16-Sep-17 A
1	South West (Zone A)	66d	17-May-17 A	16-Sep-17 A
2	Remove filled material to -4.35mPD (13,000m3)	13d	17-May-17 A	01-Jun-17 A
3	Remove seawall blocks at Bay Z4- 22 - 22 (400 nos.)	6d	19-May-17 A	26-May-17 A
5	Core D-wall cut holes at Panel W2D5 to W2D8	6d	27-Jun-17 A	02-Jul-17 A
6	Remove filled material to -7.0mPD up to Panel W2D8	7d	03-Jul-17 A	14-Jul-17 A
4	Remove seawall blocks at Bay 23 & 24 (120 nos.)	2d	11-Aug-17 A	15-Aug-17 A
54	Remove Outfall Q Sheet Piles Wall	14d	18-Aug-17 A	16-Sep-17 A
Portion SW1		15d	12-Jun-17 A	14-Jul-17 A
7	Vertical cut at Panel BWD14 to SA7 (25 nos./1.5m)	8d	12-Jun-17 A	30-Jun-17 A
8	Horizontal cut at Panel BWD14 to SA7 (34 nos./1.5m)	9d	29-Jun-17 A	14-Jul-17 A
Portion SW2		18d	19-Jul-17 A	04-Aug-17 A
59	Vertical cut at Panel W2D1 to W2D9 (24 nos./1.5m)	9d	19-Jul-17 A	27-Jul-17 A
69	Horizontal cut at Panel W2D1 to W2D9 (32 nos./1.5m)	9d	28-Jul-17 A	04-Aug-17 A
South West (Zone B)		34d	22-Jun-17 A	25-Jul-17 A
10	Excavation to Expose Existing Landing Steps	6d	22-Jun-17 A	27-Jun-17 A
11	Excavation to Expose Existing Intake of Windsor House	5d	28-Jun-17 A	02-Jul-17 A
12	Clear Up for Inspection of Existing Intake of Windsor House	7d	03-Jul-17 A	09-Jul-17 A
13	Remove Filled Material to -4.35mPD (11,000m3)	18d	03-Jul-17 A	20-Jul-17 A
14	Remove Filled Material to -7.0mPD	6d	18-Jul-17 A	23-Jul-17 A
15	Core D-wall Cut Holes at Panel W2D10 to W4D3 (82 nos.)	2d	24-Jul-17 A	25-Jul-17 A
South East (Zone C)		126d	24-May-17 A	24-Oct-17
16	South East (Zone C)	105d	24-May-17 A	24-Oct-17
17	Break concrete slab	2d	24-May-17 A	25-May-17 A
18	Remove filled material to -4.35mPD (7,000m3)	8d	26-May-17 A	12-Jun-17 A
19	Remove seawall blocks at Bay 2 - Bay 4 (454 nos.)	7d	13-Jun-17 A	19-Jun-17 A
Portion SE1		35d	24-Jun-17 A	28-Jul-17 A
20	Remove filled material to -7.0mPD	7d	24-Jun-17 A	30-Jun-17 A
21	Clean and Install String for Vertical Cutting	1d	01-Jul-17 A	01-Jul-17 A
22	Vertical cut at Panel W2D32 to W2D35 (18 nos./1.5m)	7d	02-Jul-17 A	14-Jul-17 A
23	Horizontal cut at Panel W2D32 to W2D35 (24 nos./1.5m)	12d	17-Jul-17 A	28-Jul-17 A
Portion SE2		34d	15-Aug-17 A	06-Sep-17 A
82	Vertical cut at Panel W2D24 to W2D31 (18 nos./1.5m)	10d	15-Aug-17 A	26-Aug-17 A
83	Horizontal cut at Panel W2D24 to W2D31 (24 nos./1.5m)	8d	03-Sep-17 A	06-Sep-17 A
SR8 (E&W)		75d	11-Aug-17 A	24-Oct-17
A61270	Vertical cut at W4D7 to W4D11 + W3D5 to W3D7 (24 nos.)	12d	11-Aug-17 A	09-Oct-17
A61230	Vertical cut at W3D2 to W3D4 (9 nos.)	3d	28-Aug-17 A	05-Sep-17 A
A61250	Horizontal cut at W3D2 to W3D4 (12 nos.)	3d	06-Sep-17 A	09-Sep-17 A
A61280	Horizontal cut at W4D7 to W4D11 + W3D5 to W3D7 (32 nos.)	15d	10-Oct-17	24-Oct-17
SR8 (West Side)		306d	15-May-17 A	16-Mar-18



Activity ID	Activity Name	Original Duration	Start	Finish
C6 Stitching Structure Construction		188d	15-May-17 A	09-Nov-17
120	SR8 - C6 Stitching Structure Construction	209d	15-May-17 A	09-Nov-17
Roof slab construction		66d	15-May-17 A	19-Jul-17 A
C61000	ICE design cert submission for Engineer's consent	9d	15-May-17 A	24-May-17 A
C61010	Erection of falsework (Revised due to rainstorm and typhoon)	22d	26-May-17 A	20-Jun-17 A
C61020	Formwork erection and diaphragm wall C.J. and couplers preparation (coring if required)	5d	21-Jun-17 A	25-Jun-17 A
C61030	Steel fixing for roof slab	8d	26-Jun-17 A	05-Jul-17 A
C61040	Final cleaning and concreting	1d	06-Jul-17 A	06-Jul-17 A
C61050	Falsework and formwork removal	6d	17-Jul-17 A	19-Jul-17 A
OHVD construction		24d	20-Jul-17 A	11-Aug-17 A
C61100	Falsework modification	8d	20-Jul-17 A	27-Jul-17 A
C61110	OHVD slab construction (box out will be formed in R.J. location)	8d	28-Jul-17 A	04-Aug-17 A
C61120	OHVD kicker wall construction	8d	05-Aug-17 A	11-Aug-17 A
Base slab construction		24d	28-Aug-17 A	17-Sep-17 A
200	Base slab construction	27d	28-Aug-17 A	17-Sep-17 A
C61060	Shuffle the vehicular access	5d	28-Aug-17 A	01-Sep-17 A
C61070	Construction of 1st portion base slab	7d	02-Sep-17 A	08-Sep-17 A
C61080	Shuffle the vehicular access	5d	09-Sep-17 A	13-Sep-17 A
C61090	Construction of 2nd portion base slab	7d	14-Sep-17 A	17-Sep-17 A
SR8 - Rotational Joint Installation		150d	22-Jun-17 A	09-Nov-17
Omega Seal Installation		15d	02-Oct-17	16-Oct-17
A62190	1st part	5d	02-Oct-17	06-Oct-17
A62200	2nd part	5d	07-Oct-17	11-Oct-17
A62210	3rd part	5d	12-Oct-17	16-Oct-17
Proprietory Cantilever Teeth Expansion Joint Installation for Base Slab		150d	22-Jun-17 A	09-Nov-17
A62220	Procurement (5 months)	150d	22-Jun-17 A	26-Oct-17
A62230	Installation	14d	27-Oct-17	09-Nov-17
Phase I - Reinstatement of Section of Sloping Seawall above Zone C Bay C6		236d	24-Jul-17 A	16-Mar-18
Backfill Rubble Mount, Inststallation of Granite Stone Facing by Land Team		91d	24-Jul-17 A	22-Oct-17
Section of Sloping Seawall above Bay C6 Reinstatement		91d	24-Jul-17 A	22-Oct-17
A61050	Dismantle Reprop Wall Partially (Above Slope Sea Wall)	5d	24-Jul-17 A	07-Oct-17
A61040	Backfilling of Rubble Mound (Grade 200 Rock)	7d	27-Sep-17 A	28-Sep-17 A
A61060	Cast Kerbing Concrete	3d	08-Oct-17	10-Oct-17
A61070	Make good rubble mound and shotcreting	5d	11-Oct-17	15-Oct-17
A61080	Installation of Granite Stone Facing	7d	16-Oct-17	22-Oct-17
Removal of Remaining Pipe Pile Wall, Sheet Pile Wall & D-wall by Marine Team		145d	22-Oct-17	16-Mar-18
260	Removal of Remaining Pipe Pile Wall, Sheet Pile Wall & D-wall	145d	22-Oct-17	16-Mar-18
A61100	Cut pipe pile wall at A1 - A14 (After A61090 & 25A)	15d	09-Dec-17	23-Dec-17
A61110	Under water cut sheet pile wall (5 nos.)	6d	24-Dec-17	29-Dec-17
A61130	Remove filled material to -4.35mPD (6,000m3)	10d	30-Dec-17	08-Jan-18
A61140	Remove seawall blocks at Bay 1 & 2 (356nos.)	8d	09-Jan-18	16-Jan-18
A61150	Remove filled material below cut off level 1m	5d	17-Jan-18	21-Jan-18
A61200	Vertical cut at Panel W4D12, 15, 16 &17 (12nos./1.5m)	4d	22-Jan-18	25-Jan-18
A61210	Horizontal cut at W4D12, 15, 16 & 17 (16 nos./1.5m)	5d	26-Jan-18	30-Jan-18



Activity ID	Activity Name	Original Duration	Start	Finish
A61160	Vertical cut at W3D8 to W3D10 (9 nos.)	3d	26-Jan-18	28-Jan-18
A61170	Horizontal cut at W3D8 to W3D10 (12 nos.)	9d	31-Jan-18	08-Feb-18
Phase II Seawall Reinstatement		38d	30-Nov-17	07-Jan-18
36	Phase II Seawall Reinstatement	31d	30-Nov-17	07-Jan-18
Along existing vertical seawall		12d	30-Nov-17	12-Dec-17
37	Along existing vertical seawall	10d	30-Nov-17	12-Dec-17
38	Vertical cut at Panel W4D13 to 14 (8 nos./1.5m)	8d	01-Dec-17	08-Dec-17
39	Horizontal cut at W4D13 to 14 (8 nos./1.5m)	4d	09-Dec-17	12-Dec-17
Reinstatement of Vertical Seawall		26d	13-Dec-17	07-Jan-18
40	Reinstatement of Vertical Seawall	21d	13-Dec-17	07-Jan-18
41	Drill hole and install dowel bar at existing vertical seawall	7d	13-Dec-17	19-Dec-17
42	Erect steel plate for external formwork of seawall (diver works)	7d	20-Dec-17	26-Dec-17
43	Pour tremie concrete for reinstatement of existing seawall (diver works)	2d	27-Dec-17	28-Dec-17
44	Remove steel formworks (diver works)	2d	29-Dec-17	30-Dec-17
45	Reinstatement grantic facing stone at vertical seawall	4d	31-Dec-17	03-Jan-18
46	Erect formwork for seawall coping	2d	04-Jan-18	05-Jan-18
47	Pour concrete for seawall coping	1d	06-Jan-18	06-Jan-18
48	Remove formwork at seawall coping	1d	07-Jan-18	07-Jan-18
TTA Revert Traffic Back to Original Alignment		177d	11-Jul-17 A	03-Jan-18
East Bound TTA - IEC East Bound, Victoria Park Road & footpath along Sea Side		175d	11-Jul-17 A	01-Jan-18
Stage 1 - IEC (East Bound)		89d	11-Jul-17 A	07-Oct-17
Reinstatemtment Existing Structure		89d	11-Jul-17 A	07-Oct-17
A10790	Reinstatement of Type 2 Wing Wall (20m) and Type 3 Parapet (10m)	21d	11-Jul-17 A	08-Sep-17 A
A10800	Install metal parapet on parapet wall (30m)	6d	02-Oct-17	07-Oct-17
Stage 2 - Victoria Park Road		69d	01-Sep-17 A	19-Nov-17
A10930	Break flexible pavement and concrete slab above EB traffic deck	2d	01-Sep-17 A	06-Sep-17 A
A10900	Remove flexible pavement and then break temp light weight concrete ramp (60m)	14d	08-Sep-17 A	28-Oct-17
A10910	Construct parapet wall Type R3 (15m) and Type R2 (25m) on extg bridge	23d	09-Sep-17 A	21-Oct-17
A10940	Dismantle traffic deck (360m2) and cut king posts (4 nos.)	5d	15-Sep-17 A	20-Sep-17 A
A10970	Backfill Type B Material up to 2m below F.F.L(Ave.2.6m High, 13 Layer@0.2m each layer)	6d	21-Sep-17 A	23-Sep-17 A
A10950	Break two concrete footings for temp traffic deck	6d	26-Sep-17 A	01-Oct-17 A
A10960	Break pipe piles (28 nos.) and cut sheet pile (60 piece)	14d	26-Sep-17 A	09-Oct-17
A10980	Backfill General Fill Material up to Formation Level (Ave. 1.5m High, 5 Layer@ 0.3m each Layer)	9d	28-Sep-17 A	11-Oct-17
A10990	Construct 450/300 stormwater pipe (20m/35m) with 2 Manholes and 1 gully	8d	12-Oct-17	19-Oct-17
A11000	Remove the temp uPVC divided pipe (45m) and two Manholes	3d	20-Oct-17	22-Oct-17
A10920	Install metal parapet on parapet wall (40m)	6d	22-Oct-17	27-Oct-17
A11010	Reinstate the road kerb along VPR (100m)	5d	23-Oct-17	27-Oct-17
A11020	Well compact formation level and subbase for SRT	8d	28-Oct-17	04-Nov-17
A11030	Lay flexible road pavement (RB, BC)	3d	05-Nov-17	07-Nov-17
A11040	Expose and Install Manhole Covers	2d	08-Nov-17	09-Nov-17
A11050	Lay flexible road pavement (WC)	2d	10-Nov-17	11-Nov-17
A11060	Lay road marking and erect permanent traffic signs	2d	12-Nov-17	13-Nov-17
A11070	Implement next TTM stage 3 (VPR footpath, EB)	1d	19-Nov-17	19-Nov-17
Stage 3 - Reinstatement of Footpath along Sea Side		43d	20-Nov-17	01-Jan-18



Activity ID	Activity Name	Original Duration	Start	Finish
Phase 1		38d	20-Nov-17	27-Dec-17
A11240	Temporary Pedestrian Diversion	4d	20-Nov-17	23-Nov-17
A11250	Break flexible pavement and concrete slab above EB traffic deck (Partially)	3d	24-Nov-17	26-Nov-17
A11310	Temporay Relocate telecom ducts	7d	24-Nov-17	30-Nov-17
A11260	Dismantle traffic deck (Partially) and Cut king posts	5d	27-Nov-17	01-Dec-17
A11270	Break two concrete footings	7d	02-Dec-17	08-Dec-17
A11280	Cut pipe piles and sheet pile	10d	02-Dec-17	11-Dec-17
A11290	Backfill Type B Material up to 2m below F.F.L (Compaction by proof rolling method of 0.2m each layer)	6d	12-Dec-17	17-Dec-17
A11300	Backfill General Fill Material up to Formation Level (Avg. 1.5m height, by SRT method of 0.3m each layer, 5 layers)	10d	18-Dec-17	27-Dec-17
Phase 2 - Sloping Seawall Reinstatement		32d	01-Dec-17	01-Jan-18
A11320	Backfill and make good rubble mound profile	7d	01-Dec-17	07-Dec-17
A11330	Install hand pack rubble	6d	08-Dec-17	13-Dec-17
A11340	Erect formwork for toe berm	3d	14-Dec-17	16-Dec-17
A11350	Concreting for toe berm	2d	17-Dec-17	18-Dec-17
A11360	Trim the rubble mound profile	4d	19-Dec-17	22-Dec-17
A11370	Shotcreting on the rubble mound	2d	23-Dec-17	24-Dec-17
A11380	Erect formwork for intermediate berms	7d	25-Dec-17	31-Dec-17
A11390	Concreting for intermediate berms	1d	01-Jan-18	01-Jan-18
West Bound - IEC West Bound & Tsing fung Street		150d	07-Aug-17 A	03-Jan-18
Stage 2 - Tsing Fung Street		119d	07-Aug-17 A	03-Dec-17
A11140	Remove flexible pavement and then break temp light weight concrete ramp (60m)	10d	07-Aug-17 A	09-Oct-17
A11150	Construct parapet wall Type R2 (18m) and Type R1 (42m) on existing bridge	42d	11-Sep-17 A	20-Nov-17
A11090	Dismantle traffic deck (300m2) and cut king posts (4 nos.)	5d	20-Sep-17 A	26-Sep-17 A
A11100	Backfill Type B Material up to 2m below F.F.L (Ave. 2.6m High, 13 Layer@ 0.2m each Layer)	6d	27-Sep-17 A	28-Sep-17 A
A11110	Backfill General Fill Material up to Formation Level (Ave. 1.5m High, 5 Layer@ 0.3m each Layer)	15d	29-Sep-17 A	04-Oct-17
A11120	Break pipe piles (28 nos.) and cut sheet pile (60 piece)	10d	29-Sep-17 A	30-Sep-17 A
A11130	Break two concrete footings for temp traffic deck	6d	01-Oct-17 A	06-Oct-17
A11170	Relay new 400 diameter PE pipe under slow lane of TFS by HKCG (4+21)	25d	07-Oct-17	31-Oct-17
A11180	Lay cross road duct for permanent lighting	3d	01-Nov-17	03-Nov-17
A11190	Reinstate the Road Kerb along TFS (100m)	6d	04-Nov-17	09-Nov-17
A11200	Well compact formation level and subbase for SRT	8d	10-Nov-17	17-Nov-17
A11210	Lay flexible road pavement (RB, BC, WC)	7d	18-Nov-17	24-Nov-17
A11160	Install metal parapet on parapet wall (60m)	6d	21-Nov-17	26-Nov-17
A11220	Lay road marking and erect permanent traffic signs	2d	25-Nov-17	26-Nov-17
A11230	Final cleaning for implement next TTM stage 3 (Victoria Park, WB)	1d	03-Dec-17	03-Dec-17
Stage 3A - Removal of Temporary Traffic Deck on Diverted Tsing Fung Street & Reinstatement Works		31d	04-Dec-17	03-Jan-18
A11690	Break flexible pavement and concrete slab above traffic deck	3d	04-Dec-17	06-Dec-17
A11700	Dismantle traffic deck and Cut king posts	5d	07-Dec-17	11-Dec-17
A11710	Break two concrete footings	7d	12-Dec-17	18-Dec-17
A11720	Cut pipe piles and sheet pile	7d	12-Dec-17	18-Dec-17
A11730	Backfill Type B Material up to 2m below F.F.L (Compaction by proof rolling method of 0.2m each layer)	6d	19-Dec-17	24-Dec-17
A11740	Backfill General Fill Material up to Formation Level (Avg. 1.5m height, by SRT method of 0.3m each layer, 5 layers)	10d	25-Dec-17	03-Jan-18



中國建築工程(香港)有限公司
CHINA STATE CONSTRUCTION ENGRG. (HONG KONG) LTD.

Actual Work
Remaining Work
Critical Remaining Work
Milestone

Contract No. HY/2010/08: Central - Wanchai Bypass Tunnel +(Slip Road 8 Section) - 3 Months Rolling Progamme

Date	Revision	Checked	Approved
02-Oct-17 08...	DWP-08 (1) - 3 Months Rolling	TL	TL

中國建築-利達聯營
CHINA STATE - LEADER JOINT VENTURE

CEDD Contract No. HK/2012/08
Wan Chai Development Phase II
Central - Wan Chai Bypass at Wan Chai West

Activity ID	Activity Name	Remaining Dur	Early Start	Early Finish
HK/2012/08 Revised Works Programme Rev.11.1(DD 30 Jun 2017)				
Dredging and Reclamation				
Marine Work Construction				
Zone D				
Seawall Construction - Zone D				
Seawall 10 & 11				
MAR20630	Zone D - Seawall 10 & 11: Install remaining seawall block	15	14-Oct-17	28-Oct-17
MAR20650	Zone D - Seawall 10 & 11: Backfill Type A	16	29-Oct-17	13-Nov-17
MAR20670	Zone D - Seawall 10 & 11: Lay geotextile and filter	19	14-Nov-17	02-Dec-17
Works for Section Completion				
Construction				
CWB Tunnel & Slip Road Structures and Facilities				
CWB D - Slip Road 1 - Trough / Retaining Wall				
CWB D - Slip Road 1 - Trough/Retaining Wall Structure				
SIIA13742	Sec II A - CWB SR1 Trough & RW: Trough Structure bay 1a & 1b: Construct box-out area & backfilling	25	07-Oct-17	31-Oct-17
Section III A - Road A2, A4 & A5				
Roadwork & Utilities - Section 1 (L1806 - L1801)				
SIIIA10301	Sec III A - roadwork and utlities section 1 carriageway - Drainage works (L1806 -L1801)	20	01-Nov-17	23-Nov-17
SIIIA10300	Sec III A - roadwork and utlities section 1 carriageway - Drainage works (L2202-L2201)	21	03-Oct-17	26-Oct-17
SIIIA10340	Sec III A - roadwork and utlities section 1 carriageway - utilities: HEC along carriageway	21	23-Dec-17	19-Jan-18
SIIIA10302	Sec III A - roadwork and utlities section 1 carriageway - gully pipe	18	24-Nov-17	14-Dec-17
SIIIA10320	Sec III A - roadwork and utlities section 1 carriageway - watermain	7	15-Dec-17	22-Dec-17
SIIIA10290	Sec III A - roadwork and utlities section 1 carriageway - Implementation of TTA Stage 5	1	30-Sep-17	30-Sep-17
Roadwork & Utilities - Section 2 (L1810 - L1806)				
SIIIA12530	Sec III A - roadwork and utlities section 2 carriageway - watermain	10	14-Nov-17	24-Nov-17
SIIIA12550	Sec III A - roadwork and utlities section 2 carriageway - Utilities: HEC along carriageway & Crossroad duct (HEC &	28	25-Nov-17	29-Dec-17
SIIIA12510	Sec III A - roadwork and utlities section 2 carriageway - gully pipe (L1801 - L1806)	25	14-Oct-17	13-Nov-17
Roadwork & Utilities - Section 3 (L1808 - L1102)				
SIIIA12810	Sec III A - roadwork and utlities section 3 carriageway - black top	7	23-Dec-17	03-Jan-18
SIIIA12770	Sec III A - roadwork and utlities section 3 carriageway - utilities: HEC & crossroad duct (PCCW & HGC)	41	13-Oct-17	30-Nov-17
SIIIA12790	Sec III A - roadwork and utlities section 3 carriageway - road kerb & formation	19	01-Dec-17	22-Dec-17
Roadwork & Utilities - Section 4 (L1406 - L1401)				
SIIIA13010	Sec III A - roadwork and utlities section 4 carriageway - road formation: crossroad duct (HEC), road kerb & formation	24	20-Oct-17	17-Nov-17
SIIIA13030	Sec III A - roadwork and utlities section 4 carriageway - black top	7	18-Nov-17	25-Nov-17
SIIIA12990	Sec III A - roadwork and utlities section 4 carriageway - watermain	10	09-Oct-17	19-Oct-17



Data Date:
30-Jun-17

- Current Milestone
- Actual Work
- Critical Remaining Work
- Remaining Work
- Remaining Level of Effort

3 Months Rolling Programme for Non-CRIII Area (Oct 2017 - Dec 2017)

(Ref. to Works Programme Rev.11.1)

Date	Revision	Checked	Approved
03-Oct-17	11.1		

Activity ID	Activity Name	Remaining Dur	Early Start	Early Finish
	Roadwork & Utilities - Section 6 (L1102 - L1411)			
SIIIA13389	Sec III A - roadwork and utlities section 6 carriageway - Backfilling above tunnel roof slab	5	05-Oct-17	10-Oct-17
SIIIA13399	Sec III A - roadwork and utlities section 6 carriageway - gully pipe (L1101 -L1102)	8	21-Oct-17	31-Oct-17
SIIIA13470	Sec III A - roadwork and utlities section 6 carriageway - black top	7	22-Nov-17	29-Nov-17
SIIIA13450	Sec III A - roadwork and utlities section 6 carriageway - road kerb & formation	18	01-Nov-17	21-Nov-17
SIIIA13395	Sec III A - roadwork and utlities section 6 carriageway - Drainage works (L1101-L1102)	9	11-Oct-17	20-Oct-17
	Section V - Remaining At-Grade Road; Remove 2nd Stage ITA			
	Roadwork & Utilities			
	Section 1 (L1504 - L1900)			
SV12460	Sec V - Roadwork & Utilities Section 1 Carriageway - Utilities (TCSS crossroad duct)	21	11-Oct-17	04-Nov-17
SV12570	Sec V - Roadwork & Utilities Section 1 footpath - utilities:TCSS	30	22-Nov-17	28-Dec-17
SV12540	Sec V - Roadwork & Utilities Section 1 footpath - Watermain	14	06-Nov-17	21-Nov-17
SV12580	Sec V - Roadwork & Utilities Section 1 footpath - paving block	30	29-Dec-17	02-Feb-18
SV12490	Sec V - Roadwork & Utilities Section 1 Carriageway - Road kerb & formation	24	06-Nov-17	02-Dec-17
SV12520	Sec V - Roadwork & Utilities Section 1 Carriageway - Black top	20	04-Dec-17	28-Dec-17
	Section 2 (L1510 - L1504)			
SV12604	Sec V - Roadwork & Utilities Section 2 Carriageway : formation for access diversion	6	30-Sep-17	07-Oct-17
SV12606	Sec V - Roadwork & Utilities Section 2 Carriageway: Divert access cross Zone B	0	09-Oct-17	
SV12630	Sec V - Roadwork & Utilities Section 2 Carriageway - Drainage Works L1406A - L1406B	21	15-Nov-17	08-Dec-17
SV12690	Sec V - Roadwork & Utilities Section 2 footpath - Drainage Works (L2104 - L2105)	25	09-Dec-17	10-Jan-18
SV12610	Sec V - Roadwork & Utilities Section 2 Carriageway - Drainage Works L1507-L1504)	31	09-Oct-17	14-Nov-17
SV12665	Sec V - Roadwork & Utilities Section 2 Carriageway - Gully pipe (L1507-L1504, L1406A)	25	09-Dec-17	10-Jan-18
	Section 3 (Culvert L - L1510)			
SIV12844	Sec V - Roadwork & Utilities Section 3 footpath - U channel	21	15-Nov-17	08-Dec-17
SIV12840	Sec V - Roadwork & Utilities footpath - Drainage works (Culvert L - L2105)	25	16-Oct-17	14-Nov-17
SIV12860	Sec V - Roadwork & Utilities Section 3 footpath - Utilities: TCSS, HGC, PCCW)	39	09-Dec-17	26-Jan-18
SIV12820	Sec V - Roadwork & Utilities Section 3 Carriageway - Black top	20	19-Dec-17	13-Jan-18
SIV12810	Sec V - Roadwork & Utilities Section 3 Carriageway - Gully pipe (Culvert L - L1611)	30	16-Oct-17	20-Nov-17
SIV12850	Sec V - Roadwork & Utilities footpath - Watermain	21	15-Nov-17	08-Dec-17
SIV12815	Sec V - Roadwork & Utilities Section 3 Carriageway - Road kerb & formation	24	21-Nov-17	18-Dec-17
	Section IV - Slip Road 3			
	Roadwork & Utilities			
	Section 1 (L16608 - L1601)			
SIV11762	Sec IV - Roadwork & Utilities at SR3 Section 1 Carriageway - Drainage Works (L2103-L2101)	21	03-Nov-17	27-Nov-17
SIV11780	Sec IV - Roadwork & Utilities at SR3 Section 1 Carriageway - Watermain	18	29-Dec-17	19-Jan-18
SIV11764	Sec IV - Roadwork & Utilities at SR3 Section 1 Carriageway - Gully pipe (L1607-L1601, L2004-L2005)	25	28-Nov-17	28-Dec-17
SIV11860	Sec IV - Roadwork & Utilities at SR3 Section 1 footpath - Drainage Works: future connection pipes	7	29-Dec-17	06-Jan-18
	Section 2 (L2301 - L2103)			
SIV11941	Sec IV - Roadwork & Utilities at SR3 Section 2 Carriageway - Drainage Works (L608-L1609)	30	19-Oct-17	23-Nov-17
SIV11960	Sec IV - Roadwork & Utilities at SR3 Section 2 Carriageway - Watermain	10	20-Dec-17	03-Jan-18



Activity ID	Activity Name	Remaining Dur	Early Start	Early Finish
SIV11942	Sec IV - Roadwork & Utilities at SR3 Section 2 Carriageway - Gully pipe (L2301-L2013, L1608-L1609)	22	24-Nov-17	19-Dec-17
SIV12010	Sec IV - Roadwork & Utilities at SR3 Section 2 Carriageway - Road kerb & formation	24	20-Dec-17	19-Jan-18
Section 3 (M/H1.6 - L2301)				
SIV12103	Sec IV - Roadwork & Utilities at SR3 Section 3 Carriageway - M1.7-M1.6: ELS	10	18-Oct-17	30-Oct-17
SIV12104	Sec IV - Roadwork & Utilities at SR3 Section 3 Carriageway - M1.7-M1.6: Construct manhole & pipes	36	31-Oct-17	11-Dec-17
SIV12105	Sec IV - Roadwork & Utilities at SR3 Section 3 Carriageway - M1.7-M1.6: backfilling & divert EVA	12	12-Dec-17	27-Dec-17
SIV12120	Sec IV - Roadwork & Utilities at SR3 Section 3 Carriageway - Drainage Works (M1.6-C1.1-C1.2): Construct MH and pipes	28	28-Dec-17	30-Jan-18
SIV12100	Sec IV - Roadwork & Utilities at SR3 Section 3 Carriageway - Drainage Works (M/H1.7 - L2301)	31	19-Oct-17	24-Nov-17
SIV12140	Sec IV - Roadwork & Utilities at SR3 Section 3 Carriageway - Gully pipe (M/H 1.7 - L2301)	30	25-Nov-17	02-Jan-18
SIV12180	Sec IV - Roadwork & Utilities at SR3 Section 3 footpath - U channel	14	24-Oct-17	09-Nov-17
SIV12220	Sec IV - Roadwork & Utilities at SR3 Section 3 footpath - Paving block	45	10-Nov-17	04-Jan-18
Section VII - Remainder Works				
Road & Drainage Works (Culvert L - M/H1.7, Adjacent to SR3)				
SVII11600	Sec IV - Roadwork & Utilities at SR3 Section 4 Carriageway - Drainage Works (Culvert L -MH1.7)	40	12-Dec-17	30-Jan-18
Retaining Wall RW5 Construction				
SVII10860	Sec VII - Retaining wall RW5 - curing, removal formwork	15	07-Nov-17	23-Nov-17
SVII10680	Sec VII - Retaining wall RW5 (bay 2) - construct base slab and wall	20	13-Oct-17	06-Nov-17
SVII10820	Sec VII - Retaining wall RW5 (bay 4) - construct base slab and wall	20	13-Oct-17	06-Nov-17
Landing Steps Construction				
Landing Steps BSW13				
SVII10920	Sec VII - Landing steps (BSW13) - install s.s. handrail / tactile / sign board / bollard	25	20-Nov-17	18-Dec-17
SVII10900	Sec VII - Landing steps (BSW13) - install vertical fender / step fender	15	02-Nov-17	18-Nov-17
Landing Steps BSW4				
SVII10980	Sec VII - Landing steps (BSW4) - install vertical fender / step fender	15	19-Dec-17	08-Jan-18
Promenade Seawall Parapet Construction				
SVII13220	Sec VII - Zone D: Construct seawall block mass concrete coping	40	04-Dec-17	22-Jan-18
SVII13140	Sec VII - Zone A1, A2 & B: Construct seawall parapet	35	02-Nov-17	12-Dec-17
Promenade Footpath and EVA Construction				
Section 2				
SVII12610	Sec VII - section 2 footpath - drainage works (L2203 - L2202A) & U-channel	49	14-Nov-17	12-Jan-18
Section 3				
SVII12850	Sec VII - section 3 footpath - watermain	18	13-Oct-17	03-Nov-17
SVII12870	Sec VII - section 3 footpath - utilities (HEC, TCSS, HGC, PCCW)	44	04-Nov-17	27-Dec-17
SVII12875	Sec VII - 3 footpath - drainage works :U chanel	14	28-Dec-17	13-Jan-18
Section 4				
SVII13054	Sec VII - section 4 footpath - U channel	14	09-Dec-17	27-Dec-17
SVII13052	Sec VII - section 4 footpath - watermain	21	15-Nov-17	08-Dec-17
SVII13050	Sec VII - section 4 footpath - drainage works (L2203 -L2203A)	21	20-Oct-17	14-Nov-17
SVII13055	Sec VII - section 4 footpath - utilities: HEC, TCSS, HEC & PCCW	56	09-Dec-17	15-Feb-18
Section 5				



Activity ID	Activity Name	Remaining Dur	Early Start	Early Finish
SVII13275	Sec VII - section 5 footpath - watermain	21	26-Oct-17	20-Nov-17
SVII13310	Sec VII - section 5 footpath - utilities: HEC, TCSS, HGC, PCCW	59	21-Nov-17	31-Jan-18
Section 6				
SVII13514	Sec VII - section 6 footpath - U channel	20	14-Dec-17	09-Jan-18
SVII13510	Sec VII - section 6 footpath - watermain	20	21-Nov-17	13-Dec-17
SVII13490	Sec VII - section 6 footpath - drainage works(Culvert L - L2204)	25	21-Oct-17	20-Nov-17
SVII13530	Sec VII - section 6 footpath - utilities: HEC, TCSS, HGC, PCCW	62	14-Dec-17	02-Mar-18